

11

Government of Jammu and Kashmir
OFFICE OF THE EXECUTIVE ENGINEER, JSD (PHE) DIVISION, PULWAMA

No. PHEP/ 4262-65
Dated. 12-11-2020

Mr. Bashir Ahmad Nalk,
Contractor,
S/o. Ghulam Ahmad Nalk,
R/o. Zalgam, Pulwama
Regd. No. 24/AA/SE/HYDL/SHOPIAN/2004-05

sub :- Retrofitting of Water Supply Scheme Akhal Putrigam by way of providing, laying and fitting of GI pipes, including repairs to chowkidar quarter, RCC jacketing to SSF Plant including laying of new filter media, face lifting of structures and construction of intake channel/chamber including installation of 64 No. FHTCs for Akhal Putrigam (JJM).

Ref:- E-NIT S.No. 41/PHEP of 2020-21, job No. (1), Circulated vide this office No. PHEP/3169-83 Dated: 29-09-2020.

Advertised Amount of work: ₹ 84,22,000.00
Alloted Amount of work: ₹ 91,86,000.00
Rupees Ninety One Lakh(s) Eighty Six Thousand Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following negotiated rates as accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No. or Qty.	Unit	RATE	
				Figures	Words
1.00	Earth work excavation by manual means in trenches for foundation drains, pipes cables etc (not exceeding 1.5 mtr in width and for shaft wells and the cesspits and the like not exceeding 10sqm on plan) depth up to 1.5 mtr including disposal of excavated soil up to 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil.	2405.25	Cum	320.00	Rupees Three Hundred Twenty Only
2.00	Dismantling of G.I. pipes (external work) including excavation and refilling, trenches, after taking out the pipes, manually by mechanical means including stacking of pipes within 50 mtrs.				
2.10	Above 40mm dia bore	600.00	Mtr	80.00	Rupees Eighty Only
3.00	Providing, supplying, fixing of 12mm thick flanged joints to 150mm dia G.I. pipe incld cost of nuts, bolts, washers, cutting of threading incld making good for jointing with welding all carriage to and fro complete				
3.10	100mm dia	57.00	Joint	1000.00	Rupees One Thousand Only
3.20	80mm dia	41.00	Joint	800.00	Rupees Eight Hundred Only
4.00	P/F of flanged pipe with flanged joints 12mm thck of flanges including cost of nuts, bolts, washers, cutting of threads and making good for jointing including testing and commissioning all carriages complete.				
4.10	100mm dia GI pipe with flanges	2000.00	Mtr	1100.00	Rupees One Thousand One Hundred Only
4.20	80mm dia GI pipe with flanges	1000.00	Mtr	800.00	Rupees Eight Hundred Only
5.00	Providing, laying and fitting of GI pipes including all carriages head load upto site of work complete.				
5.10	50mm dia	1530.00	Mtr	450.00	Rupees Four Hundred Fifty Only
5.20	40mm dia	2000.00	Mtr	365.00	Rupees Three Hundred Sixty Five Only
5.30	25mm dia	2000.00	Mtr	235.00	Rupees Two Hundred Thirty Five Only
5.40	20mm dia	3000.00	Mtr	175.00	Rupees One Hundred Seventy Five Only
5.50	15mm dia	850.00	Mtr	135.00	Rupees One Hundred Thirty Five Only
6.00	Making connections of G.I. distribution branch with G.I. mains of following sizes by providing and fitting tee including cutting and threading the pipe etc complete				
6.10	25mm to 40mm nominal bore	60.00	No	550.00	Rupees Five Hundred Fifty Only
6.20	above 40mm nominal bore	20.00	No	1220.00	Rupees One Thousand Two Hundred Twenty Only
7.00	Filling available excavated earth (excld Rock) in trenches, plinth sides of the foundation etc layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering lead up to 50 Mtr and lift up to 1.50 Mtr.	2073.00	Cum	160.00	Rupees One Hundred Sixty Only
8.00	P/F of different dias of sluice valve/ gate valve/ bend/ coils with fittings of standard make (Kirtoskar or VAGE) including all carriages upto site of work complete including tail pieces				
8.10	100mm di sluice valve	5.00	No	12000.00	Rupees Twelve Thousand Only
9.00	Providing and laying of stone soling hand packed horizontally excluding cost of stones	78.25	Cum	411.00	Rupees Four Hundred Forty One Only
10.00	Providing and laying in position cement concrete of specified grade excl. cost of centering & shuttering, all work up to plinth level 1:4:8 (1 cement:4 fine sand:8 grade stone agg.)	9.45	Cum	4200.00	Rupees Four Thousand Two Hundred Only
11.00	Providing and laying in position specified grade of reinforced cement concrete excl. the cost of centering, shuttering, finishing, & Reinforcement. All work up to plinth level (1:1:5.3)Raft (1 cement:1 1/2 course sand:3 grade stone agg. 20 mm nominal size)	27.74	Cum	7000.00	Rupees Seven Thousand Only
12.00	Providing and laying in position reinforced cement concrete of specified grade excl. cost of centering & shuttering finishing and reinforcement all work upto plinth level 1:2:4 (1 cement:2 coarse sand:4 graded stone agg. 40 mm nominal size)	22.58	Cum	5500.00	Rupees Five Thousand Five Hundred Only
13.00	Centering and shuttering including strutting, propping etc and removal of form for-				
13.10	Foundation, footings, bases of columns etc. for mass concrete.	103.50	Sqm	2000.00	Rupees Two Hundred Forty Only
13.20	Wall (any thickness) including attached plasters, buttresses, piers and string courses etc.	203.45	Sqm	2000.00	Rupees Four Hundred Thirty Only

Sub :- **Retrofitting of Water Supply Scheme Akhal Putrigam by way of providing, laying and fitting of GI pipes, including repairs to chowkidar quarter, RCC jacketing to SSF Plant including laying of new filter media, face lifting of structures and construction of intake channel/chamber including installation of 64 No. FHTCs for Akhal Putrigam (JJM).**

13.40	Suspended floors, roofs, landings, balconies and access platform	27.00	Sqm	502.00	Rupees Five Hundred Two Only
14.00	Edges of slab and breaks in floors and walls under 20cms wide	23.00	Sqm	220.00	Rupees Two Hundred Twenty Only
15.00	Reinforcement for RCC works including Straightening cutting, bending, placing in position & binding all complete (Thermo Mechanically treated bars)	4958.00	Kg	90.00	Rupees Ninety Only
16.00	12 mm thick cement plaster in 1:4 mix floating coat of neat cement (1 cement, 4 fine sand)	509.30	Sqm	220.00	Rupees Two Hundred Twenty Only
17.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering all work up to plinth level in (1:3:6) Mix (1 cement:3course sand: 6 grade stone agg. 40 mm nominal size)	30.78	Cum	4900.00	Rupees Four Thousand Nine Hundred Only
17.10	P/F of panelled 300x40mm nominal size	27.43	Mtr	750.00	Rupees Seven Hundred Fifty Only
18.00	P/F of wshbasin, indian type WC flush tank with all necessary fittings such as angle valve, CP fittings, P-Trap, door trap whichever is required for such type of fittings all leads lifts complete job.	1.00	Job	20000.00	Rupees Twenty Thousand Only
19.00	Structural steel work welded in built up section, trusses and framed work including cutting, hoisting, fixing in position and applying a primer coat of approved steel primer all complete	650.00	Kg	100.00	Rupees One Hundred Only
20.00	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15cm deep and disposal of rubbish lead upto 50 mtr and lift upto 1.5 mtr all kinds of soil	938.29	Sqm	15.00	Rupees Fifteen Only
21.00	Reinforced cement concrete work in walls (any thickness) including attached plasters, buttresses, plinth & string courses, fillets, columns, pillars, piers abutments, post & struts etc up to floor five level excluding cost of centering, shuttering, finishing & reinforcement 1:1.5:3 (1 cement:1½ course sand 3 graded crushed stone 20 mm nominal size)	20.42	Cum	8200.00	Rupees Eight Thousand Two Hundred Only
22.00	Clearance of silt from PST, FP, clear water sump, SR intake filter media etc including disposal from the premises all leads and lifts complete job.	2448.00	Cft	10.00	Rupees Ten Only
23.00	Providing and supplying of Baramulla slabs from Baramulla including all carriages leads lifts and placing into plant complete job.	208.00	Sft	150.00	Rupees One Hundred Fifty Only
24.00	Providing and supplying of Filter Media slabs from Ganderalbal including all carriages leads lifts and placing into plant complete job.	1796.00	Cft	238.00	Rupees Two Hundred Thirty Eight Only
25.00	Re-laying of filter media into filtration plant in layers after washing and cleaning complete job.	1468.00	Cft	3.50	Rupees Three And Paise Fifty Only
26.00	Demolishing cement concrete manually/ by mechanically means including disposal of material within 50 mtrs lead (1:3:6 richer mix)	23.43	Cum	1090.00	Rupees One Thousand Ninety Only
27.00	Extra for providing and mixing of water proofing material in cement conc work in doses by weight of cement as per manufacturer specification	185.00	Kg	59.00	Rupees Fifty Nine Only
28.00	P/F of Sign board of 8'x4' of size to be fitted with angle iron frame with cement concrete complete job.	1.00	No	1500.00	Rupees One Thousand Five Hundred Only
29.00	Cement concrete flooring 1:2:4 (1:cement, 2:coarse sand, 4: graded stone agg) finished with a floating coat of neat cement including cement slurry but excluding the cost of nosing of steps etc complete 40mm thick with 20mm nominal size aggregates.	25.08	Sqm	430.00	Rupees Four Hundred Thirty Only
30.00	P/F of MS Bends as required including cost of flanged joints, nuts, bolts, washers welding, cutting, fixing all carriage complete				
30.10	100mm dia	3.00	No	2500.00	Rupees Two Thousand Five Hundred Only
31.00	P/F MS Lid of 2'-6" x 2'-6" with angle iron frame with iron sheets including locking arrangements etc complete job.	2.00	No	4000.00	Rupees Four Thousand Only
32.00	Carriage of different materials from source upto actual site of work by mechanical transport including cost of loading, unloading and stacking complete				
32.10	Stone Soling (avg lead 20 Kms)	26.25	Cum	390.00	Rupees Three Hundred Ninety Only
32.20	Sand + Bajri (avg lead 45 Kms)	192.85	Cum	490.00	Rupees Four Hundred Ninety Only
32.30	Cement + steel (avg lead 45 Kms)	47.42	M.T.	470.00	Rupees Four Hundred Seventy Only
33.00	Maintenance cost for a period of three years which includes 12 months DLP	1.00	complete job	120000.00	Rupees One Lakh(s) Twenty Thousand Only

Terms and Conditions:-

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However, non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (60) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- Earnest Money of ₹ 169000/- deposited by your vide CDR No. 381126 dated 15-10-2020 has been retained in the divisional office as security deposit.
- 5- All other terms and conditions will remain same as per the original agreement form No. 25-double, Form FC - 33 and detailed E-NIT.

Checked
Head Draftsman

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for information
- 2- District Development Commissioner Pulwama for information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Pulwama for information and necessary action.
- 4- File Concerned.

Tech. Officer

Executive Engineer
USD (PHE) Div. Pulwama