

Government of Jammu and Kashmir
OFFICE OF THE EXECUTIVE ENGINEER, JSD (PHE) DIVISION, PULWAMA

No. PHEP/.....786-89.....
 Dated.....08-05-2021.....

13

Shir Ahmad Naik,
 Col. Factor,
 S/o. Ghulam Ahmad Naik,
 R/o Zagigam, Pulwama
 Regd. No. 24/AAY/SE/HYDL/SHOPIAN/2004-05

Sub :- Retrofitting of Water Supply Scheme Arihal Sharepthri by way of Providing, Laying & fitting of pipes including installation of 136 No. FHTC's for village Arihal Sharepathri including maintenance for a period of three years which includes DLP of 12 months. (underJMM)

Ref:- E-NIT S.No. 98/PHEP/Fresh of 2020-21, job No. (1), Circulated vide this office No. PHEP/5596-5607 Dated:- 13-01-2021 and S.E. Hyd. Circle, Shopian's No. SE/Hyd/329-30 dtd. 17-04-2021

Advertised Amount of work: ₹ 59,66,000.00

Alloted Amount of work: ₹ 62,91,000.00

Rupees Sixty Two Lakh(s) Ninety One Thousand Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following negotiated rates as accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No.or Qty.	Unit	Estd. Rate	RATE	
					Figures	Words
1.00	Earthwork in excavation by manual means in trenches for foundation, drains, pipes cables etc (not exceeding 1.5mtrs in width and for shafts, wells cesspits and the like not exceeding 10 Sqm on plain depth upto 1.5 mtrs, including disposal of excavated earth upto 1mtr from cutting edge disposal earth to be levelled and neatly dressed in:					
1.01	All kinds of soil	2230.00	Cum	240.45	320.00	Rupees Three Hundred Twenty Only
2.00	Dismantling of G.I pipes (external work) incld excavation and refilling trenches after taking out the pipes manually/mechanically means including stacking of pipes with 50 mtrs lead.					
2.01	above 40mm nominal bore	500.00	Mtr	59.30	99.00	Rupees Ninety Nine Only
3.00	Providing, supplying, fixing of 12mm thick flanged joints to G.I. pipes incld cost of pipes, nuts, bolts, washers, cutting of threading incld making good for jointing with welding all carriage to and fro complete					
3.01	100mm dia	400.00	Mtr	RQC	1100.00	Rupees One Thousand One Hundred Only
3.02	80mm dia	200.00	Mtr	RQC	800.00	Rupees Eight Hundred Only
4.00	Providing, laying and fitting of G.I. pipes including cost of pipes but excluding cost of earth work:					
4.01	65mm dia	1200.00	Mtr	RQC	628.00	Rupees Six Hundred Twenty Eight Only
4.02	50mm dia	2000.00	Mtr	RQC	477.00	Rupees Four Hundred Seventy Seven Only
4.03	40mm dia	3550.00	Mtr	RQC	370.00	Rupees Three Hundred Seventy Only
4.04	25mm dia	2950.00	Mtr	RQC	249.00	Rupees Two Hundred Forty Nine Only
4.05	20mm dia	3100.00	Mtr	RQC	170.00	Rupees One Hundred Seventy Only
5.00	Providing, laying and supply 15mm dia GI pipes including cost of earth work excavations for trenches, back filling of earth, L/F of pipes and all carriages complete.	1800.00	Mtr	RQC	140.00	Rupees One Hundred Forty Only



Retrofitting of Water Supply Scheme Arihal Sharepathri by way of Providing, Laying & fitting of pipes including installation of 136 No. FHTC's for village Arihal Sharepathri including maintenance for a period of three years which includes DLP of 12 months. (underJJM)

6.01	Making connections of G.I. distribution branch with G.I. mains of following sizes by providing and fixing tee including cutting and threading the pipe etc complete.					
6.01	25mm to 40mm nominal bore	30.00	No	403.65	650.00	Rupees Six Hundred Fifty Only
6.02	Above 40mm nominal bore	6.00	No	1022.15	1250.00	Rupees One Thousand Two Hundred Fifty Only
7.00	Filling available excavated earth (excl'd Rock) in trenches, plinth sides of foundation etc layers not exceeding in 20 cm in depth, consolidating each deposited layer by ramming and watering lead up to 50 Mtr and lift up to 1.50 Mtr.	2007.00	Cum	102.20	155.00	Rupees One Hundred Fifty Five Only
8.00	Providing flanges to dismantling GI pipes excluding cost of pipes and earth work but including cost of nuts, bolts, washers, welding, cutting etc complete job.					
8.10	100mm dia flanged joints	16.00	Joint	RQC	1150.00	Rupees One Thousand One Hundred Fifty Only
8.20	80mm dia flanged joints	32.00	Joint	RQC	1000.00	Rupees One Thousand Only
8.30	L/F of 50mm dia dismantling GI pipes	200.00	Mtr	27.75	40.00	Rupees Forty Only

Terms and Conditions:-


- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However the non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (60) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- Earnest Money of ₹ 74680/-, ₹76980/- deposited by your vide CDR No. 2953160, 2953162 dated 09-06-2020 have been retained in the divisional office as security deposit.
- 5- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked

Head Draftsman

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for information
- 2- District Development Commissioner Pulwama for information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Pulwama for information and necessary action.
- 4- File Concerned.


Executive Engineer,
ISD (PHE) Div. Pulwama