

**OFFICE OF THE EXECUTIVE ENGINEER PHE, JAL SHAKTI DIVISION BIJBEHARA**

Name:- GH. NABI MIR  
S/o GH. AHMAD  
R/O:- ASTAN BAZAR BIJBEHARA  
Regd. No:- 08-AA-DSE/1986-87  
GST NO. 01ALOPM2430P1ZZ

No. PHD/703-03  
Dt. 29-5-2021

Advt. Cost Rs 26.52 Lacs  
Alloted. Cost Rs 26.52 Lacs

Time for completion: \_\_\_ days

Head of Account = JJM

Subject:- Retrofitting of WSS. Viday for providing 100 percent FHTC by way of Providing, laying and fitting of mains, Sub mains and distribution pipe network system under JJM and 03 years maintenance incl 01 year DLP

Reference:- Your Tender in response to this office e-NIT No. 42 of 2020-21 issued vide No. 8711-35 dt: 24-03-2021

For & on behalf of Lt. Governor of Union territory of J&K, contract for above noted work is here by fixed with you on the following quoted rates :-

S.No		Qty.	Unit	Alloted Rates	Amount
1.00	Dismantling D.I. pipes manually/ by mechanical means breaking lead caulked joints, melting of lead and making into blocks including stacking of pipes and lead at site within 50 meter lead as per direction of Engineer-in-charge. Including excavation and refilling trenches after taking out the pipes. Upto 150 mm diameter. 125/100 mm dia DI pipe	1200.00	Mtr	282.75	339300.00
2.00	Earth work in excavation by manual means in trenches foundations drains pipes cables etc (Not exceeding 1.5m in width) and for shafts wells cesspits and not exceeding 10 sqm on plan depth upto 1.5m incld disposal of excavated earth upto 1m from cutting edge disposed earth to be levelled and neatly dressed in All kinds of soil	823.88	Cum	436.00	359211.68
3.00	Laying in position centrifugally cast (spun) iron S&S or flanged pipes (excluding cost of pipe)	185.24	QU	245.55	45485.68
4.00	Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes or Ductile Iron Pipes including testing of joints and including the cost of rubber gasket.				0
4.10	125mm dia DI pipe	154.00	Joint	117.20	18048.80
4.20	100mm dia DI pipe	63.00	Joint	89.70	5651.10
5.00	Providing and fixing G.I. pipes complete with G.I. fittings excluding trenching and refilling etc. (external work) Light Class				0.00
5.10	100mm dia GI pipe	750.00	Mtr	1135.35	851512.50
5.20	65mm dia GI pipe	250.00	Mtr	628.45	157112.50
5.30	50mm dia GI pipe	200.00	Mtr	477.50	95500.00
5.40	40mm dia GI pipe	650.00	Mtr	386.50	251225.00
5.50	25mm dia GI pipe	700.00	Mtr	249.00	174300.00
5.60	20mm dia GI pipe	900.00	Mtr	182.65	164385.00
5.70	15mm dia GI pipe	200.00	Mtr	144.40	28880.00
6.00	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	741.48	Cum	198.70	147332.08
7.00	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete 25 to 40 mm nominal bore	22.00	No	666.25	14657.50
<b>Total</b>					<b>2652601.84</b>
<b>Rs: 26.52 LACS</b>					

*[Signature]*  
Head Draftsman

*[Signature]*  
Executive Engineer  
PHE, Division Bijbehara

**Terms & Conditions**

- The cost of work should in no case exceed beyond Rs 26.52 Lacs (Rupees Twenty Six lac Fifty Two Thousand only)
- The work shall have to be completed within a period of \_\_\_ days from the date of issuance of this allotment order failing which penalty upto 10% of the total value of contract shall be imposed upon you.
- You have to attend the Divisional Office along with your enlistment card for drawl of agreement within three days from the date of issuance of this allotment order. However non drawl of agreement will not prevent the contract from being
- All other terms & conditions will remain same as laid down in the original NIT / PWD form No 25- double. And FC-33

**Copy to the :-**

- Superintending Engineer Hyd. Circle Anantnag for favour of information
- Assistant Executive Engineer PHE Sub -Division Kokernag for information & necessary action. He will ensure the completion of work within the stipulated time period and strictly in accordance with approved proposals, besides the amount of work does not exceed beyond the provision of allotment in any case for which he shall be personally responsible.