

OFFICE OF THE EXECUTIVE ENGINEER JAL SHAKTI (PHE) DIVISION QAZIGUND

Allotment Order No: PHQ/CC/ 07 of 2022-23 dated 29/08/2022
 No: PHQ/ 4024-26 DATE: 29/08/2022
 NAME: M/S Imtiyaz Ahmad Mir S/o Ab. Salam Mir R/o Nowdora Kralmad (Class BEE)
 email: imtiyaz999@gmail.com Cell No. 7066868852
 REGD. NO: SE/R&B/SB-B-780 of 2017-18 ACCOUNT NO: 0055010100000356
 GSTN: 01BRWPM7261F1ZK PAN: BRWPM7261F
 Name of Schemes:- Laying and fitting of pipes incl. P/F of pipe fittings, Construction of 2 No. collection chamber and 2 No. sluice chamber WSS Hallan
 Administrative Approval No. 207-DB of 2022 Dated 27-08-2022
 Technical Sanction NO. PHEQ/DB/61 of 2022 Dated 3/9/2022
 Alloted Cost:- **Rs.1393489/=** Thirteen lacs Ninety Three thousands four hundred eighty nine only
 Completion Time 90 Days

References: 1. Your tender received in response to E-NIT No.13 of 2022-23 ISSUED UNDER NO: PHQ/1384-99 Dated 13/06/2022 (Tender ID: 2022_PHE_173949_33) 2. This office Corrigendum No. PHQ/CC/1620-28 dated:- 24-06-2022 and Corrigendum 2nd No: PHQ/CC/ 1680-88 Dated:- 27-06-2022

For & on behalf of Lt. Governor of J&K, contract for above noted work is here by fixed with you on your quoted percentage rates, terms & conditions and are reproduced hereunder:-

Sl. No.	Description of Work / Item(s)	Qty	Unit	Rate	Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms till upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed				
1.01	All kinds of soil	144.800	Cum	436.000	63132.80
1.02	Ordinary Rock	36.200	Cum	967.850	35036.17
2	Laying and fitting of G.I. pipes (all classes) complete, including cost of pipe specials but excluding cost of pipes and Earth work				0.00
2.01	50 mm dia. nominal bore	100.000	Mtr	40.800	4080.00
2.02	40 mm dia. nominal bore	400.000	Mtr	40.800	16320.00
2.03	25 mm dia. nominal bore	800.000	Mtr	30.650	24520.00
2.04	20 mm dia. nominal bore	1000.000	Mtr	20.250	20250.00
2.05	15mm dia. nominal bore	1500.000	Mtr	20.250	30375.00
3	Providing and instalation of house hold connection touconnected household including providing and fixing of necessary pipes specials, earthwork at connection and whatever necessary complete	36.000	No	1500.000	54000.00
4	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete				0.00
4.01	15 to 40 mm nominal bore	10.000	No	666.250	6662.50
5	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/by mechanical means including stacking of pipes within 50 meters lead as per direction of Engineer-in-charge				0.00
6	Upto 40mm nominal bore	700.000	Mtr	99.750	69825.00
7	Above 40mm nominal bore	100.000	Mtr	110.650	11065.00
8	Rethreading of damaged end of pipes including all carriage.				0.00
8.01	Upto 40mm nominal bore	65.000	No	75.000	4875.00
9	Earth work in bulk excavation by manual means over areas (exceeding 30 sqm in depth, 1.5 mtr in width as well as 10 sqm on plan), including disposal of excavated earth upto 50 mtr and till upto 1.50 mtr, as directed by Engineer-in- Charge				0.00

9.01	All kinds of soil	181.000	Cum	539.350	875.2
10	Extra for every additional lift of 1.5 m or part thereof in excavation/banking excavated or stacked material. All kinds of soil	81.120	cum	81.650	662.2
11	Providing and laying of dry stone soling tightly hand picked on horizontal levels	6.020	Cum	616.400	3710.73
12	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with 1:4:8 (1 cement 4 coarse sand 8 graded stone aggregate 40 mm nominal size)	4.240	Cum	4861.835	20614.15
13	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level. 1:1½:3 (1 cement : 1½ coarse sand 3 graded stone aggregate 20 mm nominal size)	8.140	Cum	7800.760	63496.19
14	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement of mix 1:1½:3 (1 cement 1½ coarse sand 3 graded stone aggregate 20 mm nominal size)	18.560	Cum	9408.135	174614.99
15	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto five level including curing but excluding the cost of centring shuttering, finishing and reinforcement with 1:1½:3 (1 cement 1½ coarse sand 3 graded stone aggregate 20 mm nominal size)	2.440	cum	9849.345	24032.40
16	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above/upto plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more	2710.000	kg	91.138	246983.98
17	Providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification. (1 kg of water proofing material in 50 kg of cement)	186.000	kg	57.900	10769.40
18	Centering and shuttering including strutting propping etc. and removal of form for				0.00
18	Foundations, footings, bases of columns etc. for mass concrete	13.860	sqm	262.300	3640.72
18	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	193.680	sqm	573.650	111143.27

18	Suspended floors, roofs, landings, balconies and access platforms	16.400	sqm	635.800	10423.84
18	Edges of slabs and breaks in floors and walls Under 20 cm wide	36.000	sqm	242.300	8722.80
19	12mm Cement plaster finished with a floating coat of neat cement of mix 1 : 3 (1 cement 3 fine sand)	88.400	sqm	343.750	30387.50
20	12mm Cement plaster of mix 1 : 6 (1 cement 6 coarse sand)	17.280	sqm	241.750	4177.44
21	Structural steel work in built up sections, trusses and framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete Welded	440.000	kg	106.778	46982.32
22	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	162.900	Cum	198.700	32368.23
23	Carnage of material from source to dumping site at road by mechanical transport.				0.00
23	Cement and steel for avg. lead of 40 Km	15.620	MT	534.279	8345.44
23	Sand for avg. lead of 70 Km	16.380	Cum	899.093	14727.14
23	20mm Aggregate for avg. lead of 55 Km	26.220	Cum	750.053	19666.39
23	40mm Aggregate for avg. lead of 55 Km	3.820	Cum	815.247	3114.24
23.1	Stone soiling For avg lead of 15 km	6.020	Cum	401.833	2419.03
24	Carnage of Pipes material From divisional store to dumping site of work by mechanical transport For an average lead of 35 Km including loading, unloading and stacking complete				0.00
24	80/65/50/40/25/20 mm dia GI pipe	3.940	MT	401.799	1583.09
25	Carnage of material by manual labour from dumping site upto actual site of work. For an avg. distance of 2000 mtr				0.00
25	Cement	12.920	MT	817.190	10558.09
25	steel	2.700	MT	1755.498	4739.84
25	Sand and 20mm agg.	42.600	Cum	1992.237	84869.30
25	40mm Aggregate	3.820	Cum	2153.674	8227.03
25.1	Stone soiling	6.020	Cum	2343.677	14108.94
26	Carnage of pipes material from dumping site upto actual site of work by manual labour for avg. lead of 500mtrs				0.00
26	80/65/50/40/25/20 mm dia GI pipe	5.700	MT	355.695	2027.46
G TOTAL					1410843.26

Quoted Percentage rate

1.23% Below

Alloted Cost

1393489.88

Rupees :- Rupees Thirteen lacs Ninety Three thousands four hundred eighty nine only


Head Draftsman


Tech. Officer


Ex. Engineer PHE Div. Doodhmund


Terms & Conditions

1	The cost of work is restricted to Rs. 1393489/- (Rupees Thirteen lacs Ninety Three thousands four hundred eighty nine only)
2	Earnest money deposited by you vide CDR No.3106507 dtd. 23/06/22 Rs.33016/ and No. 3106549 dated:- 07-09-2022 of Rs. 15900/- in JK Bank Lower-Manda is being retained as security deposit and shall be released after as per the general terms and condition of the Contract
3	The allotted works shall be subject to check by the third party monitoring agency (TPIQM) appointed by the Department. The agency shall check the quality of works executed by the agencies, the quality of materials used for construction and the quality of machinery installed in each scheme. The TPIQM's role shall be that of an assistant to the Employer's Representative for the purpose of monitoring and evaluating of the performance of the Contract during the Contract Period
4	Agency must execute the works as per the requirements/specifications detailed in the relevant/applicable IS code/s
5	The rates are including the charges for submission of progress, Geo tagged photographs through the professional person before during and after construction and progress reports in both hard and soft copies
6	The date of start of work shall be reckoned within one week from the date of issue of Contract Allotment whichever is earlier
7	No price escalation will be paid for completion of the work within the stipulated time or extended date of completion due to any reasons whatsoever
8	In case of quantity variation OR required as per the direction of the Engineer in charge the same has to be executed at site and nothing extra will be paid beyond the overall allotted cost
9	Retention many / Security deposit shall be 10% of the contract value. The security deposit is to be recovered @ of 10% of bill amount from running account bills and shall be released after completion of the work and recommendation from the concerned Engineer in charge
10	Liquidated damages (L.D) In the event of allottee failing, declining, neglecting or delaying the supplies / works or in the event of any damage occurring or being caused by the allottee or in the event of any default or failure by the allottee in complying with any of the terms and conditions of the contract, the Department shall with or without prejudice to any other remedies available to it under any law for the time being enforce in the UT a) Terminate the contract after 15 days' notice, and/or b) Recover the amount of loss caused by damage, failure or default, as may be determined by the department and/or c) Recover the extra cost, if any, involved in allotting contract to other party and/or d) Impose Liquidated damages on account of delay beyond the schedule completion period to the tune of 0.5% of the delayed portion of contract every week but not exceeding 10% value of the contract and/or e) Forfeit the performance security and blacklist the firm.
11	Adequate precautions be taken for the environment and social protection and all safety practices in vogue be strictly adhered to during the execution of work
12	No mobilization advance shall be paid
13	The Agency shall be responsible for the time and proper setting out of all the works and for the correctness of the positions, levels, dimensions and alignment of all parts of the works and for the provision of all necessary instruments, appliances and labour in connection therewith.
14	The Agency shall make his own arrangements for the engagement of all types of the labour, required for the execution of the job. No workman below the age of 18 years shall be employed on the works. Also the bidder shall comply with the provisions of all labour laws and the rules framed there under
15	The Agency shall at his own cost make arrangements for proper storage, especially towards Rain and Snow damages of the equipment/ materials at sites till its erection/completion. For the purpose, the bidder shall, with the approval of the Engineer in charge construct temporary storage accommodation for equipment/ material at site for which land shall be provided by the department near the site of work
16	The Agency shall in connection with the work provide and maintain at his own cost all lights, guards, fencing and watching, when and where necessary or required by the Department for the protection of the work or safety and convenience of the Public etc.

17	The Agency shall in advance communicate with incharge store keeper of Divisional Store for lifting of pipe material etc and shall make adequate measures like availability of transport and labour for easy transportation from store to site against proper receipt / Challan, if required
18	As soon as letter of award is communicated to the firm, the contract shall be complete and binding upon them, the Agency/firm shall also be required to execute an agreement with the competent authority within seven days from the date of issue of letter of award. Failure to execute such an agreement in time shall not however, prevent this contract from being enforced against the firm and the date of delivery of the material/completion of works shall be reckoned from the date of issue of the letter of award.
19	All other terms and conditions as laid down in the detailed NIT/SBD/ PWD Form No 25 double /GFR 2017/Manual for procurement of Works 2019 shall remain in force and binding upon the Agency.
20	Any rules/terms and conditions, if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/guidelines stipulated in the General Finance Rules (GFR 2017) and Manual for procurement of Works 2019 Government of India.
Copy to the :-	
1	Chairman District Jal Jeevan Mission (DDC) Anantnag / Kulgam for information.
2	Superintending Engineer Hydraulic Circle Anantnag for information.
3	Assistant Executive Engineer Jal Shakti (PHE) Sub-Division Qazigund for information & necessary action. He will ensure the execution of work strictly in accordance with approved proposal/guidelines under JJM. The cost of work should not exceed beyond alloted cost for which he shall be personally responsible.
4	File concerned.


Draftsman

Tech. Officer


Ex. Engineer PHE Div. Qazigund