

OFFICE OF THE EXECUTIVE ENGINEER JAL SHAKTI (PHE) DIVISION QAZIGUND

Allotment Order No: PHQ/CC/ 47 of 2022-23 dated 31/08/2022			
No: PHQ/ 2332-34	DATE: 31/08/2022		
NAME: Arif Hussain Thokar R/O. Halsidar Kapran			
email: erthakurer786@gmail.com	Cell No. 9596596279/7006492557		
REGD. NO: SE/HydSpr/BEE/Civil-45 of 2021-22	ACCOUNT NO: 0232010100000963 JK Bank Verinag		
GSTN: 01AZTPT5521BZ1	PAN: AZTPT5521B		
Name of Schemes:-Laying and fitting of pipes incl. P/F of pipe fittings and const. of chain link fencing around structures WSS Reshipora Gawass ( UNDER JJM)			
Administrative Approval No.	59-DB of 2022	Dated	20-07-2022
Technical Sanction NO.	PHEQ/DB/48 of 08-2022	Dated	25-08-2022
<b>Alloted Cost;</b>	<b>Rs:- 1326201</b>	Rupees:- Thirteen Lacs Twenty six thousands two Hundred and one only	
Completion Time	60 Days		

References:

1. Your tender received in response to e-NIT No. PHQ/03\_OF 2022-23 Dated: 18-04-2022. Issued Under No: PHQ/ 265-80 Date: 18/04/2022 (Tender ID: 2022\_PHE\_167144\_16) . Read With CORRIGENDUM-3 Vide No: PHQ/CC/1060-70, Date:- 28-05-2022

For & on behalf of Lt Governor of J&K , contract for above noted work is here by fixed with you on your quoted percentage rates, terms & conditions and are reproduced hereunder:-

Sl. No.	Description of Work / Item(s)	Qty	Unit	Rate	Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed:				
1.01	All kinds of soils	149.850	cum	438.000	65334.60
1.02	Ordinary rock	39.150	cum	967.850	37891.33
2	Laying and fitting of pipes complete with G.I fittings excluding trenching and refiling etc. (external work)				0.00
2.01	25 mm dia GI	200.000	Mtr	30.650	6130.00
2.02	20 mm dia GI	300.000	Mtr	20.250	6075.00
2.03	15mm dia GI	950.000	Mtr	20.250	19237.50
3	Backfilling available excavated earth	117.450	cum	198.700	23337.32
4	Providin and laying of dry stone soling tightly hand packed on horizontal levels	14.630	cum	616.400	9017.93
5	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering all work up to plinth level (1:4:8) 1 cement, 4 coarse sand, 8 graded stone aggregate 40mm nominal size) crushed	14.630	cum	4861.835	71128.65
6	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchors blocks, plain window sills, fillets etc upto floor V level, including curing but excluding the cost of centring, shuttering and finishing with 1:2:4 (1 cement 2 coarse sand 4 graded stone aggregate 20 mm nominal size)	10.720	cum	8296.640	88939.96
7	Reinforced cement concrete work in walls ( any thickness) including attached pilasters, plinth & string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five	2.430	cum	9408.135	22861.77

8	Providing and laying in position specified grade of cement concrete in 1:3:6 nominal mix. Excluding cost of centering and shuttering.	32.150	cum	7269.185	233704.30
9	Structural steel work in single sections, with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete (Welded)	2674.000	Kg	95.163	254465.86
10	Providing Reinforcement to RCC works including bending, binding, cutting, straightening and placing in position complete.	231.000	Kg	91.138	21052.88
11	Centering and shuttering including strutting, propping and removal of form work				0.00
11.01	Foundations, footings, bases for columns	85.730	sqm	262.300	22486.98
11.02	Retaining walls, return walls, walls (any thickness) including attached pilasters	114.300	sqm	573.850	65591.06
11.03	Columns, pillars, piers, abutments, posts and struts.	21.490	sqm	680.150	14616.42
12	12 mm thick Cement Plaster in 1:6 nominal mix.	87.000	sqm	241.750	21032.25
13	Providing and Fixing of chain link fencing.	228.600	sqm	843.525	192829.82
14	Painting two or more coats of synthetic enamel	160.020	sqm	181.450	29035.63
15	Steel work welded in built up sections/framed	225.000	Kg	153.295	34491.38
16	Installation of house connections to unconnected household including providing and fixing of necessary pipe specials, Earth work at connection and Whatever Necessary.	89.000	No	1500.000	133500.00
17	Carriage of material from source to dumping site at road by mechanical transport including, loading, unloading and stacking complete.				0.00
17.01	Cement and steel for average lead of 15 km	17.680	Mt	303.646	5368.46
17.02	Sand for average lead of 35 km	28.300	cum	551.333	15802.72
17.03	20mm Aggregate for average lead of 30 km	40.700	cum	501.653	20417.28
17.04	40mm Aggregate for average lead of 30 Km	13.160	cum	545.284	7175.94
17.05	Stone soling for average lead of 10 km	14.630	cum	330.418	4834.02
18	Extra carriage of material from dumping site to actual work site by manual labour Avg Lead 200 mtr				0.00
18.01	cement	17.680	Mt	175.076	3095.34
18.02	Steel	28.300	Mt	376.050	10642.22
18.03	sand and 20 mm Aggregate	69.060	cum	347.001	23963.89
18.04	40 mm Aggregate	13.060	cum	375.130	4899.20
18.05	soling stone	14.630	cum	408.227	5972.36
19	Carriage of pipes from divisional stores Qazigund to dumping site on road by MT for average lead of 10km				0.00
19.01	25, 20, and 15mm Dia G.I	1.410	MT	445.959	628.80
	<b>G.TOTAL</b>				<b>1475360.86</b>
	Quoted Percentage rate		10.11%	Below	
	Alloted Cost				<b>1326201.87</b>
	<b>Rupees:- Thirteen Lacs Twenty six thousands two Hundred and one only</b>				
	<b>Terms &amp; Conditions</b>				
1	The cost of work is restricted to Rs 1326201 (Thirteen Lacs Twenty six thousands two Hundred and one only)				



2	Earnest money deposited by you vide CDR No.3108329 of 10/05/2022 JK Bank Verinag is being retained as security deposit and shall be released after as per the general terms and condition of the Contract. <i>Amount of Rs = 20000 and No. 2093746/2022-23-20/15000</i>
3	The allotted works shall be subject to check by the third party monitoring agency (TPiQM) appointed by the Department. The agency shall check the quality of works executed by the agencies, the quality of materials used for construction and the quality of machinery installed in each scheme. The TPiQM's role shall be that of an assistant to the Employer's Representative for the purpose of monitoring and evaluating of the performance of the Contract during the Contract Period
4	Agency must execute the works as per the requirements/specifications detailed in the relevant/applicable IS code/s
5	The rates are including the charges for submission of progress, Geo tagged photographs through the professional person before, during and after construction and progress reports in both hard and soft copies
6	The date of start of work shall be reckoned within one week form the date of issue of LOI / Contract Allotment whichever is earlier
7	No price escalation will be paid for completion of the work within the stipulated time or extended date of completion due to any reasons whatsoever.
8	In case of quantity variation OR required as per the direction of the Engineer in charge, the same has to be executed at site and nothing extra will be paid beyond the overall allotted cost.
9	Retention many / Security deposit shall be 10% of the contract value. The security deposit is to be recovered @ of 10% of bill amount from running account bills and shall be released after completion of the work and recommendation from the concerned Engineer in charge
10	Liquidated damages (LD): In the event of allottee failing, declining, neglecting or delaying the supplies / works or in the event of any damage occurring or being caused by the allottee or in the event of any default or failure by the allottee in complying with any of the terms and conditions of the contract, the Department shall with or without prejudice to any other remedies available to it under any law for the time being enforce in the UT. a) Terminate the contract after 15 days' notice and/or b) Recover the amount of loss caused by damage, failure or default, as may be determined by the department and/or c) Recover the extra cost, if any, involved in allotting contract to other party and/or d) Impose Liquidated damages on account of delay beyond the schedule completion period to the tune of 0.5% of the delayed portion of contract every week but not exceeding 10% value of the contract and/or e) Forfeit the performance security and blacklist the firm.
11	Adequate precautions be taken for the environment and social protection and all safety practices in vogue be strictly adhered to during the execution of work.
12	No mobilization advance shall be paid.
13	The Agency shall be responsible for the time and proper setting out of all the works and for the correctness of the positions, levels, dimensions and alignment of all parts of the works and for the provision of all necessary instruments, appliances and labour in connection therewith.
14	The Agency shall make his own arrangements for the engagement of all types of the labour, required for the execution of the job. No workman below the age of 18 years shall be employed on the works. Also the bidder shall comply with the provisions of all labour laws and the rules framed there under.
15	The Agency shall at his own cost make arrangements for proper storage, especially towards Rain and Snow damages of the equipment/ materials at sites till its erection/completion. For the purpose, the bidder shall, with the approval of the Engineer in charge construct temporary storage accommodation for equipment/ material at site for which land shall be provided by the department near the site of work.
16	The Agency shall in connection with the work provide and maintain at his own cost all lights, guards, fencing and watching, when and where necessary or required by the Department for the protection of the work or safety and convenience of the Public etc
17	The Agency shall in advance communicate with incharge store keeper, of Divisional Store for lifting of pipe material etc and shall make adequate measures like availability of transport and labour for easy transportation from store to site against proper receipt / Chellan, if required.

*Handwritten signature*

*Handwritten signature*  
To

*Handwritten signature*  
Kern


18	As soon as letter of award is communicated to the firm, the contract shall be complete and binding upon them, the Agency/firm shall also be required to execute an agreement with the competent authority within seven days from the date of issue of letter of award. Failure to execute such an agreement in time shall not however, prevent this contract from being enforced against the firm and the date of delivery of the material/completion of works shall be reckoned from the date of issue of the letter of award.
19	All other terms and conditions as laid down in the detailed NIT/SBD/ PWD Form No 25 double /GFR 2017/Manual for procurement of Works 2019 shall remain in force and binding upon the Agency.
20	Any rules/terms and conditions, if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/guidelines stipulated in the General Finance Rules (GFR 2017) and Manual for procurement of Works 2019 Government of India.

Copy to the :-

1	Chairman District Jal Jeevan Mission ( DDC) Anantnag / Kulgam for information.
2	Superintending Engineer Hydraulic Circle Anantnag for information.
3	Assistant Executive Engineer Jal Shakti (PHE) Sub-Division Dooru for information & necessary action. He will ensure the execution of works under stage contract after submission of damages reports duly recorded check certificate & proper geo tagged photographs before, during & after execution.
4	File concerned.

  
Head Draftsman

  
Tech Officer

  
Ex. Engineer PHE Div. Qazigund