

7

1

Government of Jammu and Kashmir
OFFICE OF THE EXECUTIVE ENGINEER, JSD (PHE) DIVISION, PULWAMA

Bashir Ahmad Naik,
Contractor,
S/o. Ghulam Ahmad Naik,
R/o Zaglgam, Pulwama
Regd. No. 24/AA/SE/HYDL/SHOPIAN/2004-05

No. PHEP/ 1177-80
Dated. 07-06-2021

Sub :- Retrofitting of Water Supply Scheme Kulpora Sheikhpora by way of Providing & laying of GI pipes, construction chain link fencing, repairs to toilet blocks including other allied works and Supply, Installation, Testing & Commissioning of electrical & mechanical works including installation of 40 No. FHTC's for Kulpora Sheikhpora (JJM).

- Ref:- 1- E-NIT S.No. 03/PHEP/Fresh of 2021-22, job No. (2), Circulated vide this office No. PHEP/345-57 Dated:-19-04-2021
2- Suptdg. Engineer Hydl. Circle, Shopian's letter No. SE/Hyd/917-18 dtd. 31-05-2021
3- Executive Engineer, PHE (Mech) Divn, South Awantipora's letter No. MDSA/309 dtd. 08-06-2021

Advertised Amount of work: ₹ 31,21,000.00

Alloted Amount of Work: ₹ 28,87,200.00

Rupees Twenty Eight Lakh(s) Eighty Seven Thousand Two Hundred Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby

fixed with you at the following rates quoted/accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No.or Qty.	Unit	Estd. Rate	RATE	
					Figures	Words
1.00	Earth work in excavation by manual means in trenches for foundations drains, pipes, cables etc (not exceeding 1.5mtr in width) and for shafts wells, cesspits, and the like not exceeding 10sqm on plan including dressing of sides and ramming of bottoms lift upto 1.5m, including getting out excavated earth and disposal of surplus excavated earth as directed All kinds of soils	496.80	Cum	436.00	350.00	Rupees Three Hundred Fifty Only
2.00	Providing and laying of stone soling hand packed including watering dressing and ramming all complete	9.83	Cum	612.50	600.00	Rupees Six Hundred Only
3.00	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with 1:4:8 mix (1 cement :4 coarse sand :8 graded stone aggregate 40 mm nominal size)	7.73	Cum	4419.85	4200.00	Rupees Four Thousand Two Hundred Only
4.00	Providing and laying specified grade of reinforced cement concrete including curing but excluding the cost of centring , shuttering , finishing and reinforcement all works upto plinth level 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	12.54	Cum	6344.25	6000.00	Rupees Six Thousand Only
5.00	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with 1:3:6 mix (1 cement :3 coarse sand :6 graded stone aggregate 20 mm nominal size)	42.52	Cum	4943.40	4950.00	Rupees Four Thousand Nine Hundred Fifty Only
6.00	Brick work with common burnt clay (non-modular) bricks of class designation 7.5 in foundation and plinth including curing in : Cement mortar 1:6 (1 cement : 6 coarse sand)	6.16	Cum	6183.75	6100.00	Rupees Six Thousand One Hundred Only
7.00	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto five level including curing but excluding the cost of centring, shuttering, finishing and reinforcement with 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	.75	Cum	8953.95	8000.00	Rupees Eight Thousand Only
8.00	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	1631.42	Kg	82.75	82.75	Rupees Eighty Two And Paise Seventy Five Only
9.00	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer incharge. Made of G.I. wire of dia 4 mm	139.08	Sqm	733.50	700.00	Rupees Seven Hundred Only
10.00	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	1480.00	Kg	133.30	130.00	Rupees One Hundred Thirty Only
11.00	Providing corrugated G.S sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks , bolts and nuts 8mm diameter with bitumen and G.I limpet washers or with G.I filled with white lead , including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal / vertical or curved surface) excluding the cost of purlins , rafters and trusses and including cutting to size and shape wherever required 0.63mm thick with zinc coating not less than 275gram/sqm	9.00	Sqm	951.80	900.00	Rupees Nine Hundred Only
12.00	Providing and fixing aluminum work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixed with dash fastener of required dia. and size including necessary filling up of gaps at junctions i.e. at top, bottom and sides with required EPDM rubber / neoprene gasket felt etc. Aluminum sections shall be smooth, rust free, straight, mildred and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-Charge (glazing, panelling and dash fasteners to be paid for separately.) (for fixed portion) Anodized aluminum (Anodized transparent or dyed to required shade according to IS:1868, minimum anodic coating of grade AC 15)	2.11	Sqm	5000.00	5000.00	Rupees Five Thousand Only
13.00	Steel reinforcement for RCC work including straightening, cutting , bending , placing in position and binding all complete upto plinth level thermo-Mechanically -Treated bars of grade Fe-500D or more	1130.00	Kg	79.25	79.25	Rupees Seventy Nine And Paise Twenty Five Only
14.00	Centring shuttering including strutting , propping etc. and removal of form work for					
14.10	Foundation footings , bases for columns	182.80	Sqm	262.30	200.00	Rupees Two Hundred Only

1.20	Suspended floors, roofs, landings, balconies and access platforms	6.00	Sqm	635.60	500.00	Rupees Five Hundred Only
1.30	Edges of slabs and breaks in floors and walls Under 20 cm wide	10.00	Mtr	242.30	200.00	Rupees Two Hundred Only
15.00	12mm Cement plaster of mix: 1 : 4 (1 cement : 4 fine sand)	148.51	Sqm	260.05	200.00	Rupees Two Hundred Only
16.00	Providing and fixing of sanitary items of standard quality like 500 liters sinlex , V.C Indian type , flush tank , with all accessories . pvc pipe , pipe specials , C.P items , p trap , floor trap, bends , steel sink , connecting with soakage , whichever be necessary to make functional all complete (to be paid as per actual details /measurements with supporting voucher duly verified by AEE concern)	1.00	Job	RQC	12000.00	Rupees Twelve Thousand Only
17.00	Providing and laying Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturers) of 1st quality conforming to IS: 15622 of approved make, laid on 20 mm thick bed of cement mortar 1: 4 (1 cement : 4 coarse sand) including pointing the joints with white cement and matching pigment etc., complete. In colour such as White, Ivory, Grey, Fume Red Brown	22.38	Sqm	1052.75	1000.00	Rupees One Thousand Only
18.00	Providing fixing supplying P.C.C rings including earthwork excavation and disposal of surplus excavated material outside the premises including providing and laying cement concrete in 1:2:4 mix over septic tank and soakage pit . construction of man hole chambers with angle iron frame and covering arrangements .providing fixing of P.V.C pipe (prince make B class) including bends whichever is required at site or as per directions of Engineer- in- charge (3 compartments for septic tank and 1 for soakage pit . (to be paid as per actual details /measurements)	13.00	Mtr	RQC	600.00	Rupees Six Hundred Only
19.00	Providing ,supplying fixing installation of electric fittings of standard quality incl. 19/18 copper wire cable connection with transformer , installation of panel board, switch board, switches, lighting points, heating points, fans , exhaust fans pvc conduit, havets wire , MCB, changeover , whichever is related to the item and found necessary at site or as per directions of Engineer- in- charge (to be paid as per actual details /measurements with supporting vouchers duly verified by AEE concern)	1.00	Job	RQC	6000.00	Rupees Six Thousand Only
20.00	Providing and fixing G.I. pipes complete with G.I. fittings excluding trenching and refilling etc. (external work)					
20.10	50 mm dia G.I pipes	500.00	Mtr	RQC	477.5	Rupees Four Hundred Seventy Seven And Paise Fifty Only
20.20	40 mm dia G.I pipes	1110.00	Mtr	RQC	380.00	Rupees Three Hundred Eighty Only
20.30	25 mm dia G.I pipes	800.00	Mtr	RQC	249	Rupees Two Hundred Forty Nine Only
20.40	20 mm dia G.I pipes	1000.00	Mtr	RQC	182.65	Rupees One Hundred Eighty Two And Paise Sixty Five Only
20.50	15 mm dia G.I pipes	480.00	Mtr	RQC	144.4	Rupees One Hundred Forty Four And Paise Forty Only
21.00	Making connection of G.I distribution branch with G.I main of following size by providing and fixing tees, including cutting and threading the pipe etc complete					
21.10	(a) 25 to 40 mm nominal bore	15.00	No	668.25	500.00	Rupees Five Hundred Only
21.20	(b) Above 40 mm nominal bore	2.00	No	1268.75	800.00	Rupees Eight Hundred Only
22.00	Filling available excavated earth (Excl. rock) in trenches, plinth sides of foundation etc. layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering lead upto 50mtr and lift upto 1.5mtr	418.87	Cum	198.70	120.00	Rupees One Hundred Twenty Only
23.00	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc complete	288.75	Sqm	188.80	180.00	Rupees One Hundred Eighty Only
24.00	Provision for repairs/ renovation of existing operator quarter by way of replacement/ repairs to damaged windows/ doors/ glass panes/ wire gauze shutters, electrification by way of providing, switches, pannel board, wire, lamps, heating, switch, lighting switch, control board, service line, finishing walls, with paint and which ever is required as per directions of engineers in charge to be paid as per actual	1.00	Job	RQC	5000	Rupees Five Thousand Only
25.00	Desilting of various structures including OHT, clear water sump including disposal of same from premises outside with levelling and dressing of ground etc complete	3893.14	Cft	RQC	9.00	Rupees Nine Only
26.00	Carriage of material from source of site upto site of work by mechanical transport including loading unloading stacking at site complete					
26.10	Sand and Bajri avg lead 15km	93.22	Cum	297.02	200.00	Rupees Two Hundred Only
26.20	Cement and steel avg lead 15km	13.78	M.T.	264.04	250.00	Rupees Two Hundred Fifty Only
26.30	Stone solling avg lead 15km	9.83	Cum	349.42	300.00	Rupees Three Hundred Only
26.40	Bricks avg lead 15 Kms	2815.00	No	0.79	0.50	Rupees And Paise Fifty Only
27.00	Removal of choked filter media from pressure filter vessel .The job includes all loads and lifts, disposal of choked media to dumping site outside the premises of the plant.The vessel needs to be cleaned properly and dried before laying of fresh media.	1.00	Job	RQC	10000.00	Rupees Ten Thousand Only
28.00	Providing and laying of filter media of specific size and grade (preferably from Sindh Nallah Ganderbal) duly sezeened ,washed ,free from dust ,dirt ,loom and any other inorganic material or suspension .The job includes carriage of media from Ganderbal to site including all loads and lifts required as per the site condition. The media is to be laid in different layers of specific size and grade from bottom to top over the filter bed plate. The bottom layer is to be laid without tilling/damaging the pressure nozzles.	1.00	Job	RQC	34000.00	Rupees Thirty Four Thousand Only
29.00	Providing and fitting of 12 mm dia. Fine threaded PVC nozzles auxiliary type to be fitted on filter bed plate of pressure vessel.	250.00	Job	RQC	200.00	Rupees Two Hundred Only
30.00	Providing and fitting of 29 inch.dia rubber washers /gaskets for manhole and inspection chamber and opening of pressure filter vessel.	2.00	Job	RQC	400.00	Rupees Four Hundred Only

Retrofitting of Water Supply Scheme Kulpora Sheikhpora by way of Providing & laying of GI pipes, construction chain link fencing, repairs to toilet blocks, including other allied works and Supply, Installation, Testing & Commissioning of electrical & mechanical works including installation of 40 No. FHTC's for Kulpora Sheikhpora (JJM).

1.00	Providing and fitting of 3"x5/8" nuts and bolts.	20.00	Kg	RQC	110.00	Rupees One Hundred Ten Only
32.00	Overhauling of backwash unit by way of dismantling of unit parts assembling cleaning, oiling, greasing, replacement of any damaged parts, refining of sub assemblies. Installation of backwash unit with its existing suction & delivery outlet. Job includes P/F of packing & consumables. Job also includes rewinding of its motor & full load testing.	1.00	Job	RQC	18000.00	Rupees Eighteen Thousand Only
33.00	Overhauling of air Scavenging/blower unit by way of P/F of reducing pressure weights, filling of oil, replacement of pressure valves. Job includes oiling, greasing & fitting of consumables. Job includes P/F of packing & consumables. Job also includes rewinding of its motor & full load testing.	1.00	Job	RQC	19000.00	Rupees Nineteen Thousand Only
34.00	P/F of 20 meters of 80mm dia GI by pass pipe line with 80 mm dia flanges, RI packings, Bends, nuts bolts. Job includes welding works for fitment, arrangement of welding set & skilled welder & labours involved in the job.	1.00	Job	RQC	25000.00	Rupees Twenty Five Thousand Only
35.00	P/F of 80 mm dia CI double flanged Sluice valves of reputed make.	2.00	Job	RQC	9000.00	Rupees Nine Thousand Only
36.00	P/F of 65 mm dia CI double flanged Sluice valves of reputed make.	1.00	Job	RQC	7000.00	Rupees Seven Thousand Only
37.00	Installation of horizontal pumping equipment on concrete/ angle iron base frame after dismantling the damaged foundation structure. Job includes all sorts of skilled & unskilled labour & arrangement of welding set etc. Job also includes fitment of pumping equipment & it testing.	1.00	Job	RQC	18000.00	Rupees Eighteen Thousand Only
38.00	P/F of bleach & alum dosing pumps metering type of 20lph & 3 bar pressure with motors of Cheonsej make & wiring etc. to make both units functional. Also P/F of PVC pipe fittings wherever required as per site requirement.	1.00	Job	RQC	40000.00	Rupees Forty Thousand Only
39.00	Removal of tin sheets from flocculator & cleaning them manually. The job includes all loads and lifts, disposal of mud etc. to dumping site outside the premises of the plant. The vessel needs to be cleaned properly and dried before laying of fitment of tin sheets.	1.00	Job	RQC	15000.00	Rupees Fifteen Thousand Only
40.00	P/F of 100 Amp MCCB of Havells/L&T make	2.00	Job	RQC	500.00	Rupees Five Hundred Only
41.00	P/F of 100 Amp Changeover Switch of Havells/L&T make	1.00	Job	RQC	1500.00	Rupees One Thousand Five Hundred Only
42.00	P/F of starters of L&T/ Havells/Crompton make for running of 5/7.5 hp motors of back wash, air blower etc	2.00	Job	RQC	10000.00	Rupees Ten Thousand Only
43.00	P/F of 10mm sq. single core copper cable for inter connections	30.00	Mtr	RQC	180.00	Rupees One Hundred Eighty Only
44.00	P/F of 200 Amp MCCB of Havells/L&T make	1.00	Job	RQC	800.00	Rupees Eight Hundred Only
45.00	P/F of MUG 20 starters of L&T/ Havells/Crompton make for running of 15 hp motors at Raw water station.	2.00	Job	RQC	25000.00	Rupees Twenty Five Thousand Only
46.00	Repairs to 50 Kva voltage stabilizer by way of complete rewinding of its legs & P/F of A grade T.oil to the top of it. Also P/F of disc type regulator assembly as per sample.	1.00	Job	RQC	18000.00	Rupees Eighteen Thousand Only
47.00	Repairs to 7.5 hp horizontal motor by way of complete rewinding of it & full load testing at site.	2.00	Job	RQC	7500.00	Rupees Seven Thousand Five Hundred Only
48.00	Supply, installation, testing and commissioning of bowl type Horizontal / Vertical type Open well Submersible Raw water pumping equipment (as per the specifications shown in Annexure B in Tender Document)	1.00	Job	RQC	20000.00	Rupees Twenty Thousand Only
49.00	Supply, fixing, testing & commissioning of 04 No. flood lights internal & external of the filter plant each with 24 watt LED type of Havells/ Bajaj/ Wipro/ Phillips make ; in all respects. The job includes P/F of 16 ampere ON OFF MCB switches on junction box for each flood light fitted at the bottom 6 feet from the ground level with locking arrangement. The cabling for luminaires shall be 4.0 mm square copper wire (90meters) of standard quality. (Havells/ABB/L&T) make in black & red as per ISI specifications. The cabling shall be of 2 core 16mm square PVC insulated Aluminium cable (30 meters) of (Havells/ABB/L&T) make.	1.00	Job	RQC	15000.00	Rupees Fifteen Thousand Only

Terms and Conditions:-

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However the non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (02) Months and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked

Head Draftsman

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for information
- 2- District Development Commissioner Pulwama for information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Tahab for information and necessary action.
- 4- File Concerned.

Executive Engineer
ISD (PHE) Div. Pulwama