

**OFFICE OF THE EXECUTIVE ENGINEER JAL SHAKTI (PHE) DIVISION QAZIGUND**

Allotment Order No: PHQ/CC/ 3593-96 of 2022-23, dated 09/09/2022

No: PHQ/ 3593-96 DATE: 09/09/2022

**NAME : Bashir Ahmad Mir S/O.Gh.Hassan Mir R/O.Dardkote Qazigund**

email: mirbashirdkt@gmail.com Cell No.8825098066

REGD. NO: KMR/PHE/D/RCR/1994 95/DEE/50 OF 10-1994 ACCOUNT NO: 0017030100000202 JK Bank Qazigund

GSTN: 01ANAPM7163P2ZS ANAPM7163P

Administrative Approval No. 60 DB of 2022 Dated 20/7/2022

Technical Sanction No. PHEQ/DB 52 of 2022 Dated 25-08-2022

**Alloted Cost; Rs:- 756945/=** Rupees:- Seven Lakhs Fifty Six thousands Nine Hundred and forty five only

Completion Time 60 Days

**Name of Schemes:** -Laying and fitting of additional supply line to village Larm (Tail portion) and distribution system and upgradation of sub main and improvements to existing sub mains and distribution system WSS Gassipora

**References:** 1. Your tender received in response to E-NIT No.02 of 2022-23 ISSUED UNDER NO:PHQ/225-40 Dated 18/04/2022 (Tender ID: 2022\_PHE\_167144\_22) read with CORRIGENDUM-I vide No. PHQ/CC/619-27 Date:- 10-05-2022

For & on behalf of Lt. Governor of J&K , contract for above noted work is here by fixed with you on your quoted percentage rates, terms & conditions and are reproduced hereunder:-

Sl. No.	Description of Work / Item(s)	Qty	Unit	Estd. Rate	Amount
1	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/by mechanical means including stacking of pipes within 50 meters lead as per direction of Engineer-in-charge :				0.00
1.01	15 mm to 40 mm nominal bore	500.000	Mtr	99.750	49875.00
1.02	Above 40 mm nominal bore	220.000	Mtr	110.650	24343.00
2	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed:				0.00
2.01	All kinds of soils	581.800	cum	436.000	253664.80
3	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes and Earth work but incl. cost of pipe fittings.				0.00
3.01	100 mm dia GI Pipe	58.000	Mtr	107.700	6246.60
3.02	50 mm dia GI Pipe	397.000	Mtr	40.800	16197.60
3.03	40 mm dia GI Pipe	344.000	Mtr	40.800	14035.20
3.04	25 mm dia GI Pipe	694.000	Mtr	30.650	21271.10
3.05	20 mm dia GI Pipe	844.000	Mtr	20.250	17091.00
3.06	15 mm dia GI Pipe	500.000	Mtr	20.250	10125.00
4	Providing and fixing of M.S Flanges to 80 mm dia GI Pipes including cost of flanges ,welding charges and all carriage complete .	135.000	Joint	1100.000	148500.00
5	Providing and instalation of house hold connection tounconnected household including providing and fixing of necessary pipes specials,earthwork at connection and whatever necessary.complete	68.000	No	1500.000	102000.00


6	Providing and fixing of 100/80 mm dia Sluice valves with all accessories and carriage complete job.				0 00
6.01	100 mm dia	1 000	No	5000 000	5000 00
6.02	80 mm dia	1 000	No	3000 000	3000 00
7	Rethreading of damaged pipes ends				
7.01	15 mm to 40 mm nominal bore	40 000	No	50 000	2000 00
7.02	Above 40 mm nominal bore	25 000	No	75 000	1875 00
7.03	Welding charges of pipes at spots including hire charges of welding machine and load carrier complete job	15 000	Joint	800 000	12000 00
8	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	523 600	cum	198.700	104039.32
9	Carriage of Pipes material From divisinal store to dumping site of work by mechanical transport For an average lead of 17 Km including loading , unloading and stacking complete .				0 00
9.01	80,50,40,25,20 and 15 mm dia GI Pipe	9.800	MT	325.243	3187.38
10	Extra carriage of pipe material from dumping site to actual site of work by mannual labours Avg Lead 300 Mtr				0 00
10.01	80,50,40,25,20 and 15 mm dia GI Pipe	9.800	MT	452.686	4436.32
<b>Total</b>					<b>798887.32</b>
<b>Quoted Percentage rate</b>		5.25%		Below	
<b>Allotted Cost</b>				<b>756945.74</b>	
<b>Rupees:- Six Lakhs Thrity four thousands Seven Hundred and Nine only</b>					
<b>Head Draftsman</b>		<b>Tech. Officer</b>		<b>Ex. Engineer PHE Div. Qazigund</b>	
<b>Terms &amp; Conditions</b>					
1	The cost of work is restricted to Rs. 756945/= ( Rupees Seven Lakhs Fifty Six thousands Nine Hundred and forty five only )				
2	Earnest money deposited by you vide FDR No.541250 dated 09/05/2022 for Rs.19800/=JK Bank Qazigund is being retained as security deposit and shall be released after as per the general terms and condition of the Contract				
3	The allotted works shall be subject to check by the third party monitoring agency (TPIQM) appointed by the Department. The agency shall check the quality of works executed by the agencies, the quality of materials used for construction and the quality of machinery installed in each scheme. The TPIQM's role shall be that of an assistant to the Employer's Representative for the purpose of monitoring and evaluating of the performance of the Contract during the Contract Period				
4	Agency must execute the works as per the requirements/specifications detailed in the relevant/applicable IS code/s				
5	The rates are including the charges for submission of progress, Geo tagged photographs through the professional person before , during and after construction and progress reports in both hard and soft copies				
6	The date of start of work shall be reckoned within one week form the date of issue of LOI / Contract Allotment whichever is earlier.				
7	No price escalation will be paid for completion of the work within the stipulated time or extended date of completion due to any reasons whatsoever				
8	In case of quantity variation OR required as per the direction of the Engineer in charge , the same has to be executed at site and nothing extra will be paid beyond the overall allotted cost.				


9	Retention many / Security deposit shall be 10% of the contract value. The security deposit is to be recovered @ of 10% of bill amount from running account bills and shall be released after completion of the work and
10	Liquidated damages (LD). In the event of allottee failing, declining, neglecting or delaying the supplies / works or in the event of any damage occurring or being caused by the allottee or in the event of any default or failure by the allottee in complying with any of the terms and conditions of the contract, the Department shall with or without prejudice to any other remedies available to it under any law for the time being enforce in the UT. a) Terminate the contract after 15 days' notice and/or b) Recover the amount of loss caused by damage, failure or default, as may be determined by the department and/or c) Recover the extra cost, if any, involved in allotting contract to other party and/or d) Impose Liquidated damages on account of delay beyond the schedule completion period to the tune of 0.5% of the delayed portion of contract every week but not exceeding 10% value of the contract and/or e) Forfeit the performance security and blacklist the firm.
11	Adequate precautions be taken for the environment and social protection and all safety practices in vogue be strictly adhered to during the execution of work.
12	No mobilization advance shall be paid.
13	The Agency shall be responsible for the time and proper setting out of all the works and for the correctness of the positions, levels, dimensions and alignment of all parts of the works and for the provision of all necessary instruments, appliances and labour in connection therewith.
14	The Agency shall make his own arrangements for the engagement of all types of the labour, required for the execution of the job. No workman below the age of 18 years shall be employed on the works. Also the bidder shall comply with the provisions of all labour laws and the rules framed there under.
15	The Agency shall at his own cost make arrangements for proper storage, especially towards Rain and Snow damages of the equipment/ materials at sites till its erection/completion. For the purpose, the bidder shall, with the approval of the Engineer in charge construct temporary storage accommodation for equipment/ material at site for which land shall be provided by the department near the site of work.
16	The Agency shall in connection with the work provide and maintain at his own cost all lights, guards, fencing and watching, when and where necessary or required by the Department for the protection of the work or safety and convenience of the Public etc.
17	The Agency shall in advance communicate with incharge store keeper, of Divisional Store for lifting of pipe material etc and shall make adequate measures like availability of transport and labour for easy transportation from store to site against proper receipt / Challan, if required.
18	As soon as letter of award is communicated to the firm, the contract shall be complete and binding upon them, the Agency/firm shall also be required to execute an agreement with the competent authority within seven days from the date of issue of letter of award. Failure to execute such an agreement in time shall not however, prevent this contract from being enforced against the firm and the date of delivery of the material/completion of works shall be reckoned from the date of issue of the letter of award.
19	All other terms and conditions as laid down in the detailed NIT/SBD/ PWD Form No.25 double /GFR 2017/Manual for procurement of Works 2019 shall remain in force and binding upon the Agency.
20	Any rules/terms and conditions, if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/guidelines stipulated in the General Finance Rules (GFR 2017) and Manual for procurement of Works 2019 Government of India.

Copy to the :-

1	Chairman District Jal Jeevan Mission ( DDC) Anantnag for information.
2	Superintending Engineer Hydraulic Circle Anantnag for information.
3	Assistant Executive Engineer Jal Shakti (PHE) Sub-Division <del>Deora</del> for information & necessary action. He will ensure the execution of work strictly in accordance with approved proposal/guidelines under JJM. The cost of work should not exceed beyond allotted cost for which he shall be personally responsible.
4	File concerned.

  
Head Draftsman

  
Tech. Officer

  
Ex. Engineer PHE Div. Qazigund

OFFICE OF THE EXECUTIVE ENGINEER JAL SHAKTI (PHE) DIVISION QAZIGUND

Allotment Order No: PHQ/CC/ 59 of 2022-23 dated 10/05/2022

No: PHQ/ 3522-26 DATE: 10/05/2022  
 NAME: Zakir Hussain Mir S/O Gh Nabi Mir R/O Mirgund Doru  
 email: mirzaker85180@gmail.com Cell No. 9906438382  
 REGD NO SE/Hyd/Bud-72-DEE / 2021-22 ACCOUNT NO 0044040100012139 JK Bank DOORU  
 GSTN: 01CEMPM7693M1ZD PAN: CEMPM7693M

Name of Schemes:-L/F of pipes incl. P/F of pipe specials WSS Lonepora Shish.tergam ( UNDER JJM)

Administrative Approval No. 58-DB of 2022 Dated 20-07-2022  
 Technical Sanction NO. PHEQ/DB/ 51 of 08-2022 Dated 25-08-2022  
 Alloted Cost; Rs:-663573 Lacs Six Lacs Sixty three thousands five Hundred and seventy three only  
 Completion Time 90 Days

References:1. Your tender received in response to e-NIT No. PHQ/02\_OF 2022-23 Dated: 18-04-2022  
 (Tender ID: 2022\_PHE\_167000\_3) read with CORRIGENDUM-1 vide No. PHQ/CC/619-27  
 Date:- 10-05-2022

For & on behalf of Lt. Governor of J&K, contract for above noted work is here by fixed with you on your quoted percentage rates, terms & conditions and are reproduced hereunder:-

Sl. No.	Description of Work / Item(s)	Qty	Unit	Rate	Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m. including getting out excavated earth and disposal of surplus excavated earth as directed:				
1 01	All kinds of soil	175.880	Cum	436.000	76683.68
1 02	Crucary rock	175.870	Cum	967.850	170215.78
2	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes, fittings and Earth work				0.00
2 01	40 mm dia GI Pipe	200.000	Mtr	40.800	8160.00
2 02	25 mm dia GI pipe	300.000	Mtr	30.650	9195.00
2 03	20 mm dia GI pipe	400.000	Mtr	20.250	8100.00
2 04	15 mm dia GI pipe	300.000	Mtr	20.250	6075.00
3	Filling available excavated earth (excluding rock) in trenches, path, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m	310.575	Cum	198.700	62903.45
4	Providing and fixing of MS flanges including cost of MS flanges, cutting of pipes, welding, nuts, bolts, rubber washers, all carriage upto site of work but excluding cost of earth work and re-filling ( 100 mm dia GI Pipe)	142.000	Joints	1500.000	213000.00
5	Demolishing cement concrete manually/by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge	12.000	Cum	1569.200	18830.40
6	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, buttress, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchors blocks, plain window sills, fillets etc upto floor V level, including curing but excluding the cost of centring, shuttering and finishing with (1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size)	8.000	Cum	7269.185	58153.48

7	Provision for installation of House hold connections to unconnected households including providing and fixing of necessary pipe specials Earthwork of connections and whatever necessary	20 000	No	1500 000	30000 00
8	Providing and fixing of regulating valves/air valves at various spots for regulation of water supply.				0 00
8 01	100 mm dia Gate valves	2 000	No	9000 000	18000 00
9	Carriage of pipes from divisional store up to actual site of work by M.T Avg lead 7 Km including loading, unloading and stacking complete.				0 00
9 01	100 mm dia GI Pipe	850 000	Mtr	5 129	4359 65
9 02	40/25/20 and 15 mm dia GI pipe	2 003	MT	209 875	420 38
<b>G.TOTAL</b>					<b>684096.82</b>
Quoted Percentage rate			3.00% Below		
Alloted Cost					<b>663573.92</b>
<b>Rupees:- Six Lacs Sixty three thousands five Hundred and seventy three only</b>					

Head Draftsman


Exec. Officer

Ex. Engineer PHE  
Div. Qazigund


**Terms & Conditions**

1	Earnest money deposited by you vide CDR No.2671682 of 07/05/2022 for Rs.14200/= JK Bank Doru and CDR No. 3097193 DT;- 26-08-2022 Rs 7000/= is being retained as security deposit and shall be released after as per the general terms and condition of the Contract
2	The client/paying authority shall be the concerned Executive Engineer. Besides, the supervision of the various components of the work shall be carried out by the concerned Engineers of the Division/TPIQM consultants under the overall coordination of the concerned Superintending Engineer Hydraulic Circle.
3	The allotted works shall be subject to check by the third party monitoring agency (TPIQM) appointed by the Department. The agency shall check the quality of works executed by the agencies, the quality of materials used for construction and the quality of machinery installed in each scheme. The TPIQM's role shall be that of an assistant to the Employer's Representative for the purpose of monitoring and evaluating of the performance of the Contract during the Contract Period
4	Agency must execute the works as per the requirements/specifications detailed in the relevant/applicable IS code/s
5	The rates are including the charges for submission of progress, Geo tagged photographs through the professional person before , during and after construction and progress reports in both hard and soft copies
6	The date of start of work shall be reckoned within one week form the date of issue of LOI / Contract Allotment whichever is earlier.
7	No price escalation will be paid for completion of the work within the stipulated time or extended date of completion due to any reasons whatsoever.
8	In case of quantity variation OR required as per the direction of the Engineer in charge , the same has to be executed at site and nothing extra will be paid beyond the overall allotted cost.
9	Retention many / Security deposit shall be 10% of the contract value . The security deposit is to be recovered @ of 10% of bill amount from running account bills and shall be released after completion of the work and recommendation from the concerned Engineer in charge
10	Liquidated damages (LD): In the event of allottee failing, declining, neglecting or delaying the supplies / works or in the event of any damage occurring or being caused by the allottee or in the event of any default or failure by the allottee in complying with any of the terms and conditions of the contract, the Department shall with or without prejudice to any other remedies available to it under any law for the time being enforce in the UT a) Terminate the contract after 15 days' notice and/or b) Recover the amount of loss caused by damage, failure or default, as may be determined by the department and/or c) Recover the extra cost, if any involved in allotting contract to other party and/or d) Impose Liquidated damages on account of delay beyond the schedule completion period to the tune of 0.5% of the delayed portion of contract every week but not exceeding 10% value of the contract. and/or e) Forfeit the performance security and blacklist the firm.

11	Adequate precautions be taken for the environment and social protection and all safety practices in vogue be strictly adhered to during the execution of work.
12	No mobilization advance shall be paid
13	The Agency shall be responsible for the time and proper setting out of all the works and for the correctness of the positions, levels, dimensions and alignment of all parts of the works and for the provision of all necessary instruments, appliances and labour in connection therewith.
14	The Agency shall make his own arrangements for the engagement of all types of the labour, required for the execution of the job. No workman below the age of 18 years shall be employed on the works. Also the bidder shall comply with the provisions of all labour laws and the rules framed there under.
15	The Agency shall at his own cost make arrangements for proper storage, especially towards Rain and Snow damages of the equipment/ materials at sites till its erection/completion. For the purpose, the bidder shall, with the approval of the Engineer in charge construct temporary storage accommodation for equipment/ material at site for which land shall be provided by the department near the site of work.
16	The Agency shall in connection with the work provide and maintain at his own cost all lights, guards, fencing and watching, when and where necessary or required by the Department for the protection of the work or safety and convenience of the Public etc
17	The Agency shall in advance communicate with incharge store keeper, of Divisional Store for lifting of pipe material etc and shall make adequate measures like availability of transport and labour for easy transportation from store to site against proper receipt / Challan, if required.
18	As soon as letter of award is communicated to the firm, the contract shall be complete and binding upon them, the Agency/firm shall also be required to execute an agreement with the competent authority within seven days from the date of issue of letter of award. Failure to execute such an agreement in time shall not however, prevent this contract from being enforced against the firm and the date of delivery of the material/completion of works shall be reckoned from the date of issue of the letter of award.
19	All other terms and conditions as laid down in the detailed NIT/SBD/ PWD Form No 25 double /GFR 2017/Manual for procurement of Works 2019 shall remain in force and binding upon the Agency.
20	Any rules/terms and conditions, if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/guidelines stipulated in the General Finance Rules (GFR 2017) and Manual for procurement of Works 2019 Government of India.
<b>Copy to the :-</b>	
1	Chairman District Jal Jeevan Mission ( DDC) Anantnag / Kulgam for information.
2	Superintending Engineer Hydraulic Circle Anantnag for information.
3	Assistant Executive Engineer Jal Shakti (PHE) Sub-Division Dooru for information & necessary action. He will ensure the execution of works under stage contract after submission of damages reports duly recorded check certificate & proper geo tagged photographs before, during & after execution.
4	File concerned

  
Head Draftsman

  
Tec. Officer

  
Ex. Engineer PHE  
Div. Qazigund