

HD/CC

Government of Jammu and Kashmir
OFFICE OF THE SUPERINTENDING ENGINEER HYDRAULIC CIRCLE ANANTNAG/KULGAM
HQ: ANANTNAG

Allotment Order No. 38 of 2022-23 dated 31 /12/2022

Name: - Reyaz Ahmad Dar S/O Ab Rehman R/o Bonegam
 Regd. No. 26 AAY CVPP PDHEP/CE/IL 2019-20
 email ID reyazahmad@rediffmail.com
 Phone No. 706268401
 GSTN 01AKOPD9719M1ZU
 PAN AKOPD9719M

2295
10-1-23


Allotment Order No. 38 of 2022 dated 31 /12/2022
 Subject:- Laying and fitting of pipes and shifting of feeding main WSS Rahim Sahib Bindoo

Advertised Cost : ₹ 173.47 Lacs
 Alloted Cost : ₹ 166.91 Lacs

- References:
- 1 Your tender uploaded on Tender Portal in response to e-NIT No.07 of 4/2022 issued by Executive Engineer, Jal Shakti, PHE Division Qazigund vide Tender ID 2022_PHE_167818_2.
 2. Executive Engineer, Jal Shakti, PHE Division Qazigund's letter No.PHQ/2374-80 dated 29.07.2022
 - 3 This office letter No. SE/Hyd/Cors/6447-50 dated 14.09.2022

For & on behalf of Lt. Governor of J&K, contract for above mentioned job is here by fixed with you on your following quoted rates, terms & conditions:-

Sl.No	Description of Work / Item(s)	Quantity	Units	Rate	Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed:				
1.01	All kinds of soil	10803.600	Cum	₹ 436.00	₹ 4,710,369.60
1.02	Ordinary Rock	3803.400	Cum	₹ 841.60	₹ 3,200,941.44
2	Dismantling old C.I. pipes including excavation & refilling trenches after taking out the pipes, breaking lead caulked joints, melting of lead & making into blocks, including stacking of pipes at site lead up to 50 meter :				
2.01	200mm dia. D.I Pipes	1400.000	Mtr	₹ 339.05	₹ 474,670.00
2.02	150mm dia D.I Pipes	1400.000	Mtr	₹ 304.35	₹ 426,090.00
3	Demolishing cement concrete manually/by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in- : 1:3:6 or richer mix (i/c equivalent design mix)	56.7000	Cum	₹ 1,569.20	₹ 88,973.64
4	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes and Earth work but incl. cost of fittings.				
4.01	65 mm dia. G.I. pipes	1650.0000	Mtr	₹ 73.05	₹ 120,532.50
4.02	50 mm dia. G.I. pipes	4600.000	Mtr	₹ 40.80	₹ 187,680.00
4.03	40 mm dia. G.I. pipes	3900.000	Mtr	₹ 40.80	₹ 159,120.00
4.04	25 mm dia. G.I. pipes	3800.000	Mtr	₹ 30.65	₹ 116,470.00
4.05	20 mm dia. G.I. pipes	4200.000	Mtr	₹ 20.25	₹ 85,050.00
4.06	15 mm dia. G.I. pipes	2000.0000	Mtr	₹ 20.25	₹ 40,500.00


 HD To

	Providing and fixing MS Flanges to GI pipes including cost of cutting of threaded portion, flanges, welding, nuts, bolts, Rubber Washer and carriage etc complete job.				
5.01	100mm dia G.I Pipes	548.000	Pair	₹ 1,500.00	₹ 822,000.00
5.02	80mm dia G.I Pipes	411.0000	Pair	₹ 1,350.00	₹ 554,850.00
6	Laying in position centrifugally cast (spun) iron S&S or flanged pipes (excluding cost of pipe)	5157.950	Qtl	₹ 245.55	₹ 1,266,534.62
7	Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes or Ductile Iron Pipes including testing of joints and including the cost of rubber gasket.				
7.01	350mm dia DI pipe	364.0000	Joint	₹ 361.65	₹ 131,640.60
7.02	300mm dia	300.000	joint	₹ 340.30	₹ 102,090.00
7.03	250mm dia	255.0000	joint	₹ 259.90	₹ 66,274.50
7.04	200mm dia	637.000	joint	₹ 213.00	₹ 135,681.00
7.05	150mm dia	909.000	joint	₹ 144.70	₹ 131,532.30
8	Making connection of G.I. distribution branch with G.I. main offollowing sizes by providing and fixing Tee, including cutting andthreading the pipe etc. complete				
8.01	15 to 40 mm nominal bore	20.000	Each	₹ 666.25	₹ 13,325.00
8.02	50 to 80 mm nominal bore	10.000	Each	₹ 1,268.75	₹ 12,687.50
9	Installation of house connections to unconnected household including providing and fixing of necessary pipe specials, Earth work at connection and Whatever Necessary.	216.000	No	₹ 1,500.00	₹ 324,000.00
10	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	37.800	Cum	₹ 6,465.20	₹ 244,384.37
11	Structural steel work in built up sections, trusses and framed work,including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.Welded	1000.000	kg	₹ 102.13	₹ 102,130.00

HD

TO



Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.

			13146.300	Cum	₹ 198.70	₹ 2,612,169.81
13	Carriage of Pipe material from source to dumping site at road by mechanical transport.					
13.01	350 mm dia D I Pipes	08 KM	2000.000	mtr	₹ 36.57	₹ 73,140.00
13.02	300 mm dia D I Pipes	08 KM	1650.000	mtr	₹ 26.12	₹ 43,093.05
13.03	250 mm dia D I Pipes	08 KM	1400.000	mtr	₹ 21.14	₹ 29,591.80
13.04	200mm dia D I Pipes	08 KM	2100.000	mtr	₹ 14.87	₹ 31,227.00
13.05	150 mm dia D I Pipes	08 KM	3600.000	mtr	₹ 9.14	₹ 32,914.80
13.06	100mm dia G.I Pipes for an avg. lead of 08 Km		3400.000	Mtr	₹ 5.49	₹ 18,652.40
13.07	80/65/50/40/25/20 mm dia GI pipe	08 Km	73.3300	MT	₹ 223.14	₹ 16,362.49
14	Extra Carriage of pipes material from road site upto actual site of work by manual labour for avg. lead of 500 mtrs.					
14.01	350mm dia DI pipe		2000.000	mtr	₹ 63.91	₹ 127,812.00
14.02	300 mm dia DI Pipe		1650.000	mtr	₹ 44.69	₹ 73,736.85
14.03	250 mm dia DI Pipe		1400.000	mtr	₹ 35.72	₹ 50,006.60
14.04	200mm dia D I Pipe		2000.000	mtr	₹ 20.32	₹ 40,642.00
14.05	150 mm dia D I pipe		3500.000	Mtr	₹ 13.58	₹ 47,537.00
14.06	100 mm dia GI pipe		3400.000	Mtr	₹ 9.60	₹ 32,650.20
14.07	80/65 mm dia GI pipe		73.330	MT	₹ 355.70	₹ 26,083.11
Original Schedule Value						₹ 16,773,146.000
Add Quoted/Accepted percentage					-(Minus) 0.49%	-₹ 82,188.000
Alloted Amount						₹ 16,690,958.000

(Rupees One Crore Sixty Six Lac Ninety Thousand Nine Hundred Fifty Eight Only)

Terms & Conditions

1	The overall payment under the contract will be restricted to DAP/DPR provision. i.e Rs. 156.12 lacs
2	This letter of allotment & your tender will constitute a legal contract document and the conditions laid down in the detailed NIT/Form No 25-double will hold good and binding upon you.
3	You have to attend the Divisional/Circle Office along with your enlistment card for drawl of agreement . However non-drawl of agreement will not prevent the contract from being enforced upon you.
4	You are advised to deposit 3% of the allotted amount in the form of CDR/TDR/Bank Guarantee pledged to the undersigned within a weeks' time positively. the same shall be retained as Performance Security Deposit and be released subject to the successful completion & expiry of DLP of the work.


 To 


	The date of start of work shall be reckoned within one week from the date of issuance of this Contract allotment.
6	The work shall have to be completed within a period of One Hundred Twenty (120) days from the date of issuance of allotment mentioned above.
7	The work be executed strictly in accordance with approved proposals & in close supervision of the Engineer I/C of both wings of Civil as well as Mechanical.
8	After testing and commissioning of work, the bidder will have to make a trial run of the work for a period of 03 months during which the bidder will have to operate and maintain the executed work to the full satisfaction of the Department.
9	The defects Liability period shall be for a period of 12 Months which shall commence after the successful completion of Trial run. The bidder shall be responsible to make good & remedy at his own expense any defect in works which is noticed during the DLP. In case any defect remains unattended by the firm at the completion of DLP, the department may extend the DLP for such time as deemed fit for getting the defect rectified subject to a maximum ceiling of 6 Months.
10	The bidder shall be responsible for the time and proper setting out of all the works and for the correctness of the positions, levels, dimensions and alignment of all parts of the works and for the provision of all necessary instruments, appliances and labour in connection therewith.
11	The rates are including the Charges for Submission of progress, Geo-tagged photographs, videographic record through the professional person before, during & after construction and progress reports in both hard and soft copies. Taking Cross-Sections/ L- Sections by Auto Level / ETS before and after execution. Preparation of work abstract of executed work, preparation of bills besides, the rates quoted/alloted are inclusive of taxes and the taxes viz. GST/Income tax/Cess etc. shall be deducted at source from running account bills.
12	All the Cement, R.C.C, Steel, plumbing and other works shall be strictly as per relevant IS Codes, CPHEEO norms/requirements/specifications and normal PWD practices.
13	You shall be solely responsible for carrying out the mandatory tests required or as decided by Engineer-in-charge for the quality control at your own costs. The cost of conducting all tests shall be borne by the contractor and shall be deemed to have been included in the item rates for various items of work and percentage rate tendered. Nothing extra shall be payable on this account.
14	You have to furnish the confirmatory survey, structural & functional design including geo-technical analysis, soil investigation, and quality control tests done at your level duly vetted by DIQC as per terms & conditions of the NIT. The vetting charges for the design if any are to be borne by you.
15	The allotted works shall be subject to check by the third party monitoring agency (TPIQM) appointed by the Department. The agency shall check the quality of works executed by the agencies, quality of materials used for construction and quality of machinery installed in each scheme. The TPIQM's role shall be that of an assistant to the Employer's Representative for the purpose of monitoring and evaluation of the performance of the Contract during the Contract Period.
16	Any item of work not included in the BOQ but required for the completion of the work, shall be executed by the contractor, as directed by the Department. Such extra item shall be paid at J&K SSR 2020 rates with allotted appreciation/depreciation of the contractor. In case such item does not figure in J&K SSR 2020, the same shall be paid as per the current market rate analysis, to be approved by the competent authority.
17	No price escalation will be paid for completion of the work within stipulated time or extended date of completion due to any reason whatsoever.
18	No extra claim towards any type of tax, freight, etc shall be entertained whatsoever.
19	No mobilisation advance shall be paid.


GH
HD

TO

SE

	Retention money/Security deposit shall be 10% of the contract value. The Security Deposit is to be recovered at the rate of 10% of bill amount from Running Account Bills and shall be released after completion of the defect liability period.
21	In the event of allottee failing, declining, neglecting or delaying the supplies / works or in the event of any damage occurring or being caused by the allottee or in the event of any default or failure by the allottee in complying with any of the terms and conditions of the contract, the Department shall with or without prejudice to any other remedies available to it under any law for the time being enforce in the UT: a) Terminate the contract after 15 days' notice and/or b) Recover the amount of loss caused by damage, failure or default, as may be determined by the department and/or c) Recover the extra cost, if any, involved in allotting contract to other party, and/or d) Impose Liquidated damages on account of delay beyond the schedule completion period to the tune of 0.5% of the delayed portion of contract every week but not exceeding 10% value of the contract. and/or e) Forfeit the performance security and blacklist the firm.
22	All risks of loss or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the Contract are the responsibility of the Bidder.
23	Any failure or commission to carry out the provision of the contract shall not give rise to any claim by the department or bidder one against the other if such failure of commission arises from the 'ACT OF GOD' which shall include all natural calamities such as fires, floods, earthquake, hurricane, strikes, riots, embargoes or from any political or other reasons beyond the control of the parties including war, or a state of insurgency.
24	The bidder shall in connection with the work provide and maintain at his own cost all lights, guards, fencing and watching, when and where necessary or required by the Department for the protection of the work or safety and convenience of the Public etc.
25	From the commencement of the work to the completion thereof the same shall be under the bidders charge. The bidder shall be held responsible for and make good any loss or injuries by fire or other causes / theft and shall hold the Government harmless for any claims for injuries to persons or damage to property happening from any neglect, default, want of proper care and misconduct on the part of the bidder, or any of his employees, during the execution of work. The bidder shall be responsible for the compensation if any, to labour under the existing labour laws of the country.
26	In the event of the death or insanity or insolvency or imprisonment of the bidder or where the bidder being a partnership or firm becomes dissolved or being corporation goes into liquidation, voluntary or otherwise, the contract may, in the option of the Engineer-in-charge, be terminated by notice in writing posted at the site of the works.
27	The damage caused to the work during execution or prior to actual completion of work/handling over of the project before defect liability period due to any natural calamity/human interference, the same shall be got restored/made good by you at your own cost.
28	No damage is caused to existing structures like roads, bridges, buildings or other public utilities as a result of construction of this work. Wherever any damage occurs to any public/private infrastructure or public utility, the same shall be rectified/made good by you at your own cost.
29	Adequate precautions be taken for environment and social protection besides, all safety practices in vogue be strictly adhered to during execution of work.
30	No objection certificate from the concerned regulatory authority may also be sought wherever required.
31	All other terms & conditions will remain same as laid down in the original NIT /SBD/GFR-2017/ Procurement Manual 2019/Operational guidelines for JJM.


Head Draftsman


Technical Officer,


Superintending Engineer
Hydraulic Circle Anantnag/Kulgam
HQ: Anantnag

No. SE/Hyd/Cors/ 1062457
Dated: 31/12/2022

Copy to the :-

1	Chief Engineer Jal Shakti (PHE) Department Srinagar for favour of information.
2	District Development Commissioner Kulgam (Chairman District Jal Jeevan Mission) for information. This is with reference to your Authorization order No. 350/DDCK of 2022 dated 06.08.2022 issued under endorsement No. DDCK/JJM/2022-23/3674-77 dated 06.08.2022.
3	Executive Engineer Jal Shakti, PHE Division Qazigund for information & necessary action. He will ensure the completion of work within the stipulated time period and strictly in accordance with JJM Guidelines.
4	File concerned.