

**OFFICE OF THE  
EXECUTIVE ENGINEER SPECIAL SUB DIVISION GUREZ**

Allotment Order No. 17 EE/SSDG/2022-23

Dated 07/12 /2022

M/S Munwar Khan & Sons  
Prop:-Mohammad Munwar Khan  
S/O Lal Khan R/O Bumai Tulail  
Registration No.KMR/PHED/RCR/1995-96/BEE/41 of 8/1995-95  
GSTTN No:01ARMPK8785F2ZH

Adv Cost of Work: -Rs.27.48 Lacs  
Allotted Cost:- Rs. 26,39,800.00  
(Excl. Cost of Pipes)  
Time of Completion: (12 Months)  
Major Head: - JJM

**SUBJECT:-** Laying and fitting of GI pipes including Construction of protection works/ head works at head site, Intake Chamber near head site, 0.03 lac gallon SR, Sluice Chamber, supporting pillars for RWM at spots, Chain Link fencing around structures, Cattle troughs for Retrofitting of WSS Kashpot Tulail for 100% coverage of FHTCs "Under JJM).

**Reference:-** Your tender in response to e-NIT No:- 58-EE/SSDG of 2022-23 S.No.(01) issued under No. EE/SSDG/2009-18 dated:- 03/06/2022. & Superintending Engineer Hyd. Authorization No.SE/Hyd/DB/3282-84 Dt.28-06-2022.

For and on behalf of Lt. Governor Union Territory of Jammu and Kashmir contract for the above mentioned work is fixed with you at an allotted cost of Rs.2639800/- (Twenty Six Lakh Thirty Nine Thousand Eight Hundred Rupees) (Excl. Cost of pipes) as worked out at the rates quoted/ offered/ negotiated and accepted by you against the items of the advertised rate list/ quantity schedule subject to fulfillment of the terms and condition stipulated hereunder:-

S. No	Particulars	Quantity	Unit	Alloted Rate	Amount (In Rupees)
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr. including disposal of excavated earth upto 1 mtr from cutting edge, disposed earth is to be levelled and neatly dressed in: All kinds of soil	888.23	Cum	400.00	355292.00
1.01	Ordinary rock	386.42	Cum	850.00	328457.00
2	laying and fitting of GI pipes in tenches as per IS: 1239 of 2004 and ammendments pipe (Light grade) 65mm dia pipe (Light grade)	200.00	RM	70.00	14000.00
2.01	50mm dia pipe (Light grade)	1500.00	RM	40.00	60000.00
2.02	40mm dia pipe (Light grade)	600.00	RM	40.00	24000.00
2.03	25mm dia pipe (Light grade)	1000.00	RM	30.00	30000.00
2.04	20mm dia pipe (Light grade)	1560.00	RM	20.00	31200.00
2.05	15mm dia pipe (Light grade)	1250.00	RM	20.00	25000.00
3	Making connection of G.I distribution branch with G.I main of following sizes by providing & fixing of Tee including cutting & threading the pipe etc. Complete: 15mm dia nominal bore FHTC,s to household including cost of water meter and bibcocks.	34.00	No	1400.00	47600.00
4	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. Layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering lead upto 50m and lift upto 1.5m.	1016.76	Cum	180.00	183016.80
5	Providing/fixing of regulating devices including all carriages complete: 65mm dia Sluice valve	3.00	No	7000.00	21000.00
5.01	50mm dia Sluice valve	3.00	No	5000.00	15000.00

Head Draftsman

contd. On 2<sup>nd</sup>

Executive Engineer

ECT:-

.../laying and fitting of GI pipes including Construction of protection works/ head works at head site, Intake Chamber near head site, 0.03 lac gallon SR, Sluice Chamber, supporting pillars for RWM at spots, Chain Link fencing around structures, Cattle troughs for Retrofitting of WSS Kashpot Tulail for 100% coverage of FHTCs "Under JJM).

6	P/fixing of MS control valve chamber size 0.60x0.60x0.60 fabricated out of 5mm thick MS plate including hire charges of DG set, generator, welder and all carriages complete job. (2No)	2.00	No	10000.00	20000.00
7	Providing and laying of stone soling (hand packed).	11.35	Cum	600.00	6810.00
8	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	10.18	Cum	4900.00	49882.00
9	Providing/laying in position specified grade of reinforced cement concrete including curing but excluding cost of centering, shuttering, finishing & reinforcement. All works upto plinth level 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size) : Base/Raft	11.28	Cum	7900.00	89112.00
9.01	Walls	30.70	Cum	9500.00	291650.00
9.02	Slab/Ring beam	3.58	Cum	9900.00	35442.00
9.03	Dome	1.15	Cum	10500.00	12075.00
10	Providing/laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing & reinforcement. All works upto plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	12.72	Cum	7000.00	89040.00
11	Mild Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding wire.	4817.44	Kgs	95.00	457656.80
12	Providing and fixing of MS main hole cover of 0.75 x 0.75 size fixed with 50x60 MM ISA	5.00	No	3000.00	15000.00
13	Centering and shuttering including strutting, propping etc. and removal of form work in: Bases/Raft	65.28	Sqm	260.00	16972.80
13.01	Walls	232.06	Sqm	570.00	132274.20
13.02	Slab	16.43	Sqm	630.00	10350.90
13.03	Ring beam	4.77	Sqm	500.00	2385.00
13.04	Domes	7.55	Sqm	2080.00	15704.00
14	Providing and mixing of water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specifications.	69.52	Kgs	66.00	4588.32
15	12 mm thick cement plaster in 1:4 mix (1 cement : 4 coarse sand)	25.43	Sqm	260.00	6611.80
16	Structural steel work welded in built up sections framed work including cutting hoisting fixing in position and applying a priming cost of steel primer	348.98	Kgs	105.00	36642.90
17	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete (G.I. wire of dia 4 mm) complete job	21.84	Sqm	800.00	17472.00
19	Providing and fixing of mild steel round holding down bolts with nuts and washers and plates complete.	16.00	Kgs	93.00	1488.00
20	Carriage of material by M/T Incl loading, unloading and stacking complete job				
20.01	Steel/Cement from nearest source	30.65	M.T	300.00	9195.00
20.02	Sand from nearest source	29.90	Cum	250.00	7475.00
20.03	Aggregate from nearest source	55.82	Cum	270.00	15071.40
20.04	Stone/Soling from nearest source	11.35	Cum	300.00	3405.00
20.04	Pipes from Divisional Store	14.65	M.T	320.00	4688.00

Head Draftsman

MS. S. S. S.

contd. On 3<sup>rd</sup>

Executive Engineer

**ECT:-** Laying and fitting of GI pipes including Construction of protection works/ head works at head site, Intake Chamber near head site, 0.03 lac gallon SR, Sluice Chamber, supporting pillars for RWM at spots, Chain Link fencing around structures, Cattle troughs for Retrofitting of WSS Kashpot Tulail for 100% coverage of FHTCs "Under JJM).

21	Carriage by Mannual Transport. Steel/Cement	30.65	M.T	1010.00	30956.50
21.01	Sand	29.90	Cum	1100.00	32890.00
21.02	Aggregate	55.82	Cum	1100.00	61402.00
21.03	Stone soling	11.35	Cum	1200.00	13620.00
21.04	Pipes	14.65	M.T	1050.00	15382.50
<b>Total in Figures</b>				<b>Rs.2639800/- (Twenty Six Lakh Thirty Nine Thousand Eight Hundred Rupees)</b>	

**TERMS AND CONDITIONS:-**

01. This letter of allotment will constitute a legal contract between the government and the contractor and the conditions as laid down in the master e-NIT for 2022-23 and PWD Form No. 25 (Double) will also hold good even before the drawl of an agreement between the Government and the contractor.
02. That the date of start of the work shall be reckoned within Two days from the date of issue of allotment and in case of delay on the part of the contractor in execution of the work within stipulated time of completion a penalty upto 10% of contract value shall be imposed upon him.
03. The contractor has deposited an amount of Rs.24200/ bearing No.3058441 dated 31/10/2022 & No.3154724 Dt.16-06-2022 Rs.5000/-in shape of earnest money (CDR)/TDR through J&K Bank Branch Dawar Gurez . which has been retained in the divisional office and shall only be released after the successful completion / commissioning of work and after observing the DLP period is over.
- 4.1 he contractor has to strictly follow the quality Control measures as per relevant IS code. The sampling of concrete has to be done by the contractor in presence of JE/Engineer Incharge and has to get tested the sample from reputed laboratory approved by the Govt. of J&K.
- 4.2 The department shall not be responsible for any site/ land dispute arising if any unforeseen circumstances.
- 4.3 The contractor has to get Hydraulic Structural design of various structures from the reputed consultants and have to get it verified from design Directorate Srinagar.
05. The GI Pipe class LA as per IS 1239 part ist is to be checked / tested by CEIL/RIET and subsequently by third party fixed by the Chief Engineer.
06. The allotment order No. and name of the executing agency must be mentioned on the pipe bill/inspection note and original copies must be submitted to this Office.
07. The Socket drift certificate must be inspected by CEIL / RIET .
08. The pipe must be dumped and properly stacked dia wise at a proper site as per the consent of Engineer Incharge.
09. The payment of the work shall be made as and when the funds are made available by the competent authority under the proper scheme / account head.
10. The Contractor shall attend the divisional office within 03 days after the issue of this allotment order for drawl of the agreement with the department.
11. Nothing shall be paid to the contractor on account of dewatering/ diversion even if involved at site of work.
12. The mileage for carriage of materials by mechanical transport / by manual labour as advertised/ allotted shall be final and nothing shall be allowed beyond allotted.
13. If the Contractor does not start the work within 15 days of issue this allotment order, the allotment shall be cancelled at the risk & cost of contractor without serving any notice. The Astt. Executive Engineer concerned shall intimate this office regarding the same.

No: -EE/SSDG/ 8484-91  
 Dated: 07/12/2022  
 Head Draftsman  
 MS Paleel

Executive Engineer  
 Special Sub Division  
 Gurez

**Copy to the:-**

01. Chief Engineer Kashmir Jal Shakti PHE Department Srinagar for favour of information
02. District Development commissioner( chairman JJM Bandipora) for favour of information
03. Superintending Engineer Hydraulic Circle Bla/ Bpr H.Q Sopore for favour of information.
04. Technical Officer to Mission Director JJM for favour of information
05. Assistant Executive Engineer (JSD) PHE Sub-Division Gurez for Information & necessary action.
- 06-08. AAO/Head Assistant/ Head Draftsman Divlsonal Office for information.
09. Concerned File