



Union Territory of Jammu & Kashmir

Office of the Executive Engineer (R&B) Division Gurez

Allotment Order No. 20 /EE/SSDG/2023-24

Dt- 30 / 08 /2023

The Assistant Executive Engineer
(PHE) Sub Division Gurez

Head of Account-
JJM

Subject: Laying and fitting of GI pipes including Construction of protection works/ head works at head site, Intake Chamber near head site, 0.02 lac gallon SR, Sluice Chamber, supporting pillars for RWM at spots, cattle trough for Retrofitting of WSS Check Bayant Tulail for 100% coverage of FHTCs "Under JJM)

Reference:- This office e-NIT No:- 10/EE/SSDG of 2023-24 S.No.(04) issued under No EE/SSDG/324-33 dated:- 20/04/2023. & L.O.I No.EE/SSDG/2508-10 Dt.07-07-2023 & Member of Secretary DJJM Superintending Engineer Hyd.Circle Bla/Bpr H.Q Sopore's No.SE/Hyd/DB/3885-98 Dt.06-07-2023.

For and on behalf of the Lt Governor of UT Jammu & Kashmir, the Executive Engineer Spl. Sub Division Gurez hereby fixes the contract for above named work in favour M/S G.M Construction Prop:- Ghulam Murtaza Malik S/o:-Ghulam Mohammad Malik R/O Sonerwani Bandipora Regd. No:-SE(R&B)SB-B-2105 of 2019-20 GSTIN No:01BJBPM9294H1Z4 on the rates as per Annexure (A) forming part of this allotment letter.

The contract shall be Governed by the terms and conditions of the tender notice referred to above and also by the terms and condition of the detailed tender notice which is in vogue in this Division

The contractor should be directed to attend the Divisional office along with his valid registration card duly renewed for making necessary entry therein within a week's time & draw of necessary agreement with the Department. The tender submitted by the contractor, floated tender notice and this allotment order shall constitute a legal contract document even before draw of formal agreement deed & in the event of contractor's failure to do so he shall be responsible for the resultant consequences.

The performance security deposited by the contractor in shape of the CDR bearing No. 3447787 dated 25-08-2023 worth Rs. 58000 issued by the J&K Mini Sect. Bandipora is retained in this office till successful completion of work for defect liability period.

The date of start of work shall be reckoned after 3 days from the date of issue of letter of intent/ allotment order

The time of completion of work shall be (40)days.

The cost on allotted rates works out of Rs. 1932000 / (Nineteen Lakh Thirty Two Thousand Rupees only)(Excl'd. Cost of pipes) against the advertised cost of Rs.19.32 Lacs.

Note:-)

I)The work shall have to be executed strictly as per the items advertised and proposals, in no case should thereby deviation in any item/ items of work or to execute any item beyond the rate list or exceed the quantities.

II)In case the contractor fails to execute the work the CDR/earnest money deposited by the contractor will be forfeited in first instance, besides the contractor will be recommended for black listing or debarred from contracts in P.W.D especially in this division for at least one year

III) In case of any delay caused in execution of works penalty upto 10% shall be imposed upon the contractor or the Department shall be at the liberty to terminate the contract in or full(as the case may be) and the contract shall be completed through some other available sources at the risk and cost of the defaulting agency after serving not more than two notices which should be strictly noted.

IV) The control of the budget allocation which include the cost of key construction material shall be sole responsibility of the concerned Assistant Executive Engineer and shall not exceed under any circumstances except from the proper approvals from the competent authority and the AEE concerned will make it sure that no liability is created on this account is ensured

V) The AEE concerned will make it sure that Geo-tagged photographs showing before execution, during execution and after execution of work is enclosed with every claim

VI). The rates shall include the charges on account of Geo-tagged Photographs etc.

VII) Service tax plus surcharges as required under rules framed by Govt. should be deducted from the bills of the contractor. In case Govt. increases the rates of service tax, the contractor has to pay the same at his own cost. No claim whatsoever will be entertained on this account.

VIII) The defect liability will be (18) months from the date of actual completion of the contract.

IX) The Department shall not be responsible for any site dispute which may occur during the execution of work

No.EE/SSDG/ 4857-61

Dated: 30-08-2023 Head Draftsman

Executive Engineer
(R&B) Division Gurez

Copy to the:

1. Superintending Engineer (Hyd) Circle Baramulla H.Q Sopore for favour of information
- 2 M/S G.M Construction Prop:- Ghulam Murtaza Malik S/o:-Ghulam Mohammad Malik R/O Sonerwani Bandipora for information & r/a
- 3). Head Draftsman Drawing Branch Divisional Office for information.
- 4). Head Assistant Divisional Office for information.

(Contd..on..page..2nd)

(Page..2nd) Name of the Work: Laying and fitting of GI pipes including Construction of protection works/ head works at head site, Intake Chamber near head site, 0.02 lac gallon SR, Slake Chamber, supporting pillars for RWM at spots, cattle trough for Retrofitting of WSS Check Bayant Talail for 100% coverage of FHTCs "Under JJM)

Sl. No.	Item Description	Qty	Unit	Rate Quoted By The Bidder (L1) Rate in Rs. P	Percentage of Quantity by Tenderer
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10sqm on plan, depth upto 1.5mtr. Including disposal of excavated earth upto 1 mtr from cutting edge, disposed earth is to be levelled and neatly dressed in: All kinds of soil	638.04	Cum	436.00 (Four Hundred Thirty Six Rupees)	
1.01	Ordinary rock	273.56	Cum	967.00 (Nine Hundred Sixty Seven Rupees)	
2	laying and fitting of GI pipes in trenches as per IS: 1239 of 2004 and amendments pipe (Light grade) 50mm dia pipe (Light grade)	200.00	RM	40.80 (Forty Rupees and Eighty Paise)	
2.01	40mm dia pipe (Light grade)	1090.00	RM	40.80 (Forty Rupees and Eighty Paise)	
2.02	25mm dia pipe (Light grade)	1050.00	RM	30.65 (Thirty Rupees and Sixty Five Paise)	
2.03	20mm dia pipe (Light grade)	1100.00	RM	20.25 (Twenty Rupees and Twenty Five Paise)	
2.04	15mm dia pipe (Light grade)	1036.00	RM	20.25 (Twenty Rupees and Twenty Five Paise)	
3	Making connection of G.I distribution branch with G.I main of following sizes by providing & fixing of Tee including cutting & threading the pipe etc. Complete: 15mm dia nominal bore FHTCs to household including cost of water meter and bibcocks.	25.00	No	1500.00 (One Thousand Five Hundred Rupees)	
4	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. Layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering lead upto 50m and lift upto 1.5m.	711.06	Cum	198.70 (One Hundred Ninety Eight Rupees and Seventy Paise)	
5	Providing/fixing of regulating devices including all carriages complete: 65mm dia Sluice valve	3.00	No	8000.00 (Eight Thousand Rupees)	
6	50mm dia Sluice valve	3.00	No	5000.00 (Five Thousand Rupees)	
7	P/fixing of MS control valve chamber size 0.60x0.60x0.60 fabricated out of 5mm thick MS plate including hire charges of DG set, generator, welder and all carriages complete job. (2No)	2.00	No	10000.00 (Ten Thousand Rupees)	
8	Providing and laying of stone soling (hand packed).	8.09	Cum	616.40 (Six Hundred Sixteen Rupees and Forty Paise)	
9	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	5.97	Cum	4910.94 (Four Thousand Nine Hundred Ten Rupees and Ninety Four Paise)	

(Contd..on..page..3rd)

Head Draftsman

Executive Engineer
(R&B) Division Durez

@ At Par on the advertised rates for all items of work

(Page..3rd) Name of the Work: Laying and fitting of GI pipes including Construction of protection works/ head works at head site, Intake Chamber near head site, 0.02 lac gallon SR, Sluice Chamber, supporting pillars for RWM at spots, cattle trough for Retrofitting of WSS Check Bayant Talali for 100% coverage of FHTCs *Under JJM)

10	Providing/laying in position specified grade of reinforced cement concrete including curing but excluding cost of centering, shuttering, finishing & reinforcement. All works upto plinth level 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size) : Base/Raft	7.72	Cum	7979.55 (Seven Thousand Nine Hundred Seventy Nine Rupees and Fifty Five Paise)
10.01	Walls	15.54	Cum	9503.16 (Nine Thousand Five Hundred Three Rupees and Sixteen Paise)
10.02	Slab/Ring beam	1.75	Cum	9948.83 (Nine Thousand Nine Hundred Forty Eight Rupees and Eighty Three Paise)
10.03	Dome	0.85	Cum	10509.61 (Ten Thousand Five Hundred Nine Rupees and Sixty One Paise)
11	Providing/laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing & reinforcement. All works upto plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	9.88	Cum	7049.16 (Seven Thousand Forty Nine Rupees and Sixteen Paise)
12	Mild Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding wire.	2933.88	Kgs	93.23 (Ninety Three Rupees and Twenty Three Paise)
13	Providing and fixing of MS main hole cover of 0.75 x 0.75 size fixed with 50x60 MM ISA	4.00	No	3000.00 (Three Thousand Rupees)
14	Centering and shuttering including strutting, propping etc. and removal of form work in: Bases/Raft	73.67	Sqm	262.30 (Two Hundred Sixty Two Rupees and Thirty Paise)
14.01	Walls	122.26	Sqm	573.85 (Five Hundred Seventy Three Rupees and Eighty Five Paise)
14.02	Slab	3.89	Sqm	635.60 (Six Hundred Thirty Five Rupees and Sixty Paise)
14.03	Ring beam	4.01	Sqm	502.85 (Five Hundred Two Rupees and Eighty Five Paise)
14.04	Domes	5.60	Sqm	2086.80 (Two Thousand Eighty Six Rupees and Eighty Paise)
15	Providing and mixing of water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specifications.	146.68	Kgs	66.58 (Sixty Six Rupees and Fifty Eight Paise)
16	12 mm thick cement plaster in 1:4 mix (1 cement : 4 coarse sand)	25.65	Sqm	260.00 (Two Hundred Sixty Rupees)
18	Providing and fixing of mild steel round holding down bolts with nuts and washers and plates complete.	38.00	Kgs	93.23 (Ninety Three Rupees and Twenty Three Paise)

@ At Par on the advertised rates for all items of work

(Contd..on..page..3rd)

Balwinder
Head Draftsman

Executive Engineer
(R&B) Division Gurez


(Page..3rd) Name of the Work: Laying and fitting of GI pipes including Construction of protection works/ head works at head site, Intake Chamber near head site, 0.02 lac gallon SR, Sluice Chamber, supporting pillars for RWM at spots, cattle trough for Retrofitting of WSS Check Bayant Tulail for 100% coverage of FHTCs "Under JJM)

19	Carriage of different materials from source to Road site of by MT. Incl. loading and unloading & stacking, Steel/Cement 25 Km	12.79	M.T	349.39 (Three Hundred Forty Nine Rupees and Thirty Nine Paise)
19.01	Sand 25 Km	17.81	M.T	393.03 (Three Hundred Ninety Three Rupees and Three Paise)
19.02	Aggregate 25 Km	38.34	Cum	427.21 (Four Hundred Twenty Seven Rupees and Twenty One Paise)
19.03	Stone/Soling 25 Km	8.09	Cum	462.37 (Four Hundred Sixty Two Rupees and Thirty Seven Paise)
19.04	Pipes 25 Km	8.99	Cum	349.39 (Three Hundred Forty Nine Rupees and Thirty Nine Paise)
20	Carriages of materials by H/L from road site upto actual site of work. Cement 3500 Mtr	6.40	M.T	1175.93 (One Thousand One Hundred Seventy Five Rupees and Ninety Three Paise)
20.01	Steel 3500 Mtr	6.40	M.T	2526.12 (Two Thousand Five Hundred Twenty Six Rupees and Twelve Paise)
20.02	Sand 3500 Mtr	17.81	Cum	2924.58 (Two Thousand Nine Hundred Twenty Four Rupees and Fifty Eight Paise)
20.03	Aggregate 3500 Mtr	38.34	Cum	3161.56 (Three Thousand One Hundred Sixty One Rupees and Fifty Six Paise)
20.04	Stone soling 3500 Mtr	8.09	Cum	3440.48 (Three Thousand Four Hundred Forty Rupees and Forty Eight Paise)
20.05	Pipes 3500 Mtr	8.99	M.T	1482.90 (One Thousand Four Hundred Eighty Two Rupees and Ninety Paise)

At Par on the advertised rates for all items of work

(Rates & Quantities checked)


Head Draftsman


Executive Engineer
(R&B) Division Gurez