

OFFICE OF THE EXECUTIVE ENGINEER (JSD) PHE DIVISION

BARAMULLA

Email: kmrphela@gmail.com (FAX) 01952234575 (Tel) 01952234244

Page No:
108



No. 6605-16

dt. 15-9-2022

M/s. Buhroo Mechanical Pvt. Ltd
R/o. Azad Gunj Baramulla
Regd No.

Sub: Laying fitting of pipes, constt. of chain link fencing, renovation /improvements to PST for WSS Brandub under JJM.

Ref: 1/- Constitution of District JalJeevan Mission, Administrative Council DecisionNo: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.

2/- UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).

3/- Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.

4/- Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.

5/- District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No. SE/Hyd/DB/7137-49 dated 07.09.2022.

6/- Your tender received in response to this office ENIT No: 39 of 2022 (S.No 13).

1/- Amount of work advertised: 6268000.00

2/- Allotted cost of work: 6174019.00

(Rupees Sixty One Lacs Seventy Four Thousand & Nineteen Only)

3/- Time of completion: (90 days)

For and on behalf of Lt. Governor of Jammu and Kashmir Union Territory, the above noted work is hereby allotted to you on quoted rates given in the Annexure "A" t this allotment, on the terms and conditions given here under :


Conditions:

01. Time of completion is essence of the contract.
02. The work shall have to be started by you at site immediately & ensure its successful completion within a period of 90 days from the date of issuance of allotment from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
03. An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
04. The allotted works shall be subject to Check by the third party monitoring agency appointed by the Department.
05. Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
06. Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
07. The firm shall be bound for satisfactory performance of works for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise, you shall have to rectify the same within a period of 10 days of receipt of

2

7-2-22

- intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
08. After testing and commissioning of works you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
 09. The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
 10. Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
 11. Date of start of the work within 07 days from the date of issue of this letter. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
 12. All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
 13. Any rules/ terms and conditions if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.


Technical Officer to
Executive Engineer
PHE Division Baramulla

(Encl: Annexure "A")


Executive Engineer
Jal Shakti Department
PHE Division Baramulla

Copy to the :-

- 1/- Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srinagar/ Jammu for information.
- 2/- Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3/- District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4/- Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No: 2105-14 Dated: 04-06-2022.
- 5/- Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6/- Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7/- Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8/- Chief Planning Officer Baramulla (Member DJJM) for information.
- 9/- Chief Medical Officer Baramulla (Member DJJM) for information.
- 10/- District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla (Member DJJM) for information.
- 11/- District Information Officer Baramulla (Member DJJM) for information.
- 12/- File Concerned.

Comp. by: ShahidFarooq (Correspondence)


-1.50%

Annexure "A"

of work:

fitting of pipes, constt of chain link fencing, renovation /improvements to PST for WSS Brandub under JJM

No	Description of Work / Item(s)	No.of Qty	Units	Allotted Rate	Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed:All kinds of soil	2224.8000	Cum	429.460	955462.60
2	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: Ordinary rock	556.200	Cum	953.332	530243.397
3	Earth work in excavation by manual means over areas (exceeding 30cms and upto 1.5 mtr in width as well as 10sqm on Plan) including disposal of excavation earth upto 1mtr for cutting edge, disposal earth to be levelled and neatly dressed in all kinds of soil Ordinary rock	87.500	Cum	531.260	46485.2281
4	Laying & fitting of G.I. pipes complete with G.I. fittings excluding trenching and refilling etc. (external work)			0.000	
4.1	80 mm dia. nominal bore	2500.000	Mtr	71.954	179885.62
4.2	65 mm dia. nominal bore	2000.000	Mtr	71.954	143908.
4.3	50 mm dia. nominal bore	1100.000	Mtr	40.188	44206.
4.4	40 mm dia. nominal bore	3000.000	Mtr	40.188	12056
4.5	25 mm dia. nominal bore	3000.000	Mtr	30.190	90570.7
4.6	20 mm dia. nominal bore	3500.0000	Mtr	19.946	69811.87
4.7	15 mm dia. nominal bore	1500.000	Mtr	19.946	29919.37
5	Laying in position centrifugally cast (spun) iron S&S or flanged pipes(excluding cost of pipe)K7 100mmdia D.I	850.950	Qtl	241.867	205816.510
6	Providing push-on-joints to Centrifugally (Spun) Cast Iron S&S including testing of joints and including the cost of rubber gasket	818.000	NO	88.35 805.730	72270.3 659087.1
7	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	2572.920	Cum	195.720	503570.615
8	Making connections of GI distribution branch with GI mains of following size by providing and fixing tee , including cutting and threrading the pipe etc. complete			0.000	
8.1	25 to 40mmØ	5.0000	NO	656.256	3281.2812
8.2	40 to 80mmØ	8.000	NO	1249.719	9997.7
9	Providing and laying DI specials of class K-12 suitable for push on jointing as per IS: 9523Upto 600mmØ	10.000	Kgs	167.450	1674.
10	Providing and fixing D.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately). Confirming to IS:14846 read with latest amendments.			0.000	

62  Page 1 of

	Description of Work / Item(s)	No. of Qty	Units	Allotted Rate	Amount
	100mmØ sluice valve	2.000	each	12966.540	25933.0
	Providing and fixing gun metal gate valve with C.I. wheel of approved quality incl. all necessary accessories as complete job.			0.000	
11.1	25 mm nominal bore	7.000	No	535.692	3749.8457
11.2	40 mm nominal bore	5.0000	No	694.130	3470.647
11.3	50 mm nominal bore	8.000	No	928.609	7428.8
11.4	65 mm nominal bore	10.000	No	1545.317	15453.172
12	Providing and fixing C.I. double acting air valve of approved quality with bolts, nuts, rubber insertions etc. complete (The tail pieces, tapers etc. if required will be paid separately).			0.000	
12.1	50mmØ Double acting	10.000	No	5069.943	50699.427
12.2	80mmØ Double acting	8.000	No	6137.387	49099.09
12.3	100mmØ Double acting	6.000	No	8061.485	48368.917
13	Providing and fixing of MS surface boxes (0.75x0.75x0.75) of 6mm thick plate for sluice valves. The job includes fixing of angle iron frame legs in cement concrete 1:2:4 mix with locking arrangements complete.	5.000	Kg	6895.000	34475
14	Providing & fixing of MS bends of required dia and Tee's including carriage of welding machine upto site of work and fixing at site including cost of rubber gaskets/washers/nuts & bolts etc as complete job.	200.0000	Kg	206.850	41370
15	Providing and fixing DI tail piece male/female to DI/CI pipes one side socketed and one side flanged including all sorts of carriages upto site of work complete job.			0.000	
15.1	100mmØ DI	8.000	No	3940.000	31520
16	Providing and laying hand packed stone soling 50 mm nominal size including filling, spreading, dressing, ramming, all leads lifts and all carriages complete.	21.500	Cum	1300.200	27954
17	Clearance of dry slit	6.480	Cum	99.436	644.3436
18	For Extra/ Additional Left for 1.5 to 3.0 M	6.4800	Cum	80.425	521.1556
19	Providing and laying in position cement concrete 1:4:8 Mix	14.660	Cum	4788.903	70205.3113
20	Providing and laying in position cement concrete 1:2:4 Mix	90.000	Cum	6466.712	582004.093
21	Providing and laying in position cement concrete 1:1.5:3 Mix	8.590	Cum	7683.749	65003.4004
22	Structural steel work in single section trusses and faced walls	4757.920	Kg	104.174	495649.654
23	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia 4 mm	457.500	Sqm	722.498	330542.606
24	Providing and fixing of Grill gate fitted on 100mm dia pipe poles of required design incl. fixing of Nuts and bolts other related items. All work complete job	325.000	Kg	94.708	30780.0187
25	12mm thick cement plaster 1:4 (mix)	264.320	Sqm	256.149	67705.3697
26	Applying priming coat: With ready mixed red oxide Zinc Chromate primer of approved brand and manufacture on steel galvanized iron/steel works.	473.2600	Sqm	51.959	24589.9980
27	Painting two or more coats of synthetic enamel paint of approved brand and manufacture.	15.760	Sqm	78.899	1243.4403
28	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete	601.440	kgs	85.862	51641.1119
29	Centring, shuttering, strutting and propping etc and foundation, footing bases of column			0.000	
29.1	Walls	514.320	sqm	565.242	290715.394

Description of Work / Item(s)	No.of Qty	Units	Allotted Rate	Amount
Carraige of Material by Mech. Transport 35Kms			0.000	
1 below 100mm Pipes	54.839	M.Ton	306.046	16783.2782
2 DI 100mm Dia	4500.000	Mton	11.840	53278.6
30.3 Cement /steel for 35kms	27.055	M.Ton	482.650	13058.0957
30.4 Sand 35 kms	48.770	Cum	543.060	26485.0386
30.5 Stone Aggregate 40mm 35 km	13.190	Cum	590.281	7785.80573
30.6 Stone Aggregate below 40mm 35km	88.730	Cum	543.257	48203.1980
30.7 Stone Soling 15 kms	21.500	Cum	395.803	8509.75482
31 Carraige of Material by Manual labour lead= 400m			0.000	
31.1 100mm Dia DI	4500.000	M.Ton	8.195	36878.
31.2 Below 100mm GI Pipes	54.840	M.Ton	306.040	16783.2061
Total				6174019.6
(Rupees Sixty One Lacs Seventy Four Thousand & Nineteen Only)				

Rates & Qty checked by:

 Head Draftsman

 Technical Officer

 Executive Engineer
PHE Division Baramulla