

OFFICE OF THE EXECUTIVE ENGINEER PHE, DIVISION BIJBEHARA

M/s Mushtaq Amad Vaid	No/PHB: 5109-94
S/o Gh Mohd Vaid	Dated: 15-07-2023
R/o Bijbehara	GST. No:- 01ADZPV4772G1ZY

Regd. No:- 81-DEE-DSEA-1988-89

Tender ID: 2023_PHE_217594_2 (DSC Parvaiz Ah Malik)

Adv. Cost Rs: 7.08 Lacs

Alloted Cost Rs: 5.367 Lacs

Subject:- L/f of pipes ,Plastering of existing SR & Improvements to existing pipe network for WSS Gawran under JJM.

Reference

1.Your tender received in response to this office : e-NIT No.35 OF 2023-24 issued under NO/PHE/4083-93 Dated:19.06.2023

02-4. DJJM /District Development Commissioner Anantnag's Authorization No:DDCA/JJM/2022-23/3858-60 Dated: 30.07.2022 , No/DDCA/DJMM/9413 Dt: 04.11.22 and No/DDCA/JJM/12613 Dated:03.02.2023

05. Superintending Engineer Hyd.Circle Anantnag's Authrozation Letter No:SE/Hyd/4590 Dated: 03.08.2022

06. Superintending Engineer Hyd.Circle Anantnag's Authrozation Letter No:SE/Hyd/8445 Dt: 10.11.2022

Sl.No	Description of Work / Item(s)	Qty	Units	Estimated Rate	Amount
1	Dismantling old plaster or skirting, raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 meters lead.	50.89	Sqm	35.35	1798.962
2	12mm Cement plaster finished with a floating coat of neat cement of mix				
3	1 : 3 (1 cement : 3 fine sand)	50.89	Sqm	343.75	17493.438
4	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/by mechanical means including stacking of pipes within 50 meters lead as per direction of Engineer-in-charge :				
5	15 mm to 40 mm nominal bore.	390	Mtr.	99.75	38902.5
6	Above 40 mm nominal bore	384	Mtr.	110.65	42489.6
7	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed (1 meter from cutting edge)				
8	All kinds of soil	611.84	Cum	436	266762.24
9	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes, fittings and Earth work.				

(Handwritten Signature)

L/f of pipes, Plastering of existing SR & Improvements to existing pipe network for WSS Gawran under JJM.

Subject:-	500	Mtr.	20.25	10125
10	15 mm dia. G.I. pipes	1680	20.25	34020
11	20 mm dia. G.I. pipes	944	30.65	28933.6
12	25 mm dia. G.I. pipes	668	40.8	27254.4
13	40 mm dia. G.I. pipes	426	40.8	17380.8
14	50 mm dia. G.I. pipes	290	73.05	21184.5
15	80 mm dia. G.I. pipes			
16	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete			
17	50 to 80 mm nominal bore	6	1268.75	7612.5
18	25 to 40 mm nominal bore	70	666.25	46637.5
19	Providing and fixing D.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately). Confirming to IS:14846 read with latest.amendments.			
20	150 mm dia Sluice valve	1	20243	20243
21	80 mm dia Gate valve	1	10815	10815
22	Filling available excavated earth (excl.d. rock) in trenches plinth sides of foundation etc. in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming & watering lead upto 50 m, & lift upto 1.5 m.	550.65	198.7	109414.155
23	Carriage of pipes from divisional store bejbera to dumping site on road by MT			
24	Below 100 mm G.I Pipes (30 kms)	8.26	445	3675.7
25	By Manual Labour including loading, unloading and stacking Avg. 600 mtr			
26	Below 100 mm G.I Pipes	8.26	400.68	3309.617

Total Amount	708052.51
Deduct @24.19% of all items	171277.90
Alloted Amount after the deductions	536774.609
Amount Alloted	5.367 lacs

Rates & Qty Checked

Head
Draftsman

Technical Officer

Executive Engineer
Jan Shakti PHE Division Bijbehara

Subject:- L/f of pipes, Plastering of existing SR & Improvements to existing pipe network for WSS Gawran under JJM.

Terms & Conditions

1	The cost of work should in no case exceed beyond Rs. 5.367 Lacs Rupees Five lac thirty six thousand and seven hundred only
2	The work shall have to be completed within a period of 20 days , from the date of issuance of this allotment order failing which penalty upto 10% of the total value of contract shall be imposed upon you.
3	Earnest money deposited by you vide GDR NO: 3454151 Dated 22/10/2023 @ 21500/= JAK Bank Jabalpur , successful completion of the work and expiry of defect clause.
4	Client/Paying Authority: The client/paying authority shall be the concerned Executive Engineer. Besides, the supervision of the various components of the work shall be carried out by the concerned Engineers of the Division/TPQM consultants under the overall coordination of the concerned Superintending Engineer Hydraulic Circle/Executive Engineer/Assistant Executive Engineer.
5	Terms of Payment: Payment can be claimed on a monthly basis subject to the amount of bill being proportionate to the value of work viz a viz completion period within a variation of -5%.
6	Warranty: The firm shall be bound for satisfactory performance of works for 18 months after the successful commissioning of subject work. If during warranty period any malfunctioning/ defects arise, the firm /joint venture shall have to rectify the same within a period of ten days of receipt of intimation. In case of any failure on the part of the firm/joint venture to remove the defect, the Department may get the defects removed/ repaired by any other agency and cost thereof shall be recovered from the firm / joint venture and shall be recommended for further punitive action as governed under the relevant clause of the contract including blacklisting.
7	Trial Run: After testing and commissioning of work, the bidder will have to make a trial run of the work for a period of 03 months during which the bidder will have to operate and maintain the executed work to the full satisfaction of the Department.
8	Defects Liability Period (DLP): The defects Liability period shall be for a period of 12 Months which shall commence after the successful completion of Trial run. The bidder shall be responsible to make good & remedy at his own expense any defect in works which is noticed during the DLP. In case any defect remains unattended by the firm at the completion of DLP, the department may extend the DLP for such time as deemed fit for getting the defect rectified subject to a maximum ceiling of 6 Months.
9	Liquidated damages (LD) In the event of allottee failing, declining, neglecting or delaying the supplies / works or in the event of any damage occurring or being caused by the allottee or in the event of any default or failure by the allottee in complying with any of the terms and conditions of the contract, the Department shall with or without prejudice to any other remedies available to it under any law for the time being enforce in the UT: a) Terminate the contract after 15 days notice and/or b) Recover the amount of loss caused by damage, failure or default, as may be determined by the department and/or c) Recover the extra cost, if any, involved in allotting contract to other party. and/or d) Impose Liquidated damages on account of delay beyond the schedule completion period to the tune of 0.5% of the delayed portion of contract every week but not exceeding 10% value of the contract. and/or e) Forfeit the performance security and blacklist the firm.
10	Force Majeure: Any failure or commission to carry out the provision of the contract shall not give rise to any claim by the department or bidder one against the other if such failure of commission arises from the 'ACT OF GOD' which shall include all natural calamities such as fires, floods, earthquakes, hurricane, strikes, riots, embargoes or from any political or other reasons beyond the control of the parties including war, or a state of insurgency.
11	Specifications of job: Tenderer/s must execute the works as per the requirements/specifications detailed in the relevant/applicable IS code/s
12	Bidder Dying, Becoming Insolvent Or Imprisoned: In the event of the death or insanity or insolvency or imprisonment of the bidder or where the bidder being a partnership or firm becomes dissolved or being corporation goes into liquidation, voluntary or otherwise, the contract may, in the option of the Engineer-in-charge, be terminated by notice in writing posted at the site of the works, communications/ instructions.
13	Safety of Govt. Infrastructures: The bidder should ensure the safety of the water supply lines, sewer lines, telephone cables, power cables, storm water drains etc., pipe laying alignment and, if any damage occurs during execution it should be attended immediately at the cost of the bidder. Failing to attend immediately, the same will be got done by the Department at the risk and cost of the allottee.
14	Allottee's risk and insurance: All risks of loss or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the Contract are the responsibility of the Bidder.

Subject:-	L/f of pipes, Plastering of existing SR & Improvements to existing pipe network for Gawran under JJM.
15	Work under Bidders Charge: From the commencement of the work to the completion thereof the same shall be under the bidders charge. The bidder shall be held responsible for any claims for injuries to persons or damage to property happening from any neglect, default, want of proper care and misconduct on the part of the bidder, or any of his employees, during the execution of the work. The bidder shall be responsible for the compensation if any, to labour under the existing labour laws of the country.
16	Setting Out of Works: The bidder shall be responsible for the time and proper setting out of all the works and for the correctness of the positions, levels, dimensions and alignment of all parts of the works and for the provision of all necessary instruments, appliances and labour in connection therewith.
17	Labour: The bidder shall make his own arrangements for the engagement of all types of the labour, required for the execution of the job. No workman below the age of 18 years shall be employed on the works. Also the bidder shall comply with the provisions of all labour laws and the rules framed there under.
18	Storage at Site: The bidder shall at his own cost make arrangements for proper storage especially towards Rain and Snow damages of the equipment/ materials at sites till its erection/completion. For the purpose the bidder shall, with the approval of Engineer in charge construct temporary storage accommodation for equipment/ material at site for which land shall be provided by the department near the site of work.
19	Watch & Ward of Works: The bidder shall in connection with the work provide and maintain at his own cost all lights, guards, fencing and watching, when and where necessary or required by the Department for the protection of the work or safety and convenience of the Public etc.
20	Final Acceptance: The equipment/work shall be accepted by the Department only after the system has been tested and has performed satisfactorily in all respects, at site, in accordance with the provisions of the contract.
21	Cleaning Up: On completion of the works the bidder shall clear away, load into trucks or any other transport and remove from the site all constructional plant, surplus materials, dismantled or otherwise, earth and rubbish and temporary works of every kind and leave the whole of the site and works clean and in a workmanship condition, to the satisfaction of the Department.
22	Power and Water Supply: The bidder/firm shall make his own arrangement, at his own cost, for all lines, individual power points, etc. to the machinery and plant required by him for the erection, testing and commissioning of the equipment ordered on him. The bidder shall pay for all electrical energy consumed by him for this purpose at the prevalent electricity tariff in J&K State. Such charges shall be paid by the bidder/firm directly to the Power Corporation and the bidder's final bill shall be settled only after he gets a no outstanding certificate from the concerned Electric Division. The Division shall not be responsible, and the bidder shall have no claim whatsoever for any interruption in power supply or voltage fluctuation or total cut off at the site. The bidder/firm must provide an alternative source of power, at his own cost, at the site for completion of the work. The bidder shall make his own arrangements for water to be used for the execution/Hydro-testing/ water tightness Test/ Curing, labour colony, Site Office etc.
23	Agreement: As soon as letter of award is communicated to the firm, the contract shall be complete and binding upon them, the bidder/firm shall also be required to execute an agreement with the competent authority within seven days from the date of issue of letter of award. Failure to execute such an agreement in time shall not however, prevent this contract from being enforced against the firm and the date of delivery of the material/completion of works shall be reckoned from the date of issue of the letter of award in favour of successful firm.
24	Tender quantities: <u>The advertised quantities in the tender documents are tentative and subject to increase or decrease, depending upon actual requirement at site as per the design and other considerations. The successful bidder shall have no claim/ reservation on this account and the decision of the department shall be final and binding.</u>
25	Third Party Monitoring: The allotted works shall be subject to check by the third party monitoring agency (TPIQM) appointed by the Department. The agency shall check the quality of works executed by the agencies, quality of materials used for construction and quality of machinery installed in each scheme. The TPIQM's role shall be that of an assistant to the Employer's Representative for the purpose of monitoring and evaluation of the performance of the Contract during the Contract Period.
26	All other terms and conditions as laid down in form No.25 of P.W.D. shall remain in force and binding on successful tenderer.

Copy to the :-

- 1 Chief Engineer Kmr PHE Department Srinager for favour of information please.
- 2 District Dev. Commissioner Anantnag for favour of information please
- 3 Superintending Engineer Hyd. Circle Anantnag for favour of information
Assistant Executive Engineer PHE Sub -Division Anantnag for information & necessary action. He will ensure the completion of work within the stipulated time period and strictly in accordance with approved proposals, besides the amount of work does not exceed beyond the provision of allotment in any case for which he shall be personally responsible.
- 4
- 5 Technical Officer Divisional Office for information
- 6 File Concerned

Executive Engineer
PHE Division Bijnahara

