

OFFICE OF THE EXECUTIVE ENGINEER (JSD) PHE DIVISION

BARAMULLA

Email: kmrpheb1a@gmail.com (FAX) 01952234575 (Tel) 01952234244



Allotment Order No.

12 of 2023

Dated: 08-4-2023

Name of the agency/ contractor	Reyaz Ahmad Mir
Address	Narupora Kokernag
Registration No.	09/BEE/SE/HYD/Ang/2009
Contact/ Email	riyazmir21179@gmail.com
Name of work	Retrofitting of WSS Ganjipora Buran by way of Laying and fitting of Main /Submain /Distribution System at various spots (for providing 100 percent FHTC) under JJM.
References	This office ENIT 77 of 2022 (S.No. 09)
Accord of administrative approval No. & date	149/SE/HYD/DB/JJM of 2022-23 dated: 31-01-2023
Advertised Cost	Rs. 15,96,268/-
Allotted Cost	Rs. 15,96,268/- (Rupees Fifteen Lacs Ninety Six Thousand Two Hundred Sixty Eight Only)
Time of completion	30 days

For and on behalf of Lt. Governor of Jammu and Kashmir Union Territory, the above noted work is hereby allotted to you on quoted rates given in the Annexure "A" t this allotment, on the terms and conditions given here under :

Conditions:

01. Time of completion is essence of the contract.
02. The work shall have to be started by you at site immediately & ensure its successful completion within a period of **30** days from the date of issuance of allotment from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
03. An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
04. The allotted works shall be subject to Check by the third party monitoring agency appointed by the Department.
05. Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
06. Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
07. The firm shall be bound for satisfactory performance of works for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise, you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost thereof shall be recovered from you and shall be


recommended for further punitive action as governed under the relevant clause of the contract including black listing.

08. After testing and commissioning of works you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
09. The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
10. Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
11. Date of start of the work within 07 days from the date of issue of this letter. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
12. All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
13. Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I).

Flanges involved (if any) shall only be used in case of extreme exigencies, like rocky terrain, gorge & where trench is not possible.

(Encl: Annexure "A")

No. 491-503
Dt. 11-04-2023


Executive Engineer
Jal Shakti Department
PHE Division Baramulla

Copy to the :-

- 1/- Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srinagar/ Jammu for information.
- 2/- Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3/- District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4/- Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No: 15788-15800 Dated: 13.03.2023.
- 5/- Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6/- Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7/- Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8/- Chief Planning Officer Baramulla (Member DJJM) for information.
- 9/- Chief Medical Officer Baramulla (Member DJJM) for information.
- 10/- District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla (Member DJJM) for information.
- 11/- District Information Officer Baramulla (Member DJJM) for information.
- 12/- Asstt. Ex. Engineer PHE Sub Division Pattan, for information.
- 13/- File Concerned.

eProcurement System Government of Jammu And Kashmir
Annexure "A"

Scope of work:
Laying and fitting of WSS Ganjipora Buran by way of Laying and fitting of Main /Submain /Distribution System at various spots (for providing 100 percent FHTC) under JJM.


Sl. No	Description of Work / Item(s)	No. of Qty	Units	Rate	Total Amount
	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed:				
1.1	All Kinds of soil	1482.8000	Cum	436.000	646500.800
2	Laying and fitting of G.I. pipes (all classes) complete including cost of pipe specials and excluding cost of Pipes and Earth work.				0.000
2.1	100mm dia	1200.000	Rm	107.070	128484.000
2.2	65mm dia	1000.000	RM	73.050	73050.000
2.3	50mm dia	1500.000	RM	40.800	61200.000
2.4	40mm dia	1880.000	RM	40.800	76704.000
2.5	25mm dia	2945.000	RM	30.650	90264.250
2.6	20mm dia	3100.000	RM	20.250	62775.000
2.7	15mm dia	3000.000	RM	20.250	60750.000
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	1334.470	Cum	198.700	265159.189
4	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete(25 mm to 40 mm Nominal bore.)	7.000	No	666.250	4663.750
5	Providing and fixing gun metal gate valve with C.I. wheel of approved quality incl. all accessories and all carriages complete.				0.000
5.1	25 mm nominal bore	4.000	No	543.850	2175.400
5.2	40 mm nominal bore	5.000	No	704.700	3523.500
6	Providing and fixing of MS surface boxes (0.75x0.75x0.75) of 6mm thick plate for sluice valves. The job includes fixing of angle iron frame legs in cement concrete 1:2:4 mix with locking arrangements complete. Including Earth work	5.000	Job	6000.000	30000.000
7	Manufacturing providing fixing of MS Bends/ Tees including charges of welding machine upto site of work .To be manufactured as per site requiremnt.	20.000	KG	210.000	4200.000
8	Providing fixing of 12mm thick flanges to existing G.I pipes incl. cost of rubber washers, nuts, bolts and including carriage of welding machine & gen set involving welding at site as per the ground profile complete job.				0.000
8.1	100mm	10.000	Pair	1350.000	13500.000
8.2	65mm	12.000	Pair	850.000	10200.000
8.3	50mm dia G.I	12.000	Pair	700.000	8400.000
9	carriage of material from source to site of work by Mechanical Transport including loading unloading and stacking etc.Upto 30 Kms.				0.000
9.1	Pipes (below 100mm dia)	30.320	M.ton	445.959	13521.477
9.2	100mm dia GI pipe	1200.000	mtr	10.833	12999.600

(Handwritten signatures and initials)

Description of Work / Item(s)	No. of Qty	Units	Rate	Total Amount
Carriage of pipe by head load from safe dumping site to the actual site of work for an avg lead of 300mts	43.600	M.Ton	265.719	11585.348
Pipes (below 100mm dia)	30.320	M.ton	265.719	8056.600
100mm dia GI pipe	1200.000	mtr	7.130	8556.000
Total				1596269
Quoted Rate @ par of advertised cost				0
Total Allotted Amount				1596269
(Rupees Fifteen Lacs Ninety Six Thousand Two Hundred Sixty Nine Only)				

is & Qty checked by:


Head Draftsman



Executive Engineer
PHE Division Baramulla