

OFFICE OF THE EXECUTIVE ENGINEER PHE DIVISION BARAMULLA

Email: kmrphebla@gmail.com (FAX) 01952234575 (Tel) 01952234244


Allotment Order No. 05 of 2023 dated 08-04-2023

Name of the agency/ contractor	Irshad Ahmad Bhat S/o. Late Mohd Sultan Bhat
Address	Ushkara
Registration No.	359/AYY/CE/KCC/PDC/2002-03
Contact/ Email	ms.irshad210@gmail.com
Name of work	Retrofitting of W.S.Scheme Nagbal (Dardi Hajin) by way of :- Laying and fitting of Main /Submain /Distribution System at various spots, Constt. of intake chamber, Constt. of intake channel and Constt. of support pillars cum anchor blocks at different spots (for providing 100% FHTC) under JJM
References	This office ENIT 79 of 2023 (S.No. 07)
Accord of administrative approval No. & date	121/SE/Hyd/DB/JJM of 2022-23 dated 31.01.2023
Advertised Cost	Rs. 3595000/-
Allotted Cost	Rs. 3738800/- (Rupees Thirty Seven Lacs Thirty Eight Thousand Eight Hundred Only)
Time of completion	60 days

For and on behalf of Lt. Governor of Jammu and Kashmir Union Territory, the above noted work is hereby allotted to you on quoted rates given in the Annexure "A" t this allotment, on the terms and conditions given here under :

Conditions:

01. Time of completion is essence of the contract.
02. The work shall have to be started by you at site immediately & ensure its successful completion within a period of 60 days from the date of issuance of allotment from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
03. An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
04. The allotted works shall be subject to Check by the third party monitoring agency appointed by the Department.
05. Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
06. Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
07. The firm shall be bound for satisfactory performance of works for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise, you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.




- recommended for further punitive action as governed under the relevant clause of the contract including black listing.
08. After testing and commissioning of works you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
 09. The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
 10. Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
 11. Date of start of the work within 07 days from the date of issue of this letter. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
 12. All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
 13. Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I).

Flanges involved (if any) shall only be used in case of extreme exigencies, like rocky terrain, gorge & where trench is not possible.

(Encl: Annexure "A")

No. 366-78
Dt. 8/4/23


Executive Engineer
Jal Shakti Department
PHE Division Baramulla

Copy to the :-

- 1/- Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srinagar/ Jammu for information.
- 2/- Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3/- District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4/- Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No: 16212-24 Dated: 18.03.2023.
- 5/- Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6/- Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7/- Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8/- Chief Planning Officer Baramulla (Member DJJM) for information.
- 9/- Chief Medical Officer Baramulla (Member DJJM) for information.
- 10/- District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla (Member DJJM) for information.
- 11/- District Information Officer Baramulla (Member DJJM) for information.
- 12/- Asstt. Ex. Engineer PHE Sub Division Kreeri, for information.
- 13/- File Concerned.

Comp. by: ShahidFarooq (Correspondence)

Annexure "A"

of work:

fitting of W.S. Scheme Nagbal (Dardi Hajin) by way of :- Laying and fitting of Main /Submain /Distribution System at various spots, Constt. of intake chamber, Constt. of intake channel and Constt. of support pillars cum anchor blocks at different spots (for providing 100% JG) under JJM

Sl.No	Description of Work / Item(s)	No.of Qty	Units	Rate	Total Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed:				
1.1	All kinds of soil.	1758.670	Cum	436.000	766780.120
1.2	Earth work in excavation by mechanical means (hydraulic excavator) in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed, within a lead of 50 metres: All kinds of soil	112.000	cum	252.050	28229.600
2	Providing and laying hand packed stone soling 50 mm nominal size including filling, spreading, dressing, ramming, all leads lifts and all carriages complete.	17.700	cum	1320.000	23364.000
3	Providing & Laying in position cement concrete of 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size) excluding the cost of centring and shuttering all work upto plinth level incl. dewatering.	12.680	cum	4861.835	61648.068
4	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	61.420	Cum	6978.675	428630.219
5	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	52.150	cum	9408.135	490634.240
6	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto five level including curing but excluding the cost of centring, shuttering, finishing and reinforcement with 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	0.580	Cum	9849.345	5712.620
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more.	4699.100	Kg	87.175	409644.043
8	Centering and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns etc. for mass concrete.	3.360	sqm	262.300	881.328

Description of Work / Item(s)		No. of Qty	Units	Rate	Total Amount
	Centering and shuttering including strutting, propping etc. and removal of form for:- Walls (any thickness) including attached plasters, buttresses, plinth and string courses etc.	551.440	sqm	573.850	316443.844
10	Centering and shuttering including strutting, propping etc. and removal of form for: Suspended floors, roofs, landings, balconies and access platforms.	4.000	sqm	635.600	2542.400
11	Providing and fixing of MS lid cover of size 0.60x0.60m with angle iron frame 45x45x5mm and 25x25x5mm and 4mm thick lid cover with priming coat and all carriages upto site of work.	1.000	C.Job	4500.000	4500.000
12	Manufacturing /Fabrication and installation of MS drum made out of 6mm thick MS sheet incl. fixing of flanged nipples as per site requirement incl. fixing of supply main and including installation of MS stand with all carriages upto site of work complete.	1.000	C.Job	20000.000	20000.000
13	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes, fittings and Earth work.				0.000
13.1	15 mm dia. nominal bore	2360.000	Mtr	20.250	47790.000
13.2	20 mm dia. nominal bore	3300.000	Mtr	20.250	66825.000
13.3	25 mm dia. nominal bore	2600.000	Mtr	30.650	79690.000
13.4	40 mm dia. nominal bore	1700.000	Mtr	40.800	69360.000
13.5	80 mm dia. nominal bore	1200.000	Mtr	73.050	87660.000
14	Providing and fixing C.I. double acting air valve of approved quality with bolts, nuts, rubber insertions and other accessories complete.				0.000
14.1	25 mm dia.	5.000	No	2200.000	11000.000
15	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	1563.300	cum	198.700	310527.710
16	Providing and fixing gun metal gate valve with C.I. wheel of approved quality with all accessories and all carriages complete.				0.000
16.1	20 mm nominal bore	8.000	No	463.700	3709.600
16.2	25 mm nominal bore	5.000	No	543.850	2719.250
16.3	80 mm nominal bore	4.000	No	2406.700	9626.800
17	Providing and fixing of MS surface boxes (0.75x0.75x0.75) of 6mm thick plate for sluice valves. The job includes fixing of angle iron frame legs in cement concrete 1:2:4 mix with locking arrangements complete.	1.000	Job	7000.000	7000.000
18	carriage of material from source to dumping site of work by Mechanical Transport including loading unloading and stacking etc.				0.000
18.1	Pipes (below 100mm dia) for 30 Km	26.050	M.ton	446.166	11622.400
18.2	Cement /Steel avg. lead 30 KMS	52.520	M.ton	445.959	23421.700
18.3	Sand / Stone aggregate for 30 Kms	159.810	Cum	501.653	80169.300
18.4	Stone aggregate 40 mm for 30 Kms	11.410	Cum	545.284	6221.100
18.5	Stone solling for 30 Kms	17.700	cum	590.203	10446.600
19	carriage of material from road / dumping site to the actual site of work by Manual means including loading unloading and stacking for avg. lead 800 Mtrs.				0.000
19.1	Pipes (below 100mm dia)	26.050	M.ton	490.659	12781.400
19.2	Cement	47.810	M.ton	389.114	18603.400
19.3	Steel	4.700	M.ton	835.866	3928.800
19.4	Sand / Stone aggregate	159.810	Cum	895.408	143095.400

Description of Work / Item(s)	No.of Qty	Units	Rate	Total Amount
Stone aggregate 40mm	11.410	Cum	967.978	11044.629
Stone solling	17.700	cum	1053.377	18644.773
Total				3595000
Quoted Rate @ Above 4%				143800
Total Allotted Amount				3738800
(Rupees Thirty Seven Lacs Thirty Eight Thousand Eight Hundred Only)				

Rates & Qty checked by:


Head Draftsman



Executive Engineer
PHE Division Baramulla