

Government of Jammu and Kashmir  
OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI  
email: urihydraulic@gmail.com

Allotment Order No. 04 of 05/2023

M/S : AR Constructions  
Prop: : Abdul Rouf Chesti  
S/O : Abdul Bari Chesti  
R/O : Sangri Colony Baramulla  
Registration No. : CE/UEED/AAY/Civil-49/2018-19  
TIN No./GST No:- : 01ANFPC4538B1Z3

Name of work : Construction of Water Supply Scheme Gantamulla Payeen by way of Construction Commissioning and Testing of Intake Chambers /SSFPs/ Protection works, Chain Link fencing, and other allied works (for providing 100% FHTC)

eNIT No. : 53 /Hyd/Uri of 2022-23 TENDER ID 2022\_IFC\_207248\_48  
Your Tender Received in response to : eNIT No:53/Hyd/Uri\_of 2022-23 Dated: 06/03/2023 issued under endorsement No:- HDU/CC-02/5930-40 Dated: 06/03/2023 (S. No: 48) Tender ID : 2022\_IFC\_202344\_34

Reference : (i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.  
(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.  
(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.  
(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.  
(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).  
(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.  
(vii) Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/2022/1214-44 Dated: 24-05-2022.  
(viii) This Office Letter No: HDU/CC-02/6399-6400 dated:- 31/03/2023  
(viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/189-201 Dated:- 05/04/2023

Ref: to AAA : Accorded vide Order No. 50/SE/Hyd/DB/JJM of 2022-23 Dated:- 26/08/2022. issued under Endorsement No:- SE/HYD/DB/6462-67 Dated:- 26/08/2022.

Ref: to Tech. Sanction : Accorded vide Order No.CE/PHE/DB/548 of 09/2022 Dated:- 10/09/2022. issued under Endorsement No:- CE/PHE/DB/21476-80 Dated:- 10/09/2022.

LOI issued under No: : NIT No./53/41-42 Dated:- 05/04/2023

Advertisement cost : Rs:59.20Lacs

Allotted cost : ₹ 6037643.77 Rupees Sixty Lakh(s) Thirty Seven Thousand Six Hundred Forty Three And Paise Seventy Seven Only

Time of completion : 120-days

M.H. of Account : (JJM)

Ref. To CDR No. :

Name of the Bank :

BID Declaration Format Submitted

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates quoted by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

## Allotted Rates as "Annexure A" Enclosed"

## Terms and Conditions:-

- 1 Time of completion is essence of the contract.
- 2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of 120 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
- 3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
- 4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.
- 5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
- 6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
- 7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise, you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
- 8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
- 9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
- 10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
- 11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
- 12 Earnest Money @2% deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depositions of 03% performance security of the value of the contract
- 13 All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
- 14 Any rules/ terms and conditions if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Checked by

Head Draftsman  
NO: HDU/SC-04

DATED:

Copy to the:

759-70

12-05-2023

Executive Engineer  
Hydraulic Division Uri

(Syed Shafiq)

- 1 Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srinagar/ Jammu for information.
- 2 Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3 .District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4 Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/189-201 Dated:- 05/04/2023
- 5 Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6 Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7 Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8 Chief Planning Officer Baramulla (Member DJJM) for information.
- 9 Chief Medical Officer Baramulla (Member DJJM) for information.
- 10 District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla (Member DJJM) for information
- 11 District Information Officer Baramulla (Member DJJM) for information.
- 12 Assistant Executive Engineer PHE Sub Division Uri for information.
- 13 File.

**Annexure "A" to the Allotment Order No. 04 of 05/2023**

**Construction of Water Supply Scheme Gantamulla Payeen by way of Construction Commissioning and Testing of Intake Chambers /SSFPs/ Protection works, Chain Link fencing, and other allied works (for providing 100% FHTC)**

#	Particulars	Qty	Unit	Rate	Amount
1	E/W in bulk excavation by manual means in trenches for foundations, drains, pipes, cables etc (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, depth upto 1.5 mtr including disposal of excavated earth within 1km from cutting edge, disposed earth to be leveled and neatly dressed :				
1.1	In all kinds of soils	466.600	Cum	539.350	251660.71
2	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	102.490	Cum	198.700	20364.76
3	Providing and laying stone soling 2nd class	43.433	Cum	616.400	26772.10
4	Providing and laying in position cement concrete in specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level. 1 : 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	29.560	Cum	4861.835	143715.84
5	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	112.190	Cum	6465.195	725330.23
6	Providing and laying in position specified grade of reinforced cement concrete including curring but excluding cost centering shuttering finishing and reinforcement ( all work upto plinth level) : 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	41.380	Cum	7800.760	322795.45
7	Reinforced Cement concrete work in wall ( any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	56.900	Cum	9408.135	535322.88
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 150 landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3( 1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	2.810	Cum	9849.345	27676.66
9	Providing hoisting and fixing upto floor five level pre cast reinforced cement concrete work in string courses, bends, coopings, bedplates, anchor block, plain window sills, and the like including setting in position in cement mortar 1:5:3 including cost of centering shuttering and curring but excluding cost of reinforcement 1:1.5:3 1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	1.120	Cum	8679.000	9720.48
10	Centering and shuttering including strutting propping etc. and removal of Form work for.				0.00
10.1	Foundations, footings, bases of columns	19.710	Sqm	262.300	5169.93

*(Handwritten signatures and initials)*

	Particulars	Qty	Unit	Rate	Amount
	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	864.540	Sqm	573.850	496116.28
3	Suspended floors, roofs, landings, balconies and access platform.	24.480	Sqm	635.600	15559.49
4	Columns, Pilers, abutment, posts and struts.	37.800	Sqm	680.150	25709.67
11	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	565.390	Sqm	357.995	202406.79
12	Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification	85.000	Kg	67.650	5750.25
13	Providing and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron embedded into concrete blocks with Angle Iron frames 50X50X6mm , Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements handles/hinges Complete Job.	545.000	Kg	102.140	55666.30
14	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	329.280	Kg	102.140	33632.66
15	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	12923.110	Kg	87.175	1126572.11
16	Supplying at site Angle iron post & strut of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes upto 10 mm dia. etc. complete.	1472.400	Kg	102.140	150390.94
17	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	153.480	Kg	102.140	15676.45
18	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case railing and similar works and applying primer coat	51.730	Kg	190.190	9838.53
19	Providing and fixing of PVC ISIS Mark inside concrete wall for inlet and outlet of 40mm/50mm dia engh	20.000	No	200.000	4000.00
20	Providing/Shrouding and laying of filter media of required grade from ganderbal, Sind Nallah source inclusive of all sorts of carriages upto site of work complete job.	105.600	Cum	8500.000	897600.00
21	Providing and Fixing of (4mm-Dia Wire) GI chain link fabric fencing of required width in mesh size 50X50mm including strengthening with 2mm wire/nuts/bolts and washers as required as per instruction of Engineer Incharge at site.	373.140	Sqm	733.500	273698.19
22	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer				0.00
22.1	Cement and Steel (15Kms)	103.260	Mton	303.646	31354.49
22.2	Sand. 20Kms)	120.720	Cum	402.293	48564.81
22.3	Agg. 20mm (60Kms)	186.330	Cum	799.733	149014.25
22.4	Agg. 40mm (60Kms)	26.620	Cum	869.239	23139.14
22.5	Stone Soling (07-Kms)	43.430	Cum	276.322	12000.66



Particulars		Qty	Unit	Rate	Amount
Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer					0.00
23.1	Cement (500Mtrs)	86.750	Mton	282.095	24471.74
23.2	Steel (500Mtrs)	16.220	Mton	605.958	9828.64
23.3	Sand. 500Mtrs)	120.720	Cum	621.207	74992.11
23.4	Agg. 20mm (500Mtrs)	186.330	Cum	621.000	115710.93
23.5	Agg. 40mm (500Mtrs)	26.620	Cum	671.554	17876.77
23.6	Stone Soling (500Mtrs)	43.430	Cum	730.802	31738.73
				<b>Total</b>	<b>5919838.97</b>
Excess (+)		1.99%		<b>6037643.768</b>	

Rupees Sixty Lakh(s) Thirty Seven Thousand Six Hundred Forty Three And Paise Seventy Seven Only

Checked by

Head D/Mat



**Executive Engineer**  
Hydraulic Division Uri