

Government of Jammu and Kashmir  
OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI  
email: urihydraulic@gmail.com

**Allotment Order No. 13 of 07/2023**

M/S : Mohammad Shafi Bhat  
S/O : Khazir Mohammad Bhat  
R/O : Khandbawan Nawakadal Srinagar  
Registration No. : CE(RandB)K-01/2002 - 2003/AAY  
TIN No./GST No:- : 01ADSPB9975E2ZD

Name of work : *Retrofitting of Water Supply Scheme Trikanjan by way of Construction/Commissioning of SRs, PSTs, Chainlink Fencing and other allied works (for providing 100% FHTC) under JJM (for providing 100% FHTC) under JJM*

eNIT No. : 01 /Hyd/Uri of 2023-24 TENDER ID 2023\_IFC\_209185\_31  
Your Tender Received in response to : eNIT No:01/Hyd/Uri\_of\_2023-24 Dated: 03/04/2023 issued under endorsement No:- HDU/CC-02/11-21 Dated: 03/04/2023 (S. No: 31) Tender ID : 2023\_IFC\_209185\_31

**Reference** :

*(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.*

*(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.*

*(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.*

*(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.*

*(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).*

*(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.*

*(vii) Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.*

*(viii) This Office Letter No: HDU/CC-02/ Dated:- (viii) District Superintending Engineer Hyd. Circle Bla/Bpr HO Sopore authorization No: SE/Hyd/DB/1206-17 Dated: 06/05/2023*

Ref: to AAA : Accorded vide Order No. CE/PHE/DB/1240 of 08/2022 Dated:- 31/08/2022.  
Ref: to Tech. Sanction : Accorded vide Order No. CE/PHE/DB/199 of 08/2022 Dated:- 31/08/2022.  
LOI Issued under No:- : NIT NO. 01/706-07 Dated:- 10/05/2023  
Advertisement cost : Rs: 61.11Lacs  
Allotted cost : **₹ 6349487.59** Rupees Sixty Three Lakh(s) Forty Nine Thousand Four Hundred Eighty Seven And Paise Fifty Nine Only

Time of completion : 120-days  
M.H. of Account : (JJM)  
Ref. To CDR/TDR No. : TDR NO: 504664 Dated: 21/06/2023 Amount: ₹ 190,700.00  
Name of the Bank : J&K Bank Ltd. Branch Office Nawakadal Sgr.

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

**Allotted Rates as "Annexure A" Enclosed"**

**Terms and Conditions:-**

1 Time of completion is essence of the contract.

*[Handwritten Signature]*



- 2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of 120 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
- 3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
- 4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.
- 5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
- 6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
- 7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise, you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
- 8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
- 9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
- 10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
- 11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
- 12 Earnest Money @2% deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after deposition of 03% performance security of the value of the contract
- 13 All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
- 14 Any rules/ terms and conditions if not stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Checked by

 Head Draftsman

NO: HDU/CC-04/1819-31

DATED: 12-07-2023

Copy to the:

- 1 Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srinagar/ Jammu for information.
- 2 Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3 .District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4 Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/1206-17 Dated: 06/05/2023
- 5 Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6 Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7 Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8 Chief Planning Officer Baramulla (Member DJJM) for information.
- 9 Chief Medical Officer Baramulla (Member DJJM) for information.
- 10 District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla (Member DJJM) for information
- 11 District Information Officer Baramulla (Member DJJM) for information.
- 12 Assistant Executive Engineer PHE Sub Division Uri for information.
- 13 File.

 Executive Engineer  
Hydraulic Division Uri

(Syed Shafiq)



**Annexure "A" to the Allotment Order No. 13 of 07/2023**

**retrofitting of Water Supply Scheme Trikanjan by way of Construction/Commissioning of SRs, PSTs, Chainlink Fencing and other allied works (for providing 100% FHTC) under JJM (for providing 100% FHTC) under JJM**

S#	Particulars	Qty	Unit	Rate	Amount
1	E/W in bulk excavation by manual means over areas (exceeding 30-cm in depth, 1.5 in width, as well as 10m on plan) including disposal of excavated earth lead upto 50mtr and lift upto 1.5Mtrs as directed by the Engineer Incharge				
1.1	In all kinds of soils	996.060	Cum	560.924	558713.96
2	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	108.270	Cum	206.648	22373.78
3	Providing and laying stone soling 2nd class incl. cost of stones	46.140	Cum	641.056	29578.32
4	Providing and laying in position cement concrete in specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	30.550	Cum	5056.308	154470.22
5	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size).	83.100	Cum	6723.803	558748.01
6	Providing and laying in position specified grade of reinforced cement concrete including curring but excluding cost centering shuttering finishing and reinforcement ( all work upto plinth level) 1: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed.	45.580	Cum	8112.790	369780.99
7	Reinforced Cement concrete work in wall ( any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	58.970	Cum	9784.460	576989.63
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 150 landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3( 1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	6.270	Cum	10243.319	64225.61
9	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	4434.280	Kg	106.226	471034.05
10	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case raklling and similar works and applying primer coat Including cost of all sorts of carriages of material upto site of work)	75.880	kg	197.798	15008.88





	Particulars	Qty	Unit	Rate	Amount
11	Reinforced cement concrete work in arches, arches, vaults, shelves, folded plates and roofs having slope more than 15° floor five level including curing but excluding cost of centering and shuttering, finishing and reinforcement	11.050	Cum	10820.696	119568.69
12	Centering and shuttering including strutting propping etc. and removal of Form work for.			0.000	0.00
12.1	Foundations, footings, bases of columns	28.040	Sqm	272.792	7649.09
12.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	911.740	Sqm	596.804	544130.08
12.3	Suspended floors, roofs, landings, balconies and access platform.	46.880	Sqm	661.024	30988.81
12.4	Arches, Domes, walls upto 60 mtr span	83.880	Sqm	2170.272	182042.42
12.5	Columns	25.200	sqm	707.356	17825.37
13	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	694.400	Sqm	372.320	258539.01
14	Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification including all sorts of carriages upto site of work complete	500.000	Kg	70.356	35178.00
15	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	11433.270	Kg	90.662	1036563.12
16	Providing and fixing of 4mm thick G.I chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 m dia wire and nuts, bolts and washer are required complete as per the direction of Engineer incharge. Made of G. I wire of dia 4mm	312.200	Sqm	762.840	238158.65
17	Providing and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron embedded into concrete blocks with Angle Iron frames 50X50X6mm, Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements handles/hinges Complete Job.	1090.000	Kg	106.226	115785.90
18	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	356.520	Kg	106.226	37871.55
19	Providing and fixing of PVC ISIS Mark inside concrete wall for inlet and outlet of 40mm/50mm dia length	40.000	No	208.000	8320.00
20	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)			0.000	0.00
20.1	100mm dia	8.000	Nos	7800.000	62400.00
21	Providing and fixing 50mmDia GI Bend in dome slab with one and provided with wire gauge mesh. The bends are to be fixed in dome slab during concreting for elevation purpose quality	16.000	Nos	520.000	8320.00
22	Providing and fixing of 8mm-thick MS Flanges to GI pipes including cutting of threads welding of flanges to pipe ends including laying and fitting testing and commissioning including cost of nuts, bolts, rubber washers including all carriages upto site of work complete job.			0.000	0.00
22.1	100mm dia	13.000	Joints	1352.000	17576.00
22.2	80mm dia	3.000	Joints	1248.000	3744.00

22/11/2017  




	Particulars	Qty	Unit	Rate	Amount
23	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
23.1	Cement and Steel from Divisional Store (30-Kms)	103.160	Mton	463.797	47845.34
23.2	Sand. (30-Kms)	120.040	Cum	521.716	62626.79
23.3	Agg. 20mm (75-Kms)	184.480	Cum	986.721	182030.25
23.4	Stone Soling (07-Kms))	46.140	Cum	288.808	13325.60
23.5	Agg. 40mm (75-Kms)	27.500	Cum	1072.466	29492.81
23.6	Carriage of chain link fencing (30-Kms)	0.340	Mton	463.788	157.69
24	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer (1000-Mtrs)				
24.1	Cement	87.160	Mton	478.878	41739.04
24.2	Steel	16.000	Mton	1028.706	16459.29
24.3	Sand.	120.040	Cum	1121.349	134606.71
24.4	Agg. 20mm	184.480	Cum	1121.349	206866.43
24.5	Agg. 40mm	27.500	Cum	1212.214	33335.87
24.6	Stone Soling (500-Mtrs)	46.140	Cum	760.032	35067.88
24.7	Carriage of Chain link fencing	0.340	Mton	1028.706	349.76
				<b>Total</b>	<b>6349487.59</b>

Rupees Sixty Three Lakh(s) Forty Nine Thousand Four Hundred Eighty Seven And Paise Fifty Nine Only

Checked by

Head D/Mary  
22/11/24

Executive Engineer  
Hydraulic Division Uri