

Government of Jammu and Kashmir  
OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI  
email: urihydraulic@gmail.com

**Allotment Order No. 20 of 07/2023**

M/S : M/s MIR CONSTRUCTIONS COMPANY  
Prop:- : Mukhtyar Ahmad Mughal  
S/O : Liaqat Ali Mughal Chogata  
R/O : Kundi Birjala Uri  
Registration No. : SHEP/CE/AAY/SANITARY/003 of 2018  
TIN No./GST No:- : 01AOAPM8579C2Z3

Name of work : Construction of Water Supply Scheme Dhani Sayedan by way of  
Construction/Testing & Commissioning of Intake Chambers, SSFP/PSTs and  
other allied works (for providing 100% FHTC) under JJM

eNIT No. : 11/Hyd/Uri of 2023-24 TENDER ID 2023\_IFC\_212582\_15  
Your Tender Received in : eNIT No:11/Hyd/Uri\_of\_2023-24 Dated: 17/05/2023 issued under endorsement No:-  
response to HDU/CC-02/829-39 Dated: 17/05/2023 (S. No: 15) Tender ID: 2023\_IFC\_212582\_15

Reference : (i) Constitution of District Jal Jeevan Mission, Administrative Council Decision  
No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020  
Dated: 24-04-2020.  
(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K,  
meeting convened on 04-09-2021.  
(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.  
(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-  
22 Dated: 21-02-2022 issued under Endt. No: CE/PHE/DB/41981-42033 Dated: 21-02-  
2022.  
(v) UT level committee meeting held on 28-04-2022 under the Chairmanship  
Development Commissioner Works PW (R&B).  
(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No:  
CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.  
(vii) Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District  
Development Commissioner Baramulla (Chairperson District JJM Bla) authorization  
issued vide No: DDCB/Meeting/2022/1214-44 Dated: 24-05-2022.  
(viii) This Office Letter No: HDU/eNIT-11/1039-40 Dated:- 30/05/2023 (viii)  
District Superintending Engineer Hyd. Circle Bla/Bpr 117 Sopore authorization No:  
SE/Hyd/DB/2201-14 Dated: 30/05/2023

Ref: to AAA : Accorded vide Order No. CE/PHE/DB/240 of 08/2022 Dated:- 31/08/2022.  
Ref: to Tech. Sanction : Accorded vide Order No. CE/PHE/DB/192 of 08/2022 Dated:- 31/08/2022.  
LOI Issued under No:- : NIT No. 11/1072-73 Dated:- 31/05/2023  
Advertisement cost : Rs: 117.48 Lacs.

Allotted cost : ₹ 12157842.99 Rupees One Crore Twenty One Lakh(s) Fifty Seven Thousand  
Eight Hundred Forty Two And Paise Ninety Nine Only

Time of completion : 120-days

M.H. of Account : (JJM)

Ref. To CDR/TDR No. :

Name of the Bank : Bid Security Declaration Format

For and on behalf of LT, Governor of J&K UT the contract for above noted work is fixed with you on the  
following rates accepted/negotiated by you in writing on the comparative statement on the following terms and  
conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd.  
Card is valid/in order in terms of standing rules and free for the capacity of the work

**Allotted Rates as "Annexure A" Enclosed"**

**Terms and Conditions:-**

1 Time of completion is essence of the contract.

- 2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of 120 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
- 3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
- 4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.
- 5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
- 6 Performance security equivalent to 04% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
- 7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise, you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
- 8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
- 9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
- 10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
- 11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
- 12 All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
- 13 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Head Assistant

NO: HDU/CC-04/ 1898-1910  
 DATED: 12-07-2023  
 Copy to the:

Executive Engineer  
 Hydraulic Division Uri

(Syed Shafiq)

- 1 Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srinagar/ Jammu for information.
- 2 Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3 .District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4 Distt. Superintending Engineer Hydraulic Circle Baramulla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/2201-14 Dated: 31/05/2023
- 5 Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6 Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7 Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8 Chief Planning Officer Baramulla (Member DJJM) for information.
- 9 Chief Medical Officer Baramulla (Member DJJM) for information.
- 10 District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla (Member DJJM) for information
- 11 District Information Officer Baramulla (Member DJJM) for information.
- 12 Assistant Executive Engineer PHE Sub Division Uri for information.
- 13 File.

**Annexure "A" to the Allotment Order No. 20 of 07/2023**

**struction of Water Supply Scheme Dhani Sayedan by way of Construction/Testing & Commissioning of Intake Chambers, SSFP/PSTs and other allied works (for providing 100% FHTC) under JJM**

	Particulars	Qty	Unit	Rate	Amount
	E/W in bulk excavation by manual means over areas (exceeding 30-cm in depth, 1.5 in width, as well as 10 Sqm on plan) including disposal of excavated earth lead upto 50mtr and lift upto 1.5Mtrs as directed by the Engineer incharge				
1.1	in all kinds of soils	909.760	Cum	533.350	487003.04
2	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	226.690	Cum	198.700	45043.30
3	Providing and laying stone soling 2nd class incl. cost of stones )	68.660	Cum	616.400	42322.02
4	Providing and laying in position cement concrete in specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	46.960	Cum	4861.840	228312.01
5	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	55.520	Cum	6465.200	358947.90
6	Providing and laying in position specified grade of reinforced cement concrete including curring but excluding cost centering shuttering finishing and reinforcement ( all work upto plinth level 1: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size) crushed	110.680	Cum	7800.760	863388.12
7	Reinforced Cement concrete work in wall ( any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing and reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	149.880	Cum	9408.140	1410092.02
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15° landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3( 1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	8.200	Cum	9849.350	80764.67
9	Providing and fixing upto floor five level precast cement concrete string or lacing, courses copings bed plates anchor blocks plain window sills, shelves, louvers, steps stair cases etc including hoisting and setting fr position with cement mortar 1:3 (1 cement: 3 coarse sand) cost of required centring shuttering and curing complete 1: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size)	2.240	Cum	8679.000	19440.96
10	Centering and shuttering including strutting propping etc. and removal of Form work for.				0.00
10.1	Foundations, footings, bases of columns	62.360	Sqm	262.300	16357.03
10.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	1405.060	Sqm	573.850	806293.68
10.3	Suspended floors, roofs, landings, balconies and access platform.	69.180	Sqm	635.600	43970.81

20  
K. M. S.

W

	Particulars	Qty	Unit	Rate	Amount
	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	1668.180	Sqm	358.000	597208.44
	Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification including all sorts of carriages upto site of work complete	370.000	Kg	67.600	25012.00
3	Providing and fixing of MS surface boxes (1mx1mx1m) of 6mm thick plate for sluice valves. The job includes fixing of angle iron frame legs in cement concrete 1:2:4 mix with locking arrangements complete.	2180.000	Kg	102.140	222665.20
14	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer incharge at site.	153.480	Kg	102.140	15676.45
15	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case railing and similar works and applying primer coat	194.120	Kg	190.190	36919.68
16	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	25117.850	Kg	87.180	2189774.16
17	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	1221.720	Kg	102.140	124786.48
18	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)				0.00
18.1	100mm dia	8.000	Nos	7500.000	60000.00
18.2	Providing and fixing of PVC ISIS Mark inside concrete wall for inlet and outlet of 40mm/50mm dia engh	98.000	No	200.000	19600.00
19	Providing/Shrouding and laying of filter media of required grade from ganderbal, Sind Nallah source inclusive of all sorts of carriages upto site of work complete job.	211.200	Cum	8500.000	1795200.00
20	Providing and fixing of 8mm MS Flanges to GI pipes including cutting of threads welding of flanges to pipe ends including laying and fitting testing and commissioning including cost of nuts, bolts, rubber washers including all carriages upto site of work complete job.				0.00
20.1	100mm dia	10.000	Joints	1300.000	13000.00
21	Hand-packing stones in wire-crates; including cost of stones and crates and all sorts of carriages of material upto site of work)	181.470	Cum	2500.000	453675.00
22	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer				0.00
22.1	Cement and Steel (45 Kms)				
22.2	Sand. (51Kms)	183.980	Mton	578.440	106421.39
22.3	Agg. 20mm (91Kms)	200.840	Cum	700.370	140662.31
22.4	Agg. 40mm (91Kms)	313.870	Cum	954.620	299626.58
22.5	Stone Soling	43.890	Cum	1193.190	52369.11
		61.000	Cum	277.770	16943.97
23	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer				0.00
23.1	Cement (1500Mtrs)				
23.2	Steel (1500Mtrs)	149.170	Mton	638.830	95294.27
23.4	Sand.(1500Mtrs)	28.390	Mton	1372.300	38959.60
		200.840	Cum	1535.220	308333.58

*[Handwritten signature]*


*[Handwritten signature]*

Particulars	Qty	Unit	Rate	Amount
Agg. 20mm (1500Mtrs)	313.870	Cum	1535.220	481859.50
Agg. 40mm (1500Mtrs)	43.890	Cum	1659.630	72841.16
Stone Soling (500Mtrs)	240.000	Cum	730.800	175392.00
			<b>Total</b>	<b>11747843.26</b>
<b>Excess (+)</b>		<b>3.490%</b>		<b>12157842.99</b>

Rupees One Crore Twenty One Lakh(s) Fifty Seven Thousand Eight Hundred Forty Two And Paise Ninety Nine Only

Checked by

Head D/Man

20  


  
**Executive Engineer**  
**Hydraulic Division Uri**