

Allotment Order No. 37 of 07/2023

M/S : **MIR CONSTRUCTIONS COMPANY**
 Prop. : **Mukhtyar Ahmad Mughal**
 S/O : **Liaqat Ali Mughal Chogata**
 R/O : **Kundi Barjala Uri**
 Registration No. : **SHEP/CEAAY/SANITARY/003 OF 2018**
 TIN No./GST No:- : **01AOAPM8579C2Z3**

Why allotment
(Not as %)

Name of work : **Retrofitting of Water Supply Scheme Soura Hathlanga by way of Construction of Intae Chambers, Chain Link Fencing and other allied works (for providing 100% FHTC) under JJM**

eNIT No. : 09/Hyd/Uri of 2023-24 TENDER ID 2022_IFC_212041_9
Your Tender Received in response to : eNIT No:09/Hyd/Uri_of_2023-24 Dated: 13/05/2023 issued under endorsement No:- HDU/CC-02/779-89 Dated: 13/05/2023 (S. No: 09) Tender ID : 2022_IFC_212041_9

Reference :

(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.

(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.

(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.

(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.

(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).

(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.

(vii) Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/2022/1214-44 Dated: 24-05-2022.

(viii) This Office Letter No: HDU/eNIT-11/1039-40 Dated:- 30/05/2023 (viii) District Superintending Engineer Hyd. Circle Bla/Bpr HO Sopore authorization No: SE/Hyd/DB/2560-73 Dated: 10/06/2023

Ref: to AAA : Accorded vide Order No.CE/PHE/DB/240 of 08/2022 Dated:- 31/08/2022.
 Ref: to Tech. Sanction : Accorded vide Order No. CE/PHE/DB/197 of 08/2022 Dated:- 31/08/2022.
 LOI Issued under No:- : NIT NO. 09/1285-86 Dated:- 15/06/2023
 Advertisement cost : Rs: 52.54 Lacs
 Allotted cost : **₹ 4713556.53** Rupees Forty Seven Lakh(s) Thirteen Thousand Five Hundred Fifty Six And Paise Fifty Three Only
 Time of completion : 120-days
 M.H. of Account : (JJM)
 Ref. To CDR/TDR No. : BSDF
 Name of the Bank :

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

(Signature)

Terms and Conditions:-

1 Time of completion is essence of the contract.

The work shall have to be started by you at site immediately & ensure its successful completion within a period of 120 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.

An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.

The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.

Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis. Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of

CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.

The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works.

If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.

- 8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
- 9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial
- 10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
- 11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
- 12 Earnest Money @2% deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depositions of 03% performance security of the value of the contract
- 13 All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
- 14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Head Assistant

NO: HDU/CC-04/ 2278-90

DATED: 18-07-2023.

Copy to the:

- 1 Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srinagar/ Jammu for information.
- 2 Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3 .District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4 Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/2201-14 Dated: 31/05/2023
- 5 Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6 Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7 Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8 Chief Planning Officer Baramulla (Member DJJM) for information.
- 9 Chief Medical Officer Baramulla (Member DJJM) for information.
- 10 District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla (Member DJJM) for information.
- 11 District Information Officer Baramulla (Member DJJM) for information.
- 12 Assistant Executive Engineer PHE Sub Division Uri for information.
- 13 File.

Executive Engineer
Hydraulic Division Uri

Annexure "A" to the Allotment Order No. _____ of _____/20_____

offitting of Water Supply Scheme Soura Hathlanga by way of Construction of Intae Chambers , Chain Link Fencing and other allied works (for providing 100% FHTC) under JJM

	Particulars	Qty	Unit	Rate	Amount
	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge.				
1	In all kinds of soils (Bulk)	278.880	Cum	560.924	156430.49
2	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	57.880	Cum	206.648	11960.79
3	Providing and laying stone soling 2nd class	40.280	Cum	641.056	25821.74
4	Providing and laying in position cement concrete in specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	26.720	Cum	5056.308	135104.56
5	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	129.570	Cum	6723.803	871203.13
6	Providing and laying in position specified grade of reinforced cement concrete including curring but excluding cost centering shuttering finishing and reinforcement (all work upto plinth level l: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	11.520	Cum	8112.790	93459.35
7	Reinforced Cement concrete work in wall (any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	19.090	Cum	9784.460	186785.35
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 150 landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	0.750	Cum	10243.319	7682.49
9	Reinforced cement concrete work in arches, archibs, valluts, shelves, folded plates and roofs having slope more than 150 floor five level inclding curing but excluding cost of centering and shuttering, finshing and reinforcement	2.330	Cum	10820.696	25212.22
10	Hand-packing stone in wire crates; including cost of stones and crates and all sorts of carriages of material upto site of work	104.520	Cum	2600.000	271752.00
11	Centering and shuttering including strutting propping etc. and removal of Form work for.			0.000	0.00
11.1	Foundations, footings, bases of columns	41.020	Sqm	272.792	11189.93
11.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	667.000	Sqm	596.804	398068.27

	Particulars	Qty	Unit	Rate	Amount
	suspended floors, roofs, landings, balconies and access platform.	6.570	Sqm	661.024	4342.93
	Arches, Domes, walls upto 60 mtr span	23.340	Sqm	2170.272	50654.15
	Columns, Pilers, abutment, posts and struts.	37.800	Sqm	707.356	26738.06
	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	208.840	Sqm	372.315	77754.22
	Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification	200.000	Kg	70.304	14060.80
4	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	3128.160	Kg	106.226	332290.67
15	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	3209.850	Kg	90.667	291028.11
16	Making connection of GI distribution branch with GI main of following sizes, by P/F of tees, incld. cutting and threading the pipe etc. complete			0.000	0.00
16.1	25 to 40 mm dia nominal bore	22.000	No	692.900	15243.80
16.2	Above 40 mm nominal bore	5.000	No	1319.500	6597.50
17	Providing and Fixing of GI chain link fabric fencing of required width in mesh size 50X50mm including strengthening with 2mm wire/nuts/bolts and washers as required as per instruction of Engineer Incharge at site.	468.300	Sqm	762.840	357237.97
18	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
18.1	Cement and Steel (20 Kms)	70.890	Mton	371.946	26367.22
18.2	Sand. (75Kms)	89.740	Cum	986.658	88542.72
18.3	Agg. 20mm (120Kms)	246.650	Cum	1451.622	358042.47
18.4	Agg. 40mm (120Kms)	28.890	Cum	1577.597	45576.77
18.5	Stone Soling (07-Kms)	172.910	Cum	288.808	49937.79
18.6	Chain link fencing (20 Kms)	0.470	Mton	371.946	174.81
19	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
19.1	Cement (1500Mtrs)	61.470	Mton	664.373	40839.00
19.2	Steel (1500Mtrs)	10.100	Mton	1427.202	14414.74
19.3	Sand.(1500Mtrs)	89.740	Cum	1596.629	143281.47
19.4	Agg. 20mm (1500Mtrs)	246.650	Cum	1596.629	393808.49
19.5	Agg. 40mm (1500Mtrs)	28.890	Cum	1726.015	49864.58
19.6	Stone Soling (500Mtrs)	172.910	Cum	760.032	131417.13
19.7	Chain link fencing (1500 Mtrs)	0.470	Mton	1427.265	670.81
				Total	4713556.53

Rupees Forty Seven Lacs Thirteen Thousand Five Hundred Fifty Six and Paise Fifty Three only)

Checked by

Head D.M.
20/11/2017

Executive Engineer
Hydraulic Division Uri