

19

No. PHEP/ 4246-49
Dated 12-11-2020

Mr. Bashir Ahmad Naik,
Contractor,
S/o. Ghulam Ahmad Naik,
R/o Zagigam, Pulwama
Regd. No. 24/AA/SE/HYDL/SHOPIAN/2004-05

Sub :- Retrofitting of Water Supply Scheme Achgoze Bamnoo by way of providing, laying & fitting of GI pipes, including construction of head works/ intake channel and RCC jacketing to old existing SSF Plant, including providing filter media and face lifting of structures including installation of 85 No. FHTC's for Achgoze Bamnoo (JJM).

Ref:- E-NIT S.No. 39/PHEP of 2020-21, job No. (2), Circulated vide this office No. PHEP/3077-90
Dated: 26-09-2020.

.....
Advertised Amount of work: ₹ 78,42,000.00

Alloted Amount of work: ₹ 88,02,000.00

Rupees Eighty Eight Lakh(s) Two Thousand Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following negotiated rates as accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No.or Qty.	Unit	RATE	
				Figures	Words
1.00	Earth work excavation by manual means in trenches for foundation drains, pipes cables etc (not exceeding 1.5 mtr in width and for shaft wells and the cesspits and the like not exceeding 10sqm on plan) depth up to 1.5 mtr including disposal of excavated soil up to 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil.	2307.62	Cum	324.00	Rupees Three Hundred Twenty Four Only
2.00	Dismantling of G.I. pipes (external work) including excavation and refilling, trenches, after taking out the pipes, manually by mechanical means including stacking of pipes within 50 mtrs.				
2.10	15mm to 40mm dia bore	250.00	Mtr	99.00	Rupees Ninety Nine Only
2.20	Above 40mm dia bore	300.00	Mtr	100.00	Rupees One Hundred Only
3.00	L/F of G.I. pipes excluding cost of ppe and earth work but including handling complete:-				
3.10	25mm dia G.I. pipe	250.00	Mtr	27.00	Rupees Twenty Seven Only
4.00	P/F of flanged pipe with flanged joints 12mm thck of flanges including cost of nuts, bolts, washers, cutting of threads and making good for jointing including testing and commissioning all carriages complete.				
4.10	100mm dia GI pipe with flanges	2000.00	Mtr	1100.00	Rupees One Thousand One Hundred Only
4.20	80mm dia GI pipe with flanges	1000.00	Mtr	800.00	Rupees Eight Hundred Only
5.00	Providing, laying and fitting of GI pipes including all carriages head load upto site of work complete.				
5.10	50mm dia	1000.00	Mtr	470.00	Rupees Four Hundred Seventy Only
5.20	40mm dia	1000.00	Mtr	380.00	Rupees Three Hundred Eighty Only
5.30	25mm dia	1500.00	Mtr	240.00	Rupees Two Hundred Forty Only
5.40	20mm dia	2000.00	Mtr	170.00	Rupees One Hundred Seventy Only
5.50	15mm dia	4000.00	Mtr	140.00	Rupees One Hundred Forty Only
6.00	Making connections of G.I. distribution branch with G.I. mains of following sizes by providing and fixing tee including cutting and threading the pipe etc complete.				
6.10	25mm to 40mm nominal bore	60.00	No	550.00	Rupees Five Hundred Fifty Only
6.20	above 40mm nominal bore	15.00	No	1000.00	Rupees One Thousand Only
7.00	Providing, supplying, fixing of 12mm thick flanged joints to 150mm dia G.I. pipe incld cost of nuts, bolts, washers, cutting of threading incld making good for jointing with welding all carriage to and fro complete				
7.10	80mm dia GI pipes	49.00	Joint	953.00	Rupees Nine Hundred Only
8.00	Providing and laying in position cement concrete of specified grade excl. cost of centering & shuttering, all work up to plinth level 1:4:8 (1 cement:4 fine sand:8 grade stone agg.)	6.57	Cum	200.00	Rupees Four Thousand Two Hundred Only
9.00	12 mm thick cement plaster in 1:4 mix floating coat of neat cement (1 cement,4 fine sand)	368.20	Sqm	200.00	Rupees Two Hundred Only
10.00	Clearance of silt from PST, FP, clear water sump, SR intake filter media etc including disposal from the premises all leads and lifts complete job.	10607.37	Cff	7.00	Rupees Seven Only
11.00	Cleaning and washing of filter media after removing from lant complete job.	5346.00	Cf.	6.00	Rupees Six Only
12.00	Providing and fixing of Baramulla slabs from Ganderbal including all carriages leads lifts and placing into plant complete job.	150.00	Sft	175.00	Rupees One Hundred Seventy Five Only

1b :- Retrofitting of Water Supply Scheme Achgoze Bamnoo by way of providing, laying & fitting of GI pipes, including construction of head works/ intake channel and RCC jacketing to old existing SSF Plant, including providing filter media and face lifting of structures including installation of 85 No. FHWC's for Achgoze Bamnoo (JJM).

13.00	Emptying of filter media into filtration plant in layers after washing and cleaning complete job.	2138.40	Cft	3.50	Rupees Three And Paise Fifty Only
14.00	Providing and laying in position specified grade of reinforced cement concrete excl. the cost of centering, shuttering, finishing, & Reinforcement. All work up to plinth level (1:1.5:3) Raft (1 cement:1 1/2 course sand:3 grade stone agg. 20 mm nominal size)	31.23	Cum	7000.00	Rupees Seven Thousand Only
15.00	Extra for providing and mixing of water proofing material in cement conc work in doses by weight of cement as per manufacturer specification	342.00	Kg	57.00	Rupees Fifty Seven Only
16.00	Applying priming coat with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	274.50	Sqm	40.00	Rupees Forty Only
17.00	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade old steel work (one or more coats)	274.50	Sqm	74.00	Rupees Seventy Four Only
18.00	finishing walls with water proofing cement paint of required shade on new works (two or more coats) applied @ 3.84 Kg/10Sqm	733.45	Sqm	72.00	Rupees Seventy Two Only
19.00	P/F of Sign board of 8'x4' of size to be fitted with angle iron frame with cement concrete complete job.	1.00	No	15000.00	Rupees Fifteen Thousand Only
20.00	Providing and laying of stone soling hand packed horizontally excluding cost of stones	32.56	Cum	441.00	Rupees Four Hundred Forty One Only
21.00	P/F of different dias of sluice valve/ gate valve/ bend/ collars with fittings of standard make (Kirtoskar or VAGE) including all carriages upto site of work complete including tail pieces				
21.10	150mm dia sluice valve	2.00	No	15000.00	Rupees Fifteen Thousand Only
22.00	P/F of 150mm dia MS bend including cost of flanged joints, nuts, bolts, washers all carriage complete.	5.00	No	3500.00	Rupees Three Thousand Five Hundred Only
23.00	Structural steel work welded in built up sections/ framed work including cutting hoisting fixing in position and applying priming coat of approved steel primer using structural steel etc as required in gratings, frames, guard bar ladders, railing, brackets gates and similar work	723.00	Kg	100.00	Rupees One Hundred Only
24.00	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth & string courses, fillets, columns, pillars, piers abutments, post & struts etc up to floor five level excluding cost of centering, shuttering, finishing & reinforcement 1:1.5:3 (1 cement:1 1/2 course sand:3 graded crushed stone 20 mm nominal size)	55.51	Cum	8000.00	Rupees Eight Thousand Only
25.00	Centering and shuttering including strutting, propping etc and removal of form for:-				
25.10	Foundation, footings, bases of columns etc. for mass concrete.	12.00	Sqm	250.00	Rupees Two Hundred Fifty Only
25.20	Wall (any thickness) including attached plasters, buttresses, plinth and string courses etc	305.78	Sqm	400.00	Rupees Four Hundred Only
25.30	Suspended floors, roofs, landings, balconies and access platform	70.31	Sqm	521.00	Rupees Five Hundred Twenty One Only
25.40	Edges of slab and breaks in floors and walls under 20cms wide	24.00	Sqm	241.00	Rupees Two Hundred Forty One Only
26.00	Reinforcement for RCC works including Straightening cutting, bending, placing in position & binding all complete (Thermo Mechanically treated bars)	6559.00	Kg	90.00	Rupees Ninety Only
27.00	Structural steel work welded in built up section, trusses and framed work including cutting, hoisting, fixing in position and applying a primer coat of approved steel primer all complete	901.71	Kg	109.00	Rupees One Hundred Nine Only
28.00	Providing and laying in position cement concrete of specified grade excl. cost of centering & shuttering, all work up to plinth level 1:3:6 (1 cement:3 coarse sand:6 graded stone agg. 40 mm nominal size)	15.00	Cum	4900.00	Rupees Four Thousand Nine Hundred Only
29.00	Reinforce cement concrete work in beams, suspended floors, roofs having slope upto 15 degree landings, balconies, shelves, chajjas, lintels, bands, plain window sills, stair cases, and spiral cases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:2:4 (1 cement, 2 coarse sand, 4 graded stone agg 20mm nominal size)	7.92	Cum	7500.00	Rupees Seven Thousand Five Hundred Only
30.00	Filling available excavated earth (excl'd Rock) in trenches, plinth sides of the foundation etc layers not exceeding in 20 cm in depth, consolidating each deposited layer by ramming and watering lead up to 50 Mtr and lift up to 1.50 Mtr.	1940.17	Cum	150.00	Rupees One Hundred Fifty Only
31.00	Carriage of different materials from source upto site of work by mechanical transport including cost of loading, unloading and stacking complete.				
31.10	Cement + steel (avg lead 45 Kms)	23.47	M.T.	459.00	Rupees Four Hundred Fifty Nine Only
31.20	Sand (avg lead 40 Kms)	27.01	Cum	427.00	Rupees Four Hundred Twenty Seven Only
31.30	Bajri (avg lead 30 Kms)	45.52	Cum	443.00	Rupees Four Hundred Forty Three Only
31.40	Stone Soling (avg lead 5 Kms)	17.56	Cum	201.00	Rupees Two Hundred One Only
32.00	Carriage of different materials from dumping site to actual site of work by manual means. (avg lead 2000 mtrs)				
32.10	Cement	19.95	M.T.	497.00	Rupees Four Hundred Ninety Seven Only
32.20	Steel	3.52	M.T.	1050.00	Rupees One Thousand Fifty Only
32.30	Sand + Bajri	72.53	Cum	1000.00	Rupees One Thousand Only
32.40	Stone Soling	17.56	Cum	1100.00	Rupees One Thousand One Hundred Only
33.00	Extra carriage of material by head load (avg lead 500 mtrs)				

Retrofitting of Water Supply Scheme Achgoze Bamnoo by way of providing, laying & fitting of GI pipes, including construction of head works/ intake channel and RCC jacketing to old existing SSF Plant, including providing filter media and face lifting of structures including installation of 85 No. FH/C's for Achgoze Bamnoo (JJM).

33.10	Sand + Bajri	90.48	Cum	378.00	Rupees Three Hundred Seventy Eight Only
33.20	Cement	23.84	M.T.	171.00	Rupees One Hundred Seventy One Only
33.30	Steel	4.85	M.T.	368.00	Rupees Three Hundred Sixty Eight Only
33.40	Stone Solling	15.00	Cum	444.00	Rupees Four Hundred Forty Four Only
34.00	Carriage of material by MT including cost of loading unloading				Rupees Two Hundred Seventy Three Only
34.10	Stone Solling (avg lead 10 Kms)	15.00	Cum	273.00	Rupees Three Hundred Seventy Only
34.20	Sand + Bajri (avg lead 30 Kms)	90.00	Cum	370.00	Rupees Two Hundred Ninety Three Only
34.30	Cement + steel (avg lead 20 Kms)	28.69	Cum	293.00	Rupees One Lakh(s) Ten Thousand Only
35.00	Maintenance cost for a period of three years which includes 12 months DLP	1.00	Complete Job	110000.00	

Terms and Conditions:-

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However, non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (60) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- Earnest Money of ₹ 157000/- deposited by your vide CDR No. 593502 dated. 13-10-2020 has been retained in the divisional office as security deposit.
- 5- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked

Head Draftsman

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for information
- 2- District Development Commissioner Pulwama for information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Pulwama for information and necessary action.
- 4- File Concerned.

Tech. Officer

Executive Engineer
JSD (PHE) Div. Pulwama