

Allotment Order No. 62 of 07/2023

M/S : MOHAMMAD LATEEF MALIK  
 S/O : Abdullah Malik  
 R/O : Garkote Uri  
 Registration No. : 149/BK-SE-PWD/BEE/2002-03  
 TIN No./GST No:- : 01ATGPM6721K1ZR

Name of work

*Construction of Water Supply Scheme Bandi Machikrand by way of  
 Construction/ Commissioning and Testing of PSTs/SRs and other allied  
 works (for providing 100% FHTC) under JJM*

eNIT No.

: 06/Hyd/Uri of 2023-24 TENDER ID 2023\_IFC\_210603\_1

Your Tender Received  
 in response to: eNIT No:06/Hyd/Uri of 2023-24 Dated: 27/04/2023 issued under endorsement No:-  
 HDU/CC-02/420-31 Dated: 27/04/2023 (S. No: 01) Tender ID : 2023\_IFC\_210603\_1

Reference

: (i) Constitution of District Jal Jeevan Mission, Administrative Council Decision  
 No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020  
 Dated: 24-04-2020.  
(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K,  
 meeting convened on 04-09-2021.  
(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.  
(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-  
 22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-  
 2022.  
(v) UT level committee meeting held on 28-04-2022 under the Chairmanship  
 Development Commissioner Works PW (R&B).  
(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No:  
 CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.  
(vii) Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District  
 Development Commissioner Baramulla (Chairperson District JJM Bla) authorization  
 issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.  
(viii) This Office Letter No: HDU/eNIT-11/1039-40 Dated:- 30/05/2023 (viii)  
 District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No:  
 SE/Hyd/DB/1644-56 Dated: 17/05/2023

Ref: to AAA

: Accorded vide Order No. CE/PHE/DB/240 of 08/2022 Dated:- 31/08/2022.

Ref: to Tech. Sanction

: Accorded vide Order No. CE/PHE/DB/189 of 08/2022 Dated:- 31/08/2022.

LOI Issued under No:-

: NIT NO. 12/844-45 Dated:- 17/05/2023

Advertisement cost

: Rs: 44.60 Lacs

Allotted cost

: **₹ 4638254.58** Rupees Forty Six Lakh(s) Thirty Eight Thousand Two  
 Hundred Fifty Four And Paise Fifty Eight Only

Time of completion

: 120-days

M.H. of Account

: (JJM)

Ref. To CDR/TDR No.

: TDR NO: 3437439 Dated: 11/04/2023 Amount: ₹ 90,000.00

Name of the Bank

: J&amp;K Bank Branch Office Lagama

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

1 Time of completion is essence of the contract.

The work shall have to be started by you at site immediately & ensure its successful completion within a period of 120 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.

An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.

- 4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.
- 5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
- 6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
- 7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
- 8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
- 9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial
- 10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
- 11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
- 12 Earnest Money @2% deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after deposition of 03% performance security of the value of the contract
- 13 All other terms and conditions shall be applicable as laid down in Standard bid Document& PWD form No. 25/33.
- 14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.



Head Assistant

NO: HDU/CC-04/2715-27

DATED: 19-07-2023

Copy to the:

- 1 Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.
- 2 Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3 .District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4 Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information.
- 5 Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6 Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7 Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8 Chief Planning Officer Baramulla(Member DJJM) for information.
- 9 Chief Medical Officer Baramulla(Member DJJM) for information.
- 10 District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information.
- 11 District Information Officer Baramulla (Member DJJM) for information.
- 12 Assistant Executive Engineer PHE Sub Division Uri for information.
- 13 File.



Executive Engineer  
Hydraulic Division Uri  
(Syed Shafiq)


**Annexure "A" to the Allotment Order No. 62 of 07/2023**

**uction of Water Supply Scheme Bandi Machikrand by way of Construction/ Commissioning and Testing of PSTs/SRs and other allied works (for providing 100% FHTC) under JJM**

	Particulars	Qty	Unit	Rate	Amount
1	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m <sup>2</sup> on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge.				
1.1	In all kinds of soils (Bulk)	570.960	Cum	539.350	307947.28
2	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	89.180	Cum	198.700	17720.07
3	Providing and laying stone soling 2nd class	29.660	Cum	616.400	18282.42
4	Providing and laying in position cement concrete in specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	19.450	Cum	4861.835	94562.69
5	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	6.800	Cum	6465.195	43963.33
6	Providing and laying in position specified grade of reinforced cement concrete including curring but excluding cost centering shuttering finishing and reinforcement ( all work upto plinth level l: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	48.650	Cum	7800.760	379506.97
7	Reinforced Cement concrete work in wall ( any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	61.020	Cum	9408.135	574084.40
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15° landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3( 1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	6.130	Cum	9849.345	60376.48
9	Reinforced cement concrete work in arches, archibs, valluts, shelves, folded plates and roofs having slope more than 15° floor five level incliding curing but excluding cost of centering and shuttering, finshing and reinforcement	9.340	Cum	10404.515	97178.17
10	Centering and shuttering including strutting propping etc. and removal of Form work for.				0.00
10.1	Foundations, footings, bases of columns	31.750	Sqm	262.300	8328.03
10.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	596.090	Sqm	573.850	342066.25
10.3	Suspended floors, roofs, landings, balconies and access platform.	38.700	Sqm	635.690	24607.40

*(Handwritten signatures)*

	Particulars	Qty	Unit	Rate	Amount
	Ches, Domes, walls upto 60 mtr span	79.290	Sqm	2086.800	165462.37
	2mm cement plaster of mix 1:4 (1-cement: 4-sand)	684.090	Sqm	357.995	244900.80
	Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification	900.000	Kg	67.600	60840.00
13	Providing and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron embedded into concrete blocks with Angle Iron frames 50X50X6mm , Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements handles/hinges Complete Job.	1090.000	Kg	102.140	111332.60
14	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	546.710	Kg	102.140	55840.96
15	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	13325.780	Kg	87.175	1161674.87
16	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	356.500	Kg	102.140	36412.91
17	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case railing and similar works and applying primer coat	66.020	Kg	190.190	12556.34
18	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)				0.00
18.1	65mm dia	6.000	Nos	5000.000	30000.00
18.2	50mm dia	4.000	Nos	3500.000	14000.00
19	Providing and fixing GI Bend in dome slab with one and provided with wire guage mesh. The bends are to be fixed in dome slab during concreting for elevation purpose quality				0.00
19.1	100mm dia	18.000	Nos	600.000	10800.00
19.2	50mm dia	12.000	Nos	500.000	6000.00
20	Providing and fixing of PVC ISIS Mark inside concrete wall for inlet and outlet of 40mm/50mm dia engh	40.000	No	200.000	8000.00
21	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shhall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer				0.00
21.1	Cement and Steel (50Kms)	74.210	Mton	578.439	42925.96
21.2	Sand. (60 kms)	87.980	Cum	711.873	62630.59
21.3	Agg. 20mm (100Kms)	121.700	Cum	1068.005	129976.21
21.4	Agg. 40mm (100Kms)	18.098	Cum	1160.799	21008.14
21.5	Stone Soling 7km	29.660	Cum	277.770	8238.66
22	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shhall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer 1000mtr				0.00
22.1	Cement	63.590	Mton	460.460	29280.65




Particulars	Qty	Unit	Rate	Amount
Steel	10.620	Mton	989.138	10504.65
Sand.	87.980	Cum	1078.217	94861.53
Agg. 20mm	121.700	Cum	1078.217	131219.01
Agg. 40mm	18.098	Cum	1165.594	21094.92
Stone Soling (500Mtrs)	29.660	Cum	730.800	21675.53
			<b>Total</b>	<b>4459860.17</b>

Excess (+)	4.000%
------------	--------

**4638254.58**

*Rupees Forty Six Lakh(s) Thirty Eight Thousand Two Hundred Fifty Four And Paise Fifty Eight Only*

Checked by

Head D/Man  


  
**Executive Engineer**  
**Hydraulic Division Uri**