

Government of Jammu and Kashmir
OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI
email: urihydraulic@gmail.com

Allotment Order No. 71 of 11/2022

M/S	:	Shafi & Co.
Prop	:	Nazir Ahmad Check
S/O	:	Late Mohammad Shafi Check
R/O	:	Uranbowa
Registration No.	:	12/SE/Hyd/AA/Hand/2003-04
TIN No./GST	:	01AEXPC7059N1Z0

Name of work : Construction of Water Supply Scheme Boniyar by way of Construction/Commissioning and Testing of PSTs/ SRs/SSFPs/ and Chain Link Fencing (for providing 100% FHTC) under JJM

eNIT No. : 16 /Hyd/Uri of 2022-23 TENDER ID 2022_IFC_178555_43
Your Tender Received in response to : eNIT No:16/Hyd/Uri_of_2022-23 Dated: 08/07/2022 issued under endorsement No:- HDU/CC-02/1378-88 Dated: 08/07/2022 (S. No: 51) Tender ID : 2022_IFC_178555_43

Reference : (i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.
(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.
(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.
(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.
(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).
(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.
(vii) Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/2022/1214-44 Dated: 24-05-2022.
(viii) District Superintending Engineer Hyd. Circle Bla/Bpr HO Sopore authorization No: SE/Hyd/DB/5675-87 Dated:-17/08/2022

Ref: to AAA : Accorded vide Order No. 88/SE/Hyd/DB/JJM of 2022-23 ted:- 24/09/2022. issued under Endorsement No:- SE/Hyd/DB/8333-38 Dated:- 24/09/2022.

Ref: to Tech. Sanction : Accorded by Superintending Engineer Hydraulic Circle Sopore vide Order No. 88/SE/Hyd/DB/JJM of 2022-23 ted:- 24/09/2022. issued under Endorsement No:- SE/Hyd/DB/8333-38 Dated:- 24/09/2022.

LOI issued under NO:- : HDU/CC-02/2213-26 Dated:- 30/08/2022

Advertisement cost : Rs:89.09Lacs

Allotted cost : ₹ 9265869.13

Rupees Ninety Two Lakh(s) Sixty Five Thousand Eight Hundred Sixty Nine And Paise Thirteen Only

Time of completion : 120-days

M.H. of Account : (JJM)

Ref. To CDR No. : CDR NO: 3136427 Dated: 17/05/2022

Name of the Bank : J&K Bank Ltd. Amount: ₹ 162,800.00

Branch Office Chandanwari

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

- 1 Time of completion is essence of the contract.
- 2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of 120 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.
- 3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.
- 4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.
- 5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.
- 6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.
- 7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise, you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.
- 8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.
- 9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.
- 10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.
- 11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.
- 12 Earnest Money @2% deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depoition of 03% performance security of the value of the contract
- 13 All other terms and conditions shall be applicable as laid down in Standard bid Document & PWD form No. 25/33.
- 14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.


Checked by

Head Draftsman

NO: HDU/CC-04/ 3456-67

DATED: 05-11-2022

Copy to the:


Technical Officer to
Executive Engineer
Hydraulic Division Uri


Executive Engineer
Hydraulic Division Uri

- 1 Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.
- 2 Chief Engineer Kashmir PHE Department Srinagar for favour of information.
- 3 District Development Commissioner Baramulla (Chairperson DJJM) for favour information.
- 4 Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No: 5675-87 Dated: 17/08/2022.
- 5 Additional District Development Commissioner Baramulla (Member DJJM) for information.
- 6 Assistant Commissioner Development Baramulla (Member DJJM) for information.
- 7 Divisional Forest Officer Baramulla (Member DJJM) for information.
- 8 Chief Planning Officer Baramulla (Member DJJM) for information.
- 9 Chief Medical Officer Baramulla (Member DJJM) for information.
- 10 District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla (Member DJJM) for information
- 11 District Information Officer Baramulla (Member DJJM) for information.
- 12 Assistant Executive Engineer PHE Sub Division Uri for information. This is in continuation to this office LOI issued under No: HDU/CC-02/2213-26 Dated:- 30/08/2022
- 13 File.

Annexure "A" to the Allotment Order No. 71 of 11/2022

Construction of Water Supply Scheme Boniyar by way of Construction/Commissioning and Testing of PSTs/ SRs/SSFPs/ and Chain Link Fencing (for providing 100% FHTC) under JJM

S#	Particulars	Qty	Unit	Rate	Amount
1.00	EW in excavation by manual means in trenches for foundations, drains, pipes, cables etc (Not exceeding 1.5 mtr in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, depth upto 1.5 mtr including disposal of excavated earth within 1km from cutting edge, disposed earth to be leveled and neatly dressed :				
1.10	In all kinds of soils	828.300	Cum	539.000	446453.70
2.00	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	141.760	Cum	198.700	28167.71
3.00	Providing and laying stone soling 2nd class incl. cost of stones and all sorts of carriages etc.)	41.500	Cum	616.400	25580.60
4.00	Providing and laying in position cement concrete in specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level. 1 : 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.(Including cost of all sorts of carriages of material upto site of work)	38.590	Cum	4861.835	187618.21
5.00	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)(Including cost of all sorts of carriages of material upto site of work)	113.790	Cum	6465.195	735674.54
6.00	Providing and laying in position specified grade of reinforced cement concrete including curring but excluding cost centering shuttering finishing and reinforcement (all work upto plinth level : 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed(Including cost of all sorts of carriages of material upto site of work)	68.500	Cum	7800.760	534352.06
7.00	Reinforced Cement concrete work in wall (any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.(Including cost of all sorts of carriages of material upto site of work)	87.210	Cum	9408.135	820483.45
8.00	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 150 landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size) (Including cost of all sorts of carriages of material upto site of work)	5.990	Cum	9849.345	58997.58

S#	Particulars	Qty	Unit	Rate	Amount
9.00	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. (Including cost of all sorts of carriages of material upto site of work)	1314.650	Kg	146.830	192767.13
10.00	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case railing and similar works and applying primer coat Including cost of all sorts of carriages of material upto site of work)	100.010	kg	190.190	19020.90
11.00	Reinforced cement concrete work in arches, arches, vaults, shelves, folded plates and roofs having slope more than 150 floor five level including curing but excluding cost of centering and shuttering, finishing and reinforcement (Including cost of all sorts of carriages of material upto site of work)	4.230	Cum	10404.515	44011.10
12.00	Centering and shuttering including strutting propping etc. and removal of Form work for.				0.00
12.10	Foundations, footings, bases of columns	42.130	Sqm	262.300	11050.70
12.20	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	1186.460	Sqm	573.850	680850.07
12.30	Suspended floors, roofs, landings, balconies and access platform.	46.510	Sqm	635.600	29561.76
12.40	Arches, Domes, walls upto 60 mtr span	35.240	Sqm	2086.800	73538.83
12.50	Columns	25.200	sqm	680.150	17139.78
13.00	12mm cement plaster of mix 1:4 (1-cement: 4-sand) (Including all sorts of carriages upto site of work)	940.710	Sqm	378.125	355705.97
14.00	Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification including all sorts of carriages upto site of work complete	335.000	Kg	61.500	20602.50
15.00	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars. (Including cost of all sorts of carriages of material upto site of work)	22069.180	Kg	87.175	1923880.77
16.00	Supplying ast site angle iron post and strut of 50 mm x 50mm x 6mm including bootom to split and bent at right ange in opposite direction for 10cm length abnd drelling holes up to 10mm dia extra complete	1301.000	kg	88.500	115138.50
17.00	structural steel in single section / fixed with without conneting plate including curtting hosiiting , fixing in position and applying primering coat of apprived and all job complete	2372.000	kg	102.000	241944.00
18.00	Providing and fixing of G.I chain linkfabric fencing of required wedith in mesh size 50x50 mm including strengthing with 2 m dia wire and nuts , bolts abd washer are required complete as per the dir4ection of Engineer incharge. Made of G. I wire of dia 4mm	350.010	Sqm	733.500	256732.34
19.00	Providing and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron embedded into concrete blocks with Angle Iron frames 50X50X6mm , Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements handles/hinges Complete Job.	1090.000	Kg	112.000	122080.00
20.00	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	242.610	Kg	102.000	24746.22

S#	Particulars	Qty	Unit	Rate	Amount
21.00	Providing and fixing of PVC ISIS Mark inside concrete wall for inlet and outlet of 40mm/50mm dia engh	50.000	No	200.000	10000.00
22.00	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)				0.00
22.10	65mm dia	8.000	Nos	9000.000	72000.00
23.00	Providing and laying of filter media as per direction of Engineer incharge source from ganderbal all kinds of carriage up to actual site of work complete job.	88.560	Cum	8500.000	752760.00
24.00	Providing and fixing 50mmDia GI Bend in dome slab with one and provided with wire guage mesh. The bends are to be fixed in dome slab during concreting for elevation purpose quality	12.000	No	500.000	6000.00
25.00	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shhall be paid strictly as per SSR of Rates 2012 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer				0.00
25.10	Cement and Steel	151.520	Mton	445.950	67570.34
25.20	Sand.	162.550	Cum	551.330	89618.69
25.30	Agg. 20mm	252.230	Cum	998.450	251839.04
25.40	Agg. 40mm	34.782	Cum	1085.200	37745.43
26.00	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shhall be paid strictly as per SSR of Rates 2012 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer (500-1000Mtrs)				0.00
26.10	Cement	118.550	Mton	580.630	68833.69
26.20	Steel	32.970	Mton	989.130	32611.62
26.30	Sand.	162.550	Cum	1078.210	175263.04
26.40	Agg. 20mm	252.230	Cum	1078.210	271956.91
26.50	Agg. 40mm	34.782	Cum	1165.570	40540.86
26.60	Stone Soling (100-mtrs)	57.550	Cum	1158.150	66651.53
				Total	8909489.55

Excess (+)

4.00%

9265869.134

Rupees Ninety Two Lakh(s) Sixty Five Thousand Eight Hundred Sixty Nine And Paise-Thirteen Only

Checked by

Head D/Man

Executive Engineer
Hydraulic Division Uri