

Government of Jammu & Kashmir

OFFICE OF THE EXECUTIVE ENGINEER PHE DIVISION SOPORE

M/s: Classic Construction Co.
Prop: Shabir Mustafa Rafiqi,
R/o: 28-A Polo View Srinagar Kmr.

No: PHE/JS/Spr/lec/2013-21
Dated: 13-06-2022


Subject: Construction Testing Commissioning of Over Head Tanks (OHT) along with allied works in different Divisions/Districts of Kashmir province under Jal Jeevan Mission (JJM).

- Ref: 01. Chief Engineer Kmr Jal Shakti PHE Department Sgr's E- NIT No. 129 of 2021-22 , dt. 21-02-2022.
02. This office letter of intent issued under No 1562-67 dated: 27-05-2022.

For and on behalf of Lt. Governor of Union Territory of Jammu and Kashmir, Contract for the work namely **Construction/Testing/Commissioning of 0.40 Lac Gallon Capacity OHT of Shell type with staging height of 20mtrs including construction of sluice chamber at Maidanpora for WSS Maidanpora Naidkhai** is hereby allotted to you in accordance with all the terms and conditions as laid down in the bid document read with any amendment if any, for an amount of **Rs. 8421365.00 (Rupees Eighty-four lac twenty-one thousand three hundred sixty-five only)** as per the following item rates along-with your quoted overall tender appreciation of **7% (Seven percent)**. This is in continuation to the letter of Intent referred above.

A Rates:

S No.	Description of Work / Item(S)	Unit	Qty	Unit Rate (Rs)	Amount (In Rs)
1	Earth work in bulk excavation by mechanical means (hydraulic excavator) over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m ² on plan) including disposal of excavated earth lead up to 50 meters and lift up to 1.5 m,	Cum	590.00	188.75	111362.50
2	Extra for every additional lift of 1.5 m or part thereof in excavation/banking excavated or stacked material				
a	All kinds of soil:	Cum	338.30	81.65	27622.20
3	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m ² on plan) including disposal of excavated earth lead up to 50 meters and lift up to 1.5 m, as directed by Engineer-in-Charge.				
a	All kinds of soil:	Cum	147.80	539.35	79715.93
4	Pumping out water caused by springs, tidal or river seepage, broken water mains or drains and the like.	IKL	338.30	155.55	52622.57



S No.	Description of Work / Item(S)	Unit	Qty	Unit Rate (Rs)	Amount (In Rs)
5	Close timbering in trenches including strutting, shoring and packing cavities (wherever required) complete. (Measurements to be taken of the face area timbered). 2.14.2 Depth exceeding 1.5 m but not exceeding 3 m	sqm	30.00	247.75	7432.50
6	Providing and laying 75 mm size hand packed stone soling (Quarry) including ramming and dressing including all leads lifts and all carriages complete.	Cum	79.37	1320.00	104768.40
7	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work up to plinth level with:				
a	1:4:8 (1 cement: 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	Cum	24.90	4861.84	121059.69
8	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of cantering, shuttering, finishing and reinforcement. All works up to plinth level				0.00
a	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	115.97	7800.76	904654.14
9	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts up to floor five level including curing but excluding cost of cantering shuttering, finishing and reinforcement.				0.00
a	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	89.03	9408.14	837606.26
10	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of cantering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in charge. Note: - Cement in this item is @ 330 kg/cum. Excess or less cement used as per design mix is content considered payable or recoverable separately.		1.00		0.00
A	All works above plinth level up to floor V level	Cum	37.06	9302.98	344768.25

S No.	Description of Work / Item(S)	Unit	Qty	Unit Rate (Rs)	Amount (In Rs)
11	Extra for providing richer mixes at all floor levels. Note:- Excess/ less cement over the specified cement content used is payable/ recoverable separately. 5.35.1 Providing M-30 grade concrete instead of M-25 grade BMC/RMC. (Note:- Cement content considered in M-30 is @ 340 kg/cum)	Cum	37.06	111.87	4145.90
12	Cantering and shuttering including strutting, propping etc. and removal of form for:				0.00
A	Foundations, footings, bases of columns etc. for mass concrete.	Sqm	26.87	262.30	7048.00
B	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	Sqm	927.58	573.85	532291.78
C	Suspended floors, roofs, landings, balconies and access platforms.	Sqm	11.49	635.60	7303.04
D	Lintel, beams, plinth beams, girders, bressummers and cantilevers.	Sqm	83.32	502.85	41897.46
E	Spiral staircases (including landings)	Sqm	57.57	619.80	35681.89
F	Arches, domes, vaults up to 6 m span	Sqm	100.92	2086.80	210599.86
G	Extra for arches, domes, vaults exceeding 6 m span	Sqm	100.92	1008.45	101772.77
H	Extra for shuttering in circular work (20% of respective cantering and Shuttering items)	Sqm			
I	Foundations, footings, bases of columns etc. for mass concrete.	Sqm	22.80	52.46	1196.09
J	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	Sqm	892.38	114.77	102418.45
K	Lintel, beams, plinth beams, girders, bressummers and cantilevers.	Sqm	83.32	100.57	8379.49
13	Providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification. (1 kg of water proofing material in 50 kg of cement)	kgs	450.00	57.90	26055.00
A	Extra for R.C.C./B.M.C./R.M.C. work above floor V level for each four floors or part thereof.	cum	60.40	309.05	18666.62
14	Steel reinforcement for R.C.C. work ready to use "cut and bend" rebars of approved make from factory/workshop to construction site including placing in position and binding all complete Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	26855.00	87.18	2341084.63
15	CEMENT PLASTER WITH A FLOATING COAT OF NEAT CEMENT 12mm Cement plaster finished with a floating coat of neat cement of mix:1 : 3 (1 cement : 3 fine sand)	sqm	326.26	343.75	112151.88
16	EXTERIOR FINISHING Finishing walls with water proofing cement paint of required shade on New work (two or more coats applied @ 3.84 kg/10sqm)	sqm	485.14	91.80	44535.85

[Handwritten signature and initials]

S No.	Description of Work / Item(S)	Unit	Qty	Unit Rate (Rs)	Amount (In Rs)
17	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	Cum	928.30	198.70	184453.21
18	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6mm angle iron and 3mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer.				0.00
A	Using M.S. angles 40x40x6mm for diagonal braces.	sqm	2.56	4352.95	11143.55
19	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. chequered plate wherever required, all complete.				0.00
A	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	Kg	1860.00	146.63	272731.80
20	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel primer.				0.00
A	M.S. tube	Kg	203.00	172.90	35098.70
21	Providing and fixing G.I. pipes (B medium) complete with G.I. fittings excluding trenching and refilling etc. (external work) for rising main and delivery main of OHT.				0.00
A	100 mm dia. nominal bore	Mtr	100.00	1234.95	123495.00
B	150 mm dia. nominal bore	Mtr	200.00	2167.65	433530.00
22	Providing and fixing D.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately).				0.00
A	80 mm dia. Class 1	Each	2.00	14058.00	28116.00
B	100 mm dia. Class 1	Each	4.00	17210.00	68840.00
C	150 mm dia. Class 1	Each	2.00	26720.00	53440.00
23	Providing & fixing of MS fittings viz bends of suitable degree, tees, collars etc to be fabricated from 8mm or 10mm MS plate as per the requirement of site including cost of welding. The work should be leakproof and should be painted with anti corrosive red oxide primer. Complete Job.	Kg	571.00	147.82	84405.22
24	Providing and fixing of MS flanged joints (8mm to 12mm thick) to double flanged GI/DI pipes including cutting of pipes, welding charges, cutting of flanges, rubber gasket, bolts, nuts including testing of joint and sorts of carriages. Complete Job.				0.00
A	100 mm dia. pipe	Joint	20.00	1520.00	30400.00

S No.	Description of Work / Item(S)	Unit	Qty	Unit Rate (Rs)	Amount (In Rs)
B	150 mm dia. pipe	Joint	34.00	2150.00	73100.00
25	Providing & fixing ventilator of size 450mm x 450mm made out of angle iron 40mm x 40mm with wire mesh of 25mm x 25mm size including welding charges & including all carriages upto site of work.	No	1.00	1500.00	1500.00
26	Providing & fixing of 0.63mm thick PGI sheets at construction joints including all leads and lifts complete job as directed by Engineer-in-charge	Sqm	10.30	800.00	8240.00
27	Carriage of materials by mechanical transport including loading, unloading, stacking of materials				0.00
A	Cement and Steel for an average lead of 15kms	MT	137.60	270.91	37276.53
B	Sand And 20mmAggregates for average lead 20kms	Cum	341.40	402.39	137375.95
C	20mm Above Aggregates average lead 20kms	Cum	22.20	437.30	9708.06
28	Supply, installation, testing and commissioning of Advanced Maintenance Free environment friendly Earthing system consisting of 1 no. of 3mtr length, 17.2 mm dia UL certified earth electrode made of high tensile low carbon steel circular rods, molecularly bonded copper on outer surface (minimum copper bonding thickness-250 microns) with GI terminals to connect incoming strips, (Environment friendly backfill compound duly certified as per ANSI/NSF standard 60/Toxic content certificate as safe for use near potable ground water resources strictly as per specification enclosed. Make- SHREE ELECTRODES/OBO BETTERMANN/ERICO(2 Nos UPS and 4 Nos Main L.T Panel/2 Nos Fire Fighting Panel)	Nos	1.00	15800	15800.00
29	Providing and Fixing 25 mm x 5 mm Copper Strip in 40 mm dia. G.I Pipe FRL Earth Electrode including connection with Brass nut ,bolt, spring, washer, excavation and refilling etc. as required.	Rmt	60.00	1224	73440.00
30	Supply, installation, testing and commissioning of lightening conductor made of 25 mm dia 300 mm long copper tube having single prong at top with base plate.	unit	1.00	1500	1500.00
Total Amount				Rs.	7870435.00
Add 7% on all items:				Rs.	550930.00
Grand Total:				Rs.	8421365.00

(Rupees Eighty four lac twenty one thousand three hundred sixty five only)

A Note:


- Total value of the work is Rs. **84.213 lacs** worked out on the basis of above quoted rates which includes all taxes, levies etc. and as per the drawing provided vide Chief Engineer Kashmir Jal Shakti PHE Department Srinagar's No.3337-43 dt. 12.05.2022.
- The date of start of the subject work shall be reckoned from the date of issuance of this allotment order. Given the fact that letter of intent stands already issued vide this office letter No. 1562-67 Dated. 27.05.2022, in case of failure to start the work within three

days of issuance of this allotment order action as warranted shall be initiated.

03. An agreement shall have to be drawn by you with the department within a period of 07 days from the date of issuance of this allotment order. Failure to execute such a formal deed shall not, however prevent the contract from being enforced upon you. However, payment shall not be made unless the agreement is drawn.
04. Performance security equivalent to **03%** of the value of the contract (Rs.253000.00 Rupees two lac fifty three thousand only) valid in accordance with bid conditions, shall have to be furnished by you in shape of CDR/FDR/BG within one week from the date of issuance of allotment order or at the time of signing of agreement whichever is earlier.
05. All other terms and conditions and technical specifications shall remain the same as laid down in standard bid document of the subject E-NIT read with Corrigendum, minutes of Pre-bid meeting.


Head Assistant


I/c Head Draftsman


Executive Engineer
Jal Shakti PHE Division
Sopore

Copy to the:

01. Mission Director Jal Javen Mission Civil Secretariat Srinagar for favour of information.
02. Chief Engineer Kashmir Jal Shakti PHE Department Srinagar for favour of information.
03. District Development Commissioner Bandipora (Chairman DJJM) for favour of information.
04. Director Planning Jal Shakti Civil Secretariat Srinagar for favour of information.
05. Superintending Engineer Hydraulic Circle Baramulla/Bandipora (Member Secretary JJM) for favour of information.
06. Assistant Executive Engineer PHE Sub Division Sumbal for information and necessary action.
07. M/S WAPCOAS Ltd Corporate office 76-C intuitional area sector 18 Gurgon for information.
08. File Concerned.