

## OFFICE OF THE EXECUTIVE ENGINEER, JSD (PHE) DIVISION, PULWAMA

No. PHEPI/1185-88  
Dated: 07-06-2021Mr. Mohammad Shafi Dar,  
Contractor,  
S/o. Ghulam Nabi,  
R/o Rohmu-Pulwama,  
Regd. No. CE/UEED/BE/338/2003-04

Sub :- Retrofitting of Water Supply Scheme Mehrud Utterpora by way of Providing &amp; laying of GI pipes, CGI roofing to pump operator quarter, improvements to bathroom including installation of 128 No. FHTC's for Mehrud Utterpora (JJM).

Ref:- 1- E-NIT S.No. 03/PHEP/Fresh of 2021-22, job No. (5), Circulated vide this office No. PHEP/345-57 Dated:- 19-04-2021

2- Suptdg. Engineer Hydl. Circle, Shopian's letter No. SE/Hyd/915-16 dtd. 31-05-2021

~~3- Executive Engineer, PHE (Mech) Divn, South Anantipora's letter No. MDSA/300 dtd. 08-06-2021~~

Advertised Amount of work: ₹ 17,68,000.00

Alloted Amount of Work: ₹ 16,51,600.00

**Rupees Sixteen Lakh(s) Fifty One Thousand Six Hundred Only**

For and on behalf of the Lt. Governor Union Territory of J&amp;K, the contract for the above noted work is hereby

fixed with you at the following rates quoted/accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No. or Qty.	Unit	Estd. Rate	RATE	
					Figures	Words
1.00	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc (not exceeding 1.5mtr in width) and for shafts, wells, cesspits, and the like not exceeding 10sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5m, including getting out excavated earth and disposal of surplus excavated earth as directed All kinds of soils	430.95	Cum	436.00	400.00	Rupees Four Hundred Only
2.00	Providing and laying S&S Centrifugally Cast (Spun) Ductile Iron Pipes conforming to IS : 8329 100 mm dia Ductile Iron Class K - 7 Pipes	500.00	Mtr	1108.15	1108.15	Rupees One Thousand One Hundred Eight And Paise
3.00	Providing and fixing G.I. pipes complete with G.I. fittings excluding trenching and refilling etc. (external work)					
3.10	50 mm dia G.I pipes	300.00	Cum	RQC	477.50	Rupees Four Hundred Seventy Seven And Paise Fifty Only
3.20	40 mm dia G.I pipes	390.00	Cum	RQC	388.05	Rupees Three Hundred Eighty Six And Paise Five Only
3.30	25 mm dia G.I pipes	500.00	Cum	RQC	249.00	Rupees Two Hundred Forty Nine Only
3.40	20 mm dia G.I pipes	500.00	Cum	RQC	182.65	Rupees One Hundred Eighty Two And Paise Sixty Five Only
3.50	15 mm dia G.I pipes	336.00	Cum	RQC	130.00	Rupees One Hundred Thirty Only
4.00	Making connection of G.I distribution branch with G.I main of following size by providing and fixing tees, including cutting and threading the pipe etc complete					
4.10	(a) 25 to 40 mm nominal bore	20.00	No	666.25	400.00	Rupees Four Hundred Only
4.20	(b) Above 40 mm nominal bore	8.00	No	1268.75	800.00	Rupees Eight Hundred Only
5.00	Filling available excavated earth (Excl. rock) in trenches, plinth sides of foundation etc. layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering lead upto 50mtr and lift upto 1.5mtr	387.85	Cum	198.70	130.00	Rupees One Hundred Thirty Only
6.00	Providing fixing double flanges C.I sluice valves of standard quality Kirlosker /vage make conforming to IS 780 of 1984 read with upto date amendments standard mark ISI make PN-1 including cost of nuts bolts IR cloth including all sorts of carriage upto site of work complete job including cost of pedestals and handles (to be paid as per actual details with supporting vouchers duly verified by AEE concern ) 100 mm dia sluice valve	4.00	No	RQC	12000.00	Rupees Twelve Thousand Only
7.00	Structural steel work in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. Welded	1120.00	Kg	92.85	90.00	Rupees Ninety Only

2

**Retrofitting of Water Supply Scheme Mahrud Uttarpara by way of Providing & laying of GI pipes, CGI roofing to pump operator quarter, improvements to bathroom including installation of 12B No. FHTG's for Mahrud Uttarpara (JAM)**

8.00	Providing corrugated GI sheet roofing including vertical / curved surface with polymer coated J or L hooks, bolts and nuts 8mm diameter and GI hinged washers or with GI filled with white lead, including coat of approved steel primer and two coats of approved paint on overalls of sheets complete (upto any pitch in horizontal / vertical or curved surface) excluding the cost of pulley, rafters and trusses and including cutl to size and shape wherever required 0.8mm thick with zinc coating not less than 270gram/m <sup>2</sup>	41.80	Sqm	661.60	660.00	Rupees Nine Hundred Only
9.00	Providing ridges or hips of width 60cm overall with plain GI sheets fixed with polymer coated J or L hooks, bolts and nuts 8mm dia GI hinged and bitumen washers complete with 0.8mm thick with zinc coating not less than 270 gram/m <sup>2</sup>	8.00	Mtr	691.35	690.00	Rupees Six Hundred Only
10.00	Providing and fixing planned eaves boarding. 250x32 mm (nominal size)	12.00	Mtr	693.00	690.00	Rupees Five Hundred Fifty Only
11.00	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centering and shuttering. All work upto plinth level with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	3.39	Cum	5877.45	5500.00	Rupees Five Thousand Five Hundred Only
12.00	Providing and fixing of sanitary items of standard quality like 1000 liters sphyax, W.C Indian type, flush tank, with all accessories, pvc pipe, pipe specials, C.P items, p trap, floor trap, bends, steel sink, connecting with soakage, whichever be necessary to make functional all complete. (to be paid as per actual details /measurements with supporting vouchers)	1.00	Job	RQC	20000.00	Rupees Twenty Thousand Only
13.00	Providing and applying white cement based putty of specified thickness, of approved brand and manufacturer, over the plastered wall surface to prepared the surface even and smooth complete 2 mm thick	176.61	Sqm	172.40	170.00	Rupees One Hundred Seventy Only
14.00	Applying priming coats with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanized iron/ steel works	111.48	Sqm	62.75	60.00	Rupees Fifty Only
15.00	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work	163.28	Sqm	121.95	120.00	Rupees One Hundred Twenty Only
16.00	Providing fixing supplying P.C.C rings including earthwork excavation and disposal of surplus excavated material outside the premises including providing and laying cement concrete in 1:2:4 mix over septic tank and soakage pit. construction of man hole chambers with angle iron frame and covering arrangements providing fixing of P.V.C pipe (prince make B class) including bends whichever is required at site or as per directions of Engineer- in- charge (3 compartments for septic tank and 1 for soakage pit). (to be paid as per actual details /measurements)	13.00	Mtr	RQC	600.00	Rupees Eight Hundred Only
17.00	Repairs to rolling shutter by way of providing ball bearings nuts, welding, including priming painting greasing whichever is required to make functional (to be paid as per actual details /measurements with supporting vouchers)	1.00	Job	RQC	5000.00	Rupees Five Thousand Only
18.00	Carriage of material from source of site upto site of work by mechanical transport including loading unloading stacking at site complete					
18.10	Band and flajir avg lead 10km	4.67	Cum	244.27	200.00	Rupees Two Hundred Only
18.20	Cement and steel avg lead 10km	1.06	M.T.	217.09	200.00	Rupees Two Hundred Only

**Terms and Conditions:-**

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However the non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (02) Months and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked

Head Draftsman

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for Information
- 2- District Development Commissioner Pulwama for Information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Tahab for Information and necessary action.
- 4- File Concerned.

*(Signature)*  
T.O

*(Signature)*  
Executive Engineer,  
SD (PHE) Div. Pulwama