

No. PHEP/..... 635-38
Dated: 01.05.2021

Mr. Bashir Ahmad Naik,
Contractor,
S/o. Ghulam Ahmad Naik,
R/o Zagigam, Pulwama
Regd. No. 24/AAY/SE/HYDL/SHOPIAN/2004-05

Sub :- Retrofitting of Water Supply Scheme "Pachhar Gulshanabad" by way of Providing & laying of GI pipes, construction of chowkidar quarter, revamping of filtration plant, face lifting of various structures and RCC jacketing to SSF Plant including laying of filter media including installation of 238 No. FHTC's for Pachhar Gulshanabad including maintenance for a period of three years which includes IDLP of 12 months.(JJM).

Ref:- E-NIT S.No. 127/PHEP/Fresh of 2020-21, job No. (1), Circulated vide this office No. PHEP/7020-33 Dated:- 05-03-2021

.....
Advertised Amount of work: ₹ 42,62,000.00 ✓
Alloted Amount of work: ₹ 41,90,000.00 ✓
Rupees Forty One Lakh(s) Ninety Thousand Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following negotiated rates as accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No.or Qty.	Unit	Estd. Rate	RATE	
					Figures	Words
1.00	Repairs to plaster of thickness 12mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape raking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to the dumping ground within 50 meters lead With cement mortar 1:4 (1 cement : 4 fine sand)	11.67	Sqm	403.85	350.00	Rupees Three Hundred Fifty Only
2.00	Fixing old glass panes with wooden fillets (excluding cost of fillets)	6.90	Sqm	485.40	490.00	Rupees Four Hundred Ninety Only
3.00	Providing & laying damp-proof Course 40 mm thick with cement concrete 1:2:4 (1 cement:2 coarse sand: 4 graded stone agg 12.5 mm nominal size) and curing complete	21.40	Sqm	310.55	290.00	Rupees Two Hundred Ninety Only
4.00	Providing and fixing glazed shutters for doors, windows and clerestory windows using 4mm thick float glass panes including ISI marked M.S pressed butt hinges bright finish of required size with necessary screws. Second class Kail wood	12.00	Sqm	3338.05	3200.00	Rupees Three Thousand Two Hundred Only
5.00	Providing and fixing wire gauze shutters using galvanized M.S. wire gauze of average width for aperture 1.4 mm in both directions with wire of dia. 0.63 mm for doors, windows and clerestory windows with ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws as per direction of Engineer-in-charge : Second class Kail wood	14.70	Sqm	3307.80	3000.00	Rupees Three Thousand Only
6.00	Providing and fixing plained eaves boarding 300x40 mm (nominal size)	16.00	Mtr	958.85	800.00	Rupees Eight Hundred
7.00	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	1000.00	Liter	11.25	10.00	Rupees Ten Only
8.00	Providing fixing supplying 35 liters capacity gyser (of haveli make) including C.P pipes , angle valves, etc which ever is required at site (to be paid as per actual details / supporting documents duly verified by AEE concern)	1.00	Job	RQC	12500.00	Rupees Twelve Thousand Five Hundred Only
9.00	Clearance of silt including disposal of silt outside the premises all leads lifts complete (to be paid as per details/ measurements)	6155.00	Cft	RQC	10.00	Rupees Ten Only
10.00	Removing of filter media mixed with silt including disposal of silt outside the premises all leads lifts complete (to be paid as per details/ measurements)	7170.00	Cft	RQC	8.00	Rupees Eight Only
11.00	Washing of filter media after taking out from plant including removing of unserviceable material outside the premises complete (to be paid as per details/ measurements)	5735.80	Cft	RQC	6.00	Rupees Six Only
12.00	Relaying of filter media after washing into plant in layers all complete (to be paid as per details/ measurements)	5735.80	Cft	RQC	5.00	Rupees Five Only
13.00	Providing , laying of filter media from Gandarbal of various grades including all carriages leads lifts and placing in layers into plant complete job (to be paid as per details/ measurements)	108.22	Cum	RQC	7300.00	Rupees Seven Thousand Three Hundred Only
14.00	Providing fixing double flanges C.I sluice valves of standard quality Kirloskar /vage make conforming to IS 780 of 1984 read with upto date amendments standard mark ISI make PN-1 including cost of nuts bolts IR cloth including all sorts of carriage upto site of work complete job including cost of pedestals and handles (to be paid as per actual details with supporting vouchers duly verified by AEE concern) (a) 100 mm dia sluice valve	2.00	No	RQC	14000.00	Rupees Fourteen Thousand Only
15.00	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth. Lead upto 50 meter and lift upto 1.5m, as directed by Engineer-in-Charge. All kinds of soil.	1150.00	Sqm.	83.45	70.00	Rupees Seventy Only
16.00	Applying priming coat with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanized iron/steel works	168.00	Sqm	52.75	52.75	Rupees Ffty Two And Paise Seventy Five Only
17.00	Painting on G.S sheets with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade on New work (two or more coats) including a coat of approved steel primer but excluding a coat of mordant solution	210.00	Cum	140.10	140.10	Rupees One Hundred Forty And Paise Ten Only

2
 ting of Water Supply Scheme Pachhar Gulshanabad by way of Providing & laying of GI pipes,
 ruction of chowkidar quarter, revamping of filtration plant, face lifting of various structures and RCC
 eting to SSF Plant including laying of filter media including installation of 238 No. FHTC's for Pachhar
 ulshanabad including maintenance for a period of three years which includes DLP of 12 months.(JJM).

	Finishing walls with water proofing cement paint of required shade on New work (two or more coats applied @ 3.84 kg/10sqm)	336.00	Sqm	91.80	91.80	Rupees Ninety One And Paise Eighty Only
19.00	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade on New work (two or more coats) over and including priming coat with water thinable cement primer	120.00	Sqm	149.05	153.00	Rupees One Hundred Fifty Three Only
20.00	Providing and laying of stone soling hand packed including watering dressing and ramming all complete	5.17	Cum	612.20	600.00	Rupees Six Hundred Only
21.00	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size)	5.17	Cum	4908.20	3700.00	Rupees Three Thousand Seven Hundred Only
22.00	Providing fixing of sign board including writing , painting , earthwork , concrete work for fixing of angle iron poles and M/S board including all accessories complete (to be paid as per actual details /measurements)	1.00	No	RQC	10000.00	Rupees Ten Thousand Only
23.00	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, filets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	5.85	Cum	8552.85	8000.00	Rupees Eight Thousand Only
24.00	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	15.65	Cum	7091.60	6700.00	Rupees Six Thousand Seven Hundred Only
25.00	Centring shuttering including strutting , propping etc. and removal of form work for					
25.10	Lintel, beams, plinth beams, girders, bressumers and cantilevers.	55.04	Sqm	502.85	400.00	Rupees Four Hundred Only
26.00	Steel reinforcement for RCC work including straightening, cutting , bending , placing in position and binding all complete upto plinth level thermo -Mechanically -Treated bars of grade Fe-500D or more	468.00	Kg	79.25	80.00	Rupees Eighty Only
27.00	Providing and laying S&S Centrifugally Cast (Spun)/ Ductile Iron Pipes conforming to IS : 8329					
27.10	150 mm dia Ductile Iron Class K - 7 Pipes	20.00	Mtr	RQC	1581.45	Rupees One Thousand Five Hundred Eighty One And Paise Forty Five Only
27.20	100 mm dia Ductile Iron Class K - 7 Pipes	750.00	Mtr	RQC	1108.15	Rupees One Thousand One Hundred Eight And Paise Fifteen Only
28.00	Providing and fixing of 150mm dia D.I bends including cost of carriage , spun yarn , earthwork etc complete job (to be paid as per actual details/ measurements / supporting document dully verified by AEE concern)	4.00	No	RQC	1500.00	Rupees One Thousand Five Hundred Only
29.00	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/by mechanical means including stacking of pipes within 50 meters lead as per direction of Engineer-in-charge : Above 40 mm nominal bore	800.00	Mtr	110.65	90.00	Rupees Ninety Only
30.00	Earth work in excavation by manual means in trenches for foundations ,drains, pipes, cables etc (not exceeding 1.5mtr in width) and for shafts ,wells ,cesspits, and the like not exceeding 10sqm on plan ,including dressing of sides and ramming of bottoms lift upto 1.5m, including getting out excavated earth and disposal of surplus excavated earth as directed (A) All kinds of soils	942.00	Cum	436.00	330.00	Rupees Three Hundred Thirty Only
31.00	Providing and fixing G.I. pipes complete with G.I. fittings excluding trenching and refilling etc. (external work)					
31.10	80 mm dia G.I pipes	200.00	Mtr	RQC	773.15	Rupees Seven Hundred Seventy Three And Paise Fifteen Only
31.20	50 mm dia G.I pipes	150.00	Mtr	RQC	477.50	Rupees Four Hundred Seventy Seven And Paise Fifty Only
31.30	40 mm dia G.I pipes	800.00	Mtr	RQC	386.05	Rupees Three Hundred Eighty Six And Paise Five Only
31.40	25 mm dia G.I pipes	1000.00	Mtr	RQC	249.00	Rupees Two Hundred Forty Nine Only
31.50	20 mm dia G.I pipes	900.00	Mtr	RQC	182.65	Rupees One Hundred Eighty Two And Paise Sixty Five Only
31.60	15 mm dia G.I pipes	800.00	Mtr	RQC	144.40	Rupees One Hundred Forty Four And Paise Forty Only
32.00	Providing fixing flanged joints with 12mm thick flanges including cost of nuts , bolts, washers, cutting of thread and making good for jointing including testing and commissioning all carriages head load complete. 100 mm dia G.I pipe	140.00	Joint	RQC	1150.00	Rupees One Thousand One Hundred Fifty Only
33.00	Filling available excavated earth (Excl. rock) in trenches, plinth sides of foundation etc. layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering lead upto 50mtr and lift upto 1.5mtr	847.80	Cum	198.70	140.00	Rupees One Hundred Forty Only
34.00	Making connection of G.I distribution branch with G.I main of following size by providing and fixing tees, including cutting and threading the pipe etc complete					
34.10	(a) 25 to 40 mm nominal bore	40.00	No	666.25	500.00	Rupees Five Hundred Only
34.20	(b) Above 40 mm nominal bore	15.00	No	1268.75	800.00	Rupees Eight Hundred



3
...ing of Water Supply Scheme Pachhar Gulshanabad by way of Providing & laying of GI pipes,
...struction of chowkidar quarter, revamping of filtration plant, face lifting of various structures and RCC
...keting to SSF Plant including laying of filter media including installation of 238 No. FHTC's for Pachhar
...ulshanabad including maintenance for a period of three years which includes DLP of 12 months.(JJM).

Carriage of material from source of site upto site of work by mechanical transport including loading unloading stacking at site complete						
35.10	Sand and Bajri avg lead 15km	37.26	Cum	393.02	393.00	Rupees Three Hundred Ninety Three Only
35.20	Cement and steel avg lead 10km	10.50	M.T.	349.39	350.00	Rupees Three Hundred Fifty Only
35.30	Stone solling avg lead 05km	5.17	Cum	211.02	211.00	Rupees Two Hundred Eleven Only

Terms and Conditions:-

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However the non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (03) months and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked

Head Draftsman

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for information
- 2- District Development Commissioner Pulwama for information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Pulwama for information and necessary action.
- 4- File Concerned.

Tech. Officer

Executive Engineer,
USD (PHE) Div. Pulwama