

No. PHEP/4238-41

Dated. 12/11/2020

Mr. Bashir Ahmad Nalk,
Contractor,
S/o. Ghulam Ahmad Nalk,
R/o Zagigam, Pulwama
Regd. No. 24/AA/SE/HYDL/SHOPIAN/2004-05

Sub :- Retrofitting of Water Supply Scheme Sangerwani by way of providing, laying & fitting of GI pipes, including construction of chain link fencing around structures, RC:C jacketing to SSF Plant including installation of 156 No. FHTC's for Sangerwani (JJM).

Ref:- E-NIT S.No. 39/PHEP of 2020-21, job No. (6), Circulated vide this office No. PHEP/3077-90 Dated: 26-09-2020, read with this office No. PHEP/3830 dated.28-10-2020

Advertised Amount of work: ₹ 72,04,000.00

Alloted Amount of work: ₹ 66,55,000.00

Rupees Sixty Six Lakh(s) Fifty Five Thousand Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following negotiated rates as accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No.or Qty.	Unit	RATE	
				Figures	Words
1.00	Providing and laying in position specified grade of reinforced cement concrete excl. the cost of centering, shuttering, finishing, & Reinforcement. All work up to plinth level (1:1.5:3)Raft (1 cement:1 ½ course sand:3 grade stone agg. 20 mm nominal size)	23.45	Cum	6600.00	Rupees Six Thousand Six Hundred Only
2.00	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth & string courses, filets, columns, pillars, piers abutments, post & struts etc up to floor five level excluding cost of centering, shuttering, finishing & reinforcement 1:1.5:3 (1 cement:1½:course sand:3 graded crushed stone 20 mm nominal size)	34.28	Cum	7500.00	Rupees Seven Thousand Five Hundred Only
3.00	12 mm thick cement plaster in 1:4 mix floating coat of neat cement (1 cement,4 fine sand)	558.20	Sqm	189.00	Rupees One Hundred Eighty Nine Only
4.00	Centering and shuttering including strutting, propping etc and removal of form for:-				
4.10	Foundation, footings, bases of columns etc. for mass concrete.	480.00	Sqm	216.00	Rupees Two Hundred Fifteen Only
4.20	Wall (any thickness) including attached plasters, buttresses, plinth and string courses etc	306.00	Sqm	400.00	Rupees Four Hundred Only
4.30	Suspended floors, roofs, landings, balconies and access platform	9.00	Sqm	484.00	Rupees Four Hundred Eighty Four Only
5.00	Reinforcement for RCC works including Straightening cutting, bending, placing in position & binding all complete (Thermo Mechanically treated bars)	2978.65	Kg	85.00	Rupees Eighty Five Only
6.00	Structural steel work welded in built up section, trusses and framed work including cutting, hoisting, fixing in position and applying a primer coat of approved steel primer all complete	3882.97	Kg	90.00	Rupees Ninety Only
7.00	Earth work excavation by manual means in trenches for foundation drains, pipes cables etc (not exceeding 1.5 mtr in width and for shaft wells and the cesspits and the like not exceeding 10sqm on plan) depth up to 1.5 mtr including disposal of excavated soil up to 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil.	2338.40	Cum	288.00	Rupees Two Hundred Eighty Eight Only
8.00	Providing and laying of stone setting hand packed horizontally excluding cost of stones	21.60	Cum	425.00	Rupees Four Hundred Twenty Five Only
9.00	Reinforce cement concrete work in beams, suspended floors, roofs having slope upto 15 degree landings, balconies, shelves, chajias, lintels, bands, plain window sills, stair cases, and spiral cases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:2:4 (1 cement, 2 coarse sand, 4 graded stone agg 20mm nominal size)	1.26	Cum	7500.00	Rupees Seven Thousand Five Hundred Only
10.00	Providing and fixing of G.I. chain link fencing of required width in mesh size 50x50mm including strengthening with 2mm dia wire or nuts, bolts and washers as required complete as per direction of Engineer incharge. Made of G.I. wire 4mm dia	439.20	Sqm	685.00	Rupees Six Hundred Eighty Five Only
11.00	P/F of MS Lid of size 2'-6"x2'x6" angle iron frame with iron sheet including locking arrangements complete job.	1.00	No	3000.00	Rupees Three Thousand Only
12.00	P/F of different dias of sluice valve/ gate valve/ bend/ collars with fittings of standard make (Kirkoskar or VAGE) including all carriages upto site of work complete including tail pieces				
12.10	150mm dia sluice valve	2.00	No	15000.00	Rupees Fifteen Thousand Only
12.20	100mm dia sluice valve	2.00	No	1200.00	Rupees One Thousand Two Hundred Only
13.00	Dismantling of G.I. pipes (external work) including excavation and refilling, trenches, after taking out the pipes, manually by mechanical means including stacking of pipes within 50 mtrs.				
13.10	15mm to 40mm dia bore	490.00	Mtr	63.00	Rupees Sixty Three Only
13.20	Above 40mm dia bore	120.00	Mtr	71.00	Rupees Seventy One Only
14.00	Providing, supplying, fixing of 12mm thick flanged joints to 150mm dia G.I. pipe incld cost of nuts, bolts, washers, cutting of threading incld making good for jointing with welding all carriage to and fro complete				
14.10	100mm dia	20.00	Joint	1000.00	Rupees One Thousand Only
15.00	L/F of G.I. pipes excluding cost of ppe and earth work but including handling complete:-				
15.10	25mm dia G.I. pipe	400.00	Mtr	25.00	Rupees Twenty Five Only

Job :- Retrofitting of Water Supply Scheme Sangerwani by way of providing, laying & fitting of GI pipes, including construction of chain link fencing around structures, RCC jacketing to SSF Plant including installation of 156 No. FHTC's for Sangerwani (JJM).

16.0	P/F of flanged pipe with flanged joints 12mm thick of flanges including cost of nuts, bolts, washers, cutting of threads and making good for jointing including testing and commissioning all carriages complete.	500.00	Mtr	150.00	Rupees One Hundred Fifty Only
16.1	100mm dia flanged pipes				
17.00	Providing, laying and fitting of GI pipes including all carriages head load upto site of work complete.	2500.00	Mtr	401.00	Rupees Four Hundred One Only
17.10	50mm dia	4000.00	Mtr	212.00	Rupees Two Hundred Twelve Only
17.30	25mm dia				
17.40	20mm dia	4000.00	Mtr	153.00	Rupees One Hundred Fifty Three Only
17.50	15mm dia	5000.00	Mtr	105.00	Rupees One Hundred Five Only
18.00	Filling available excavated earth (excl'd Rock) in trenches, plinth sides of the foundation etc layers not exceeding In 20 cm in depth, consolidating each deposited layer by ramming and watering lead up to 50 Mtr and lift up to 1.50 Mtr.	2048.24	Cum	122.00	Rupees One Hundred Twenty Two Only
19.00	Making connections of G I distribution branch with G I mains of following sizes by providing and fixing tee including cutting and threading the pipe etc complete.				
19.10	25mm to 40mm nominal bore	60.00	No	401.00	Rupees Four Hundred One Only
19.20	above 40mm nominal bore	20.00	No	1100.00	Rupees One Thousand One Hundred Only
20.00	P/F of Sign board of 6'x4' of size to be fitted with angle iron frame with cement concrete complete job.	1.00	No	10000.00	Rupees Ten Thousand Only
21.00	18mm thick chemical plaster under layer 12mm thick cement plaster 1:5 finished with 8mm top layer with cement plaster 1:3 mix with admixture of water proofing mixture.	308.00	Sqm	250.00	Rupees Two Hundred Fifty Only
22.00	P/F of MS Bends as required including cost of welding fixing all carriage complete				
22.10	150mm dia MS bend	8.00	No	3500.00	Rupees Three Thousand Five Hundred Only
22.20	100mm dia MS bend	4.00	Cft	2500.00	Rupees Two Thousand Five Hundred Only
23.00	Carriage of different materials from source upto site of work by mechanical transport including cost of loading, unloading and stacking complete.				
23.10	Stone Soling (avg lead 45 Kms)	21.80	Cum	595.00	Rupees Five Hundred Ninety Five Only
23.20	Sand + Bajri (avg lead 45 Kms)	238.52	Cum	506.00	Rupees Five Hundred Six Only
23.30	Cement and steel (avg lead 40 Kms)	52.27	M.T.	416.00	Rupees Four Hundred Sixteen Only
24.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering all work up to plinth level in (1:3:8) Mix (1 cement:3course sand: 8 grade stone agg. 40 mm nominal size)	108.00	Cum	4800.00	Rupees Four Thousand Eight Hundred Only
25.00	Maintenance cost for a period of three years which includes 12 months DLP	1.00	complete job	65000.00	Rupees Sixty Five Thousand Only

Terms and Conditions:-

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However, non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (60) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- Earnest Money of ₹ 145000/- deposited by your vide CDR No. 593506 dated 13-10-2020 has been retained in the divisional office as security deposit.
- 5- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked

Head Draftsman

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for information
- 2- District Development Commissioner Pulwama for information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Pulwama for information and necessary action.
- 4- File Concerned.

Tech. Officer

Executive Engineer,
USD (PHE) Div. Pulwama