

11

Government of Jammu and Kashmir

**OFFICE OF THE EXECUTIVE ENGINEER, JSD (PHE) DIVISION, PULWAMA**

No. PHEP/ 1102-05  
Dated. 02-06-2021

**Mr. Shammad Shafi Dar,**  
Contractor,  
S/o. Ghulam Nabi,  
R/o Rohmu-Pulwama,  
Regd. No. CE/UEED/BEE/338/2003-04

**Sub :-** Retrofitting of Water Supply Scheme Sundergund by way of Providing & laying of GI pipes, including renovation of damaged pump operator quarter, improvements to spring etc including installation of 23 No. FHTC's for Sundergund (JJM).

**Ref:-** E-NIT S.No. 03/PHEP/Fresh of 2021-22, job No. (4), Circulated vide this office No. PHEP/345-57 Dated:- 19-04-2021 followed by Corrigendum No. PHEP/358-71 Dated. 19-04-2021

**Advertised Amount of work: ₹ 14,18,000.00**

**Alloted Amount of work: ₹ 13,62,100.00**

**Rupees Thirteen Lakh(s) Sixty Two Thousand One Hundred Only**

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following rates which are quoted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No. or Qty.	Unit	Estd. Rate	RATE	
					Figures	Words
1.00	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc (not exceeding 1.5mtr in width) and for shafts, wells, cesspits, and the like not exceeding 10sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5m, including getting out excavated earth and disposal of surplus excavated earth as directed All kinds of soils	267.59	Cum	436.00	430.00	Rupees Four Hundred Thirty Only
2.00	Providing and fixing G.I. pipes complete with G.I. fittings excluding trenching and refilling etc. (external work)					
2.10	65mm dia G.I pipes	496.00	Mtr	RQC	630.00	Rupees Six Hundred Thirty Only
2.20	50 mm dia G.I pipes	200.00	Mtr	RQC	485.00	Rupees Four Hundred Eighty Five Only
2.30	40 mm dia G.I pipes	350.00	Mtr	RQC	390.00	Rupees Three Hundred Ninety Only
2.40	25 mm dia G.I pipes	500.00	Mtr	RQC	260.00	Rupees Two Hundred Sixty Only
2.50	20 mm dia G.I pipes	500.00	Mtr	RQC	190.00	Rupees One Hundred Ninety Only
2.60	15 mm dia G.I pipes	744.00	Mtr	RQC	135.00	Rupees One Hundred Thirty Five Only
3.00	Making connection of G.I distribution branch with G.I main of following size by providing and fixing tees, including cutting and threading the pipe etc complete					
3.10	(a) 25 to 40 mm nominal bore	10.00	No	666.25	400.00	Rupees Four Hundred Only
3.20	(b) Above 40 mm nominal bore	3.00	No	1268.75	1000.00	Rupees One Thousand Only
4.00	Filling available excavated earth (Excl. rock) in trenches, plinth sides of foundation etc. layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering lead upto 50mtr and lift upto 1.5mtr	240.83	Cum	198.70	120.00	Rupees One Hundred Twenty Only
5.00	Dismantling old plaster or skirting, raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 meters lead.	72.90	Sqm	35.35	30.00	Rupees Thirty Only
6.00	Providing fixing of poplar wood of standard quality including necessary nails, and carriage complete. (to be paid as per actual details /measurements with supporting vouchers duly verified by AEE concern)	105.00	Cft	RQC	430.00	
7.00	Providing corrugated G.S sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I limpet washers or with G.I filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal / vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required 0.63mm thick with zinc coating not less than 275gram/sqm	85.31	Sqm	951.80	900.00	Rupees Nine Hundred Only
8.00	Providing and fixing plained eaves boarding. 250x32 mm (nominal size)	10.65	Mtr	693.90	600.00	Rupees Six Hundred Only

rofiting of Water Supply Scheme Sundergund by way of Providing & laying of GI pipes, including renovation of damaged pump operator quarter, improvements to spring etc including installation of 23 No. FHTC's for Sundergund (JJM).

	Providing ridges or hips of width 60cm overall width plain G.S. sheets fixed with polymer coated J. or L hooks, bolts and nuts 8mm dia G.I. limpet and bitumen washers complete .with 0.63 mm thick with zinc coating not less than 275 gram/m <sup>2</sup>	10.82	Mtr	691.35	600.00	Rupees Six Hundred Only
10.00	Cement concrete flooring 1:2:4 (1cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry and curing complete, but excluding the cost of nosing of steps etc. complete. 40mm thick with 20 mm nominal size stone aggregate	48.30	Sqm	461.85	416.00	Rupees Four Hundred Sixteen Only
11.00	Providing and laying specified grade of reinforced cement concrete including curing but excluding the cost of centring , shuttering , finishing and reinforcement all works upto plinth level 1:2:4 mix ( 1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size )	11.56	Cum	6344.25	5500.00	Rupees Five Thousand Five Hundred Only
12.00	12mm Cement plaster of mix: 1 : 4 ( 1 cement : 4 fine sand)	112.90	Sqm	260.05	230.00	Rupees Two Hundred Thirty Only
13.00	Steel reinforcement for RCC work including straightening, cutting , bending , placing in position and binding all complete upto plinth level thermo -Mechanically -Treated bars of grade Fe-500D or more	423.00	Kg	79.25	88.00	Rupees Eighty Six Only
14.00	Centring shuttering including strutting , propping etc. and removal of form work for					
14.10	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc	72.63	Sqm	573.85	500.00	Rupees Five Hundred Only
15.00	Structural steel work in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete Welded	120.00	Kg	92.85	90.00	Rupees Ninety Only
16.00	Dismantling of truss with CGI roofing including wooden beams , rafters , purlins , etc of S.R including stacking of serviceable material within 50m lead and carriage of serviceable material upto divisional store Pulwama including engagement of labour for cleaning of S.R including removing of silt and worn out material from bed of S.R and washing of walls with bleaching powder complete . (to be paid as per actual details/measurements )					
16.10	Carpenter 2nd class	2.00	No	666.00	600.00	Rupees Six Hundred Only
16.20	Labour/helper	7.00	No	503.00	500.00	
17.00	Carriage of material from source of site upto site of work by mechanical transport including loading unloading stacking at site complete					
17.10	Sand and Bajri avg lead 10km	16.95	Cum	244.22	240.00	Rupees Two Hundred Forty Only
17.20	Cement and steel avg lead 10km	4.23	M.T.	217.09	200.00	Rupees Two Hundred Only

**Terms and Conditions:-**

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the draw of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for draw of an agreement within a weeks time positively from the date of issuance of allotment. However the non draw of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (30) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked

Head Draftsman

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for information
- 2- District Development Commissioner Pulwama for information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Tahab for information and necessary action.
- 4- File Concerned.

*[Signature]*  
Executive Engineer,  
USD (PHE) Div. Pulwama