

OFFICE OF THE
EXECUTIVE ENGINEER JAL SHAKTI PHE (HYD) DIVISION BANDIPORE

Construction including successful testing and commissioning of 0.030 MGD Slow Sand Filtration Plant and 0.15 Lac gallon RCC Service Reservoir with sluice chamber, construction of PST, chain link fencing, intake/ collection chamber WSS Nagistan Surbal.

1. This office E-NIT No 05-PHE/Hyd/Bpr of 2022-23 issued under endorsement No PHE/Hyd/Bpr/408-18 dated 18/04/2022.
2. Revised District Action Plan of District Bandipore approved by DJJM vide No DDCB/BPR/2022/2056 dated 16/07/2022.
3. Minutes of Meeting held with District Development Commissioner Bandipore (Chairman DDJM) on 04/07/2022 minutes issued vide order No 154-DDCB of 2022 dated 28/07/2022 issued under endorsement No DDCB/JJM/2022-23/2279-82 dated 28/07/2022
4. Amendment in operational guidelines for the implementation of Jal Jeevan Mission issued by NJJM, DDW&S Ministry of Jal Shakti GOI vide F. No W-11016/10/2022-JJM-IV-DDWS Dated 21/06/2022
5. Modus operandi communicated by Chief Engineer Jal Shakti PHE Kashmir vide Circular No CE/PHE/MC/DB/13745-83 Dated 26/07/2022
6. Superintending Engineer Hydraulic Circle Bla/ Bpr H.Q Sopore's Authorization No SE/Hyd/DB/4901-14 dated 29/07/2022
7. Letter of intent issued vide this office No PHE/Hyd/Bpr/JJM/3562-75 dated 30/07/2022
8. Administrative Approval Accorded by Superintending Engineer Hydraulic Circle Bla/ Bpr H.Q Sopore vide order No 60/SE/Hyd/DB/JJM of 2022-2023 dated 24/09/2022 issued endorsement No SE/Hyd/DB/8165-70 dated 24/09/2022.
9. Technical Sanction issued by Chief Engineer Jal Shakti (PHE) Department Kashmir's Order No CE/PHE/DB/743 of 11/2022 Dated 16/11/2022 issued under endorsement No CE/PHE/DB/30160-66 dated 16/11/2022.

ORDER NO. PHE/HYD/BPR/ 59 OF 2022-2023

DATED: 21/12/2022

Major Head of Account: JAL JEEVAN MISSION

Advertised Cost: Rs.57.54 Lacs

Allotted Cost: Rs.58,68,704.00

Time of Completion: 90 Days

(GST No: -01CBGPM5024B1ZF)

For and on behalf of the Lieutenant Governor of Union Territory of Jammu and Kashmir, contract for the work "Construction including successful testing and commissioning of 0.030 MGD Slow Sand Filtration Plant and 0.15 Lac gallon RCC Service Reservoir with sluice chamber, construction of PST, chain link fencing, intake/ collection chamber WSS Nagistan Surbal" is hereby fixed with Sh. Tariq Mohd Mir S/o Gh. Mohd Mir R/o Gulab Bagh Pattermulla Tehsil Lar District Ganderbal bearing Regd No CE/UEED/AAY/Civil/11/2017-18, on the allotted cost of Rs.58,68,704.00 (Rupees Fifty-Eight Lac Sixty Eight Thousand Seven Hundred Four only) on the rates quoted and subsequently negotiated / accepted by bidder on percentage basis as per the Annexure "A" of this allotment order with the standard terms and conditions as laid down in Annexure "B" of this allotment and Detailed E-NIT and SBD.

Technical Officer

Executive Engineer
PHE (Hyd) Division
Bandipore

No: - PHE/Hyd/Bpr/CC/ 0899-55

Dt: - 21/12/2022

Copy to the:

01. Chief Engineer Jal Shakti PHE Department Srinagar for favour of information.
02. District Development Commissioner Bandipore (Chairman DJJM) for favour of information.
03. Additional District Development Commissioner Bandipore (Member DJJM) for favour of information.
04. Superintending Engineer Hydraulic Circle Bla/ Bpr H.Q Sopore (Member Secretary DJJM) for favour of information.
05. Assistant Commissioner Development Bandipore (Member DJJM) for favour of information.
06. Divisional Forest Officer Bandipore (Member DJJM) for favour of information.
07. Chief Planning Officer Bandipore (Member DJJM) for favour of information.
08. Chief Medical Officer Bandipore (Member DJJM) for favour of information.
09. Chief Education Officer Bandipore (Member DJJM) for favour of information.
10. District Social Welfare Officer Bandipore/District Tribal Welfare Officer Bandipore (Member DJJM) for favour of information.
11. District Information Officer Bandipore (Member DJJM) for favour of information.
12. Assistant Executive Engineer PHE Sub-Division Bandipore for information.
13. WAPCOS Bandipore for information.
14. Sh. Tariq Mohd Mir S/o Gh. Mohd Mir R/o Gulab Bagh Pattermulla Tehsil Lar District Ganderbal for information.

OFFICE OF THE

EXECUTIVE ENGINEER PHE (HYD) DIVISION BANDIPORE

Order No. 59 PHE/HYD/BPR/2022-23 Dated 21/12/2022

"Construction including successful testing and commissioning of 0.030 MGD Slow Sand Filtration Plant and 0.15lac Gallon Capacity RCC service reservoir with sluice chamber, construction of PST, chainlink fencing, intake/ collection chamber for WSS Nagistan Surbal"

Adv. Cost :-57.54 lacs
Allotted Cost :- 5868704.00

S. No	Particulars	Qty.	Unit	Rate	Amount
1	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m ² on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge. All kinds of soil	49.860	Cum	539.350	26891.99
1.1	Ordinary or hard rock	21.370	Cum	855.650	18285.24
2	Earth work in bulk excavation by mechanical means (hydraulic excavator) over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m ² on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge. All kinds of soil	322.940	Cum	188.750	60954.93
2.1	Ordinary Rock	138.400	Cum	378.350	52363.64
3	Earth work in excavation by mechanical means (hydraulic excavator) in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed, within a lead of 50 metres:	13.820	Cum	252.050	3483.33
3.1	Ordinary or hard rock	4.610	Cum	470.000	2166.70
4	Extra for every additional lift of 1.5 m or part thereof in excavation/banking excavated or stacked material : All kinds of soil :	15.920	Cum	81.650	1299.87
4.1	Ordinary or hard rock	53.280	Cum	146.450	7802.86
5	Providing and laying of filter media (Gravel & sand) of required grade as per directions of engineer incharge incld all sort of carriage	48.560	Cum	7000.000	339920.00
6	Providing & laying Baramulla stones of approved size and texture incld all sorts of carriage complete	33.200	sqm	1800.000	59760.00
7	Removal of surface boulders by manual means	20.000	Maz	600.000	12000.00
8	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m	238.010	Cum	198.700	47292.59
9	Providing & laying stone soling in horizontal on level.	33.530	Cum	816.400	27373.89
10	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	24.230	Cum	4861.840	117802.38
11	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level: 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	37.810	Cum	7800.760	294946.74
12	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	71.880	Cum	9408.140	676257.10

Head Draftsman

Conts. On 2nd

Executive Engineer

"Construction including successful testing and commissioning of 0.030 MGD Slow Sand Filtration Plant and 0.15lac Gallon Capacity RCC service reservoir with sluice chamber, construction of PST, chainlink fencing, intake/collection chamber for WSS Nagistan Surbal"

	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, plinths, plain window sills, staircases and spiral stair cases upto five levels including curing but excluding the cost of centring, shuttering, and reinforcement with finishing 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	6.600	Cum	9849.350	65005.71
	Reinforced cement concrete work in arches, archribs, domes, vaults shells, folded plate and roofs having slope more than 15° upto floor five level level including curing but excluding the cost of centering, shuttering finishing and reinforcement with: 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	4.430	Cum	10404.520	46092.02
14	Providing & fixing of main hole cover 0.75 x 0.75 of standard quality with angle iron frame incld all necessary fittings complete	2.000	No	3500.000	7000.00
15	Providing & fixing of main hole cover 0.90 x 0.90 of standard quality with angle iron frame incld all necessary fittings complete	3.000	No	4500.000	13500.00
16	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level: Thermo-Mechanically Treated bars of grade Fe-500D or more	15037.30	kg	87.180	1310951.81
17	Structural steel work in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete Welded	650.500	kg	102.140	66442.07
18	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	2354.000	kg	91.030	214284.62
19	Centering and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns etc. for mass concrete.	218.140	sqm	262.300	57218.12
20	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	428.480	sqm	573.850	245883.25
20.1	Suspended floors, roofs, landings, balconies and access platforms	30.540	sqm	635.600	19411.22
20.2	Lintel, beams, plinth beams, girders, bressumers and cantilevers	15.440	sqm	502.850	7764.00
20.3	Arches, domes, vaults upto 6 m span	35.980	sqm	2086.800	75083.06
20.4	Extra for shuttering in circular work	114.940	sqm	114.760	13190.51
20.5	Extra for shuttering in circular work: foundation	8.990	sqm	52.460	471.62
20.6	Edges of slabs and breaks in floors and walls : Under 20 cm wide	15.000	Rm	242.300	3634.50
20.7	Columns, pillars, piers, abutments, posts and struts.	8.640	sqm	680.150	5876.50
20.8	Providing and fixing of 50mm dia G.I half bend of standard quality to be fixed in dome for aeration purpose	55.000	No	250.000	13750.00
21	Providing and incorporating PGI sheets strips 0.8mm thick at construction joints incld. All carriages complete job	4.640	Sqm	400.000	1856.00
22	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with: 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	45.000	Cum	5437.740	244698.30
23	12mm Cement plaster finished with a floating coat of neat cement of mix:1:3 (1 cement 3 sand)	117.870	sqm	343.750	40517.81
24	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia 4 mm	180.000	sqm	733.500	132030.00
25	12mm Cement plaster of mix: 1 : 4 (1 cement : 4 fine sand)	271.280	sqm	260.050	70546.36
26	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level: 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.970	Cum	6978.680	6769.32

Executive Engineer

Conts. On 3rd

Head Draftsman

"Construction including successful testing and commissioning of 0.030 MGD Slow Sand Filtration Plant and 0.15lac Gallon Capacity RCC service reservoir with sluice chamber, construction of PST, chainlink fencing, intake/ collection chamber for WSS Nagistan Surbal "

29	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchors blocks, plain window sills, fillets etc upto floor V level, including curing but excluding the cost of centring, shuttering and finishing with 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	0.000	Cum	7269.190	0.00
30	Applying priming coat:- With ready mixed red oxide Zinc Chromate primer of approved brand and manufacture on steel work (second coat)	189.800	sqm	28.900	5485.22
30	Painting with aluminum paint of approved brand and manufacture to give an even shade. Two or more coats on new work	189.800	sqm	119.400	22662.12
31	Providing and fixing of CI sluice valve with cap including all accessories like nuts, bolts rubber insertion etc and tail pieces of Kirloskar make including successful testing and commissioning. 100mm dia	5.000	No	45000.000	225000.00
32	Providing and mixing of water proofing material or equivalent for RCC work	515.180	kg	50.000	25759.00
33	Carraige of materials from source to road site of work including loading, unloading and stacking:- Stone / stone soling for an av lead of 18 km	33.530	Cum	444.682	14910.19
33.1	40mm aggregate for an av lead of 50 km	21.790	Cum	761.254	16587.72
33.2	20mm aggregate for an av lead of 50 km	236.430	Cum	700.373	165589.19
33.3	sand for an av lead of 50 km	147.920	Cum	700.373	103599.17
33.4	cement for an av lead of 12 km	127.620	MT	271.251	34617.05
33.5	steel for an av lead of 12 km	17.790	MT	271.251	4825.56
34	Carraige of materials from road site to site of work by manual labour including loading, unloading and stacking for an av lead of 1300 Mtrs. Stone / stone soling	33.530	Cum	1591.002	53346.30
34.1	40mm aggregate	21.790	Cum	1462.018	31857.37
34.2	20mm aggregate	236.430	Cum	1352.423	319753.37
34.3	sand	147.920	Cum	1352.423	200050.41
34.4	Cement	127.620	MT	715.599	91324.74
34.5	Steel	17.790	MT	1219.046	21686.83
35	Providing, erecting and fixing of sign board 2'6"x4' made up of angle iron frame work 50x50x6mm with 1mm thick M.S sheet including priming, painting and proper lettering and embedding with 1:3:6 cement concrete complete job	1.000	job	6000.000	6000.00
				TOTAL	5753632.30
				(Allotted rate @ 2% above on all items of work)	115072.64
				Grand Total Rs.5868704.00	
(Rupees Fifty Eight Lac Sixty Eight Thousand Seven Hundred Four ony)					


Head Draftsman


Executive Engineer
PHE (Hyd) Division
Bandipora

ANNEXURE "B"

including successful testing and commissioning of 0.030 MGD Slow Sand Filtration Plant and 0.15 Lac RCC Service Reservoir with sluice chamber, construction of PST, chain link fencing, intake/ collection
WSS Nagistan Surbal

TERMS AND CONDITIONS

01. The work shall be executed strictly as per approved design / drawing, specifications and JJM Guidelines. Any deviation or change in proposal/location is subject to the prior approval from the competent authority.
02. The rates allotted are inclusive of all taxes applicable as per norms amended by competent authorities from time to time. Labour cess and royalties shall have to be borne by the executing agency/contractor.
03. The execution of work shall be subject to check by the third party monitoring agency (TPIQM) appointed by the Department
04. No liability should be created on this account.
05. This letter of allotment will constitute a legal contract between the government and the contractor and the conditions as laid down in the master NIT for 2022-2023 and PWD Form No. 25 (Double) will also hold good even before the drawl of an agreement between the Government and the contractor.
06. That the date of start of the work shall be reckoned within two days from the date of issue of Letter of Intent issued vide this office No PHE/Hyd/Bpr/JJM/3562-75 dated 30/07/2022 and in case of delay on the part of the contractor in execution of the work within stipulated time of completion a penalty upto 10% of contract value shall be imposed upon him.
07. The total amount of work should not exceed **Rs.58,68,704.00** in any case.
08. The bidder shall furnish a performance security equivalent to 03% of the value of the contract within one week of the issuance of allotment order in the shape of CDR/FDR/Bank Guarantee, valid for a period of 24 Months, which shall be released after successful fulfilment of the laid down conditions in SDB/E-NIT.
09. In case the contractor fails to execute the work, the work shall be put to fresh tenders on the risk and cost of the contractor & the excess cost if involved shall be recovered from the contractor and strict action as warranted under contractual obligation shall be taken against the defaulter
10. The time of completion of the work is reckoned **90 Days (Ninety Days)** as per the condition laid down in the e-NIT.
11. The firm shall be bound for satisfactory performance of works for 18 months after the successful commissioning of subject work. If during warranty period any malfunctioning/ defects arise, the firm shall have to rectify the same within a period of ten days of receipt of intimation. In case of any failure on the part of the firm to remove the defect, the department may get the defects removed/ repaired by any other agency and cost thereof shall be recovered from the firm and shall be recommended for further punitive action as governed under the relevant clause of the contract including blacklisting
12. After testing and commissioning of work, the bidder will have to make a trial run of the work for a period of 03 months during which the bidder will have to operate and maintain the executed work to the full satisfaction of the Department
13. The defects Liability period shall be for a period of 12 Months which shall commence after the successful completion of Trial run. The bidder shall be responsible to make good & remedy at his own expense any defect in works which is noticed during the DLP. In case any defect remains unattended by the firm at the completion of DLP, the department may extend the DLP for such time as deemed fit for getting the defect rectified subject to a maximum ceiling of 6 Months
14. In the event of allottee failing, declining, neglecting or delaying the supplies / works or in the event of any damage occurring or being caused by the allottee or in the event of any default or failure by the allottee in complying with any of the terms and conditions of the contract, the Department shall with or without

to any other remedies available to it under any law for the time being enforce in the UT:

- a) Terminate the contract after 15 days' notice and/or
- b). Recover the amount of loss caused by damage, failure or default, as may be determined by the department.
- c). Recover the extra cost, if any, involved in allotting contract to other party. and/or
- d). Impose Liquidated damages on account of delay beyond the schedule completion period to the tune of 0.5% of the delayed portion of contract every week but not exceeding 10% value of the contract. and/or


15. Any failure or commission to carry out the provision of the contract shall not give rise to any claim by the department or bidder one against the other if such failure of commission arises from the 'ACT OF GOD' which shall include all natural calamities such as fires, floods, earthquake, hurricane, strikes, riots, embargoes or from any political or other reasons beyond the control of the parties including war, or a state of insurgency
16. In the event of the death or insanity or insolvency or imprisonment of the bidder or where the bidder being a partnership or firm becomes dissolved or being corporation goes into liquidation, voluntary or otherwise, the contract may, in the option of the Engineer-in-charge, be terminated by notice in writing posted at the site of the works
17. The bidder should ensure the safety of the water supply lines, sewer lines, telephone cables, power cables, storm water drains etc., pipe laying alignment and, if any damage occurs during execution it should be attended immediately at the cost of the bidder. Failing to attend immediately, the same will be got done by the Department at the risk and cost of the allottee
18. All risks of loss or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the Contract are the responsibility of the Bidder
19. **The bidder shall not sublet the whole or part of the work.** The bidder shall not assign the work or any part thereof or any benefit or any interest thereon or any claim arising of the contract, without prior written consent of the allotting authority
20. From the commencement of the work to the completion thereof the same shall be under the bidder's charge. The bidder shall be held responsible for and make good any loss or injuries by fire or other causes / theft and shall hold the Government harmless for any claims for injuries to persons or damage to property happening from any neglect, default, want of proper care and misconduct on the part of the bidder, or any of his employees, during the execution of work. The bidder shall be responsible for the compensation if any, to labour under the existing labour laws of the country
21. The bidder shall make his own arrangements for the engagement of all types of the labour, required for the execution of the job. No workman below the age of 18 years shall be employed on the works. Also the bidder shall comply with the provisions of all labour laws and the rules framed there under
22. The bidder shall at his own cost make arrangements for proper storage especially towards Rain and Snow damages of the equipment/ materials at sites till its erection/completion. For the purpose the bidder shall, with the approval of Engineer in charge construct temporary storage accommodation for equipment/ material at site for which land shall be provided by the department near the site of work
23. The bidder shall in connection with the work provide and maintain at his own cost all lights, guards, fencing and watching, when and where necessary or required by the

Department for the protection of the work or safety and convenience of the Public etc
The bidder/firm shall make his own arrangement, at his own cost, for all lines,
individual power points, etc. to the machinery and plant required by him for the
erection, testing and commissioning of the equipment ordered on him. The bidder
shall pay for all electrical energy consumed by him for this purpose at the
prevalent electricity tariff in J&K State. Such charges shall be paid by the
bidder/firm directly to the Power Corporation and the bidder's final bill shall be
settled only after he gets a no outstanding certificate from the concerned Electric
Division.

The Division shall not be responsible, and the bidder shall have no claim
whatsoever for any interruption in power supply or voltage fluctuation or total cut
off at the site. The bidder/firm must provide an alternative source of power, at
his own cost, at the site for completion of the work. The bidder shall make his own
arrangements for water to be used for the execution/Hydro-testing/ water
tightness Test/ Curing, labour colony, Site Office etc

25. Forfeit the performance security and blacklist the firm
26. Geo Tagged Photographic evidences of the work; pre-execution, during execution
and post execution should be maintained by the agency on his own expenses
27. The executing agency/contractor must execute the work as per the
requirements/specifications detailed in the relevant/applicable IS codes
28. The tests for concrete and allied materials shall have to be carried out at reputed
institute as per directions of Engineer in-charge and the charges for the same shall
have to be borne by the executing agency/contractor
29. All Environmental norms, labour laws and all other guidelines issued by competent
authorities shall be followed in letter and spirit
30. The payment of work shall be made as and when the funds are available to the
tune within available provision of DPR by the competent authority under the proper
scheme/ account head.
31. As soon as letter of award is communicated to the firm, the contract shall be
complete and binding upon them, the bidder/firm shall also be required to execute
an agreement with the competent authority within seven days from the date of
issue of letter of award. Failure to execute such an agreement in time shall not
however, prevent this contract from being enforced against the firm and the date
of delivery of the material/completion of works shall be reckoned from the date of
issue of the letter of award in favour of successful firm.
32. Nothing shall be paid to the contractor on account of dewatering/ diversion even if
involved at site of work.
33. If the Contractor have not start the work within 15 days of issuance of this letter of
intent, the contract shall be cancelled at the risk and cost of contactor without
serving any notice. The Assistant Ex. Engineer concerned shall intimate this office
regarding the same.
34. All other terms and conditions as laid down in Master E-NIT, Tender documents and
PWD form 25 shall remain in force.


Technical Officer


Executive Engineer
PHE (Hyd) Division
Bandipore