

OFFICE OF THE EXECUTIVE ENGINEER, JSD (PHE) DIVISION, PULWAMA

No. PHEP/ 4234-37
Dated. 12-11-2020

Mr. Bashir Ahmad Naik,
Contractor,
S/o. Ghulam Ahmad Naik,
R/o Zagigam, Pulwama
Regd. No. 24/AA/SE/HYDL/SHOPIAN/2004-05

Sub :- Retrofitting of Water Supply Scheme Abhama by way of providing, laying n fitting of GI pipes, including revamping of filtration plant, construction of intake channel/ intake chamber at head site, improvements to existing Impounding Reservoir by way of raising of height and face lifting of the structures including installation of 85 No. FHTCs for Abhama (JJM).

Ref:- E-NIT S.No. 39/PHEP of 2020-21, job No. (1), Circulaied vide this office No. PHEP/3077-90
Dated: 26-09-2020.

.....
Advertised Amount of work: ₹ 68,07,000.00

Alloted Amount of work: ₹ 77,15,000.00

Rupees Seventy Seven Lakh(s) Fifteen Thousand Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following negotiated rates as accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No. or Qty.	Unit	RATE	
				Figures	Words
1.00	Earth work excavation by manual means in trenches for foundation drains, pipes cables etc (not exceeding 1.5 mtr in width and for shaft wells and the cesspits and the like not exceeding 10sqm on plan) depth up to 1.5 mtr including disposal of excavated soil up to 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil.	1709.97	Cum	320.00	Rupees Three Hundred Twenty Only
2.00	Dismantling of G.I. pipes (external work) including excavation and refilling, trenches, after taking out the pipes, manually by mechanical means including stacking of pipes within 50 mtrs.				
2.10	15mm to 40mm dia bore	310.00	Mtr	71.00	Rupees Seventy One Only
2.20	Above 40mm dia bore	270.00	Mtr	80.00	Rupees Eighty Only
3.00	L/F of G.I. pipes excluding cost of ppe and earth work but including handling complete:-				
3.10	65mm dia G.I. pipe	270.00	Mtr	65.00	Rupees Sixty Five Only
3.20	25mm dia G.I. pipe	310.00	Mtr	26.00	Rupees Twenty Six Only
4.00	P/F of flanged pipe with flanged joints 12mm thck of flanges including cost of nuts, bolts, washers, cutting of threads and making good for jointing including testing and commissioning all carriages complete.				
4.10	65mm dia GI pipe with flanges	1000.00	Mtr	650.00	Rupees Six Hundred Fifty Only
5.00	Providing, laying and fitting of GI pipes including all carriages head load upto site of work complete.				
5.10	50mm dia	1500.00	Mtr	460.00	Rupees Four Hundred Sixty Only
5.20	40mm dia	1200.00	Mtr	350.00	Rupees Three Hundred Fifty Only
5.30	25mm dia	1200.00	Mtr	230.00	Rupees Two Hundred Thirty Only
5.40	20mm dia	800.00	Mtr	165.00	Rupees One Hundred Sixty Five Only
5.50	15mm dia	5000.00	Mtr	135.00	Rupees One Hundred Thirty Five Only
6.00	Making connections of G.I. distribution branch with G.I. mains of following sizes by providing and fixing tee including cutting and threading the pipe etc complete.				
6.10	25mm to 40mm nominal bore	80.00	No	500.00	Rupees Five Hundred Only
6.20	above 40mm nominal bore	20.00	No	1100.00	Rupees One Thousand One Hundred Only
7.00	Filling available excavated earth (excld Rock) in trenches, plinth sides of the foundation etc layers not exceeding in 20 cm in depth, consolidating each deposited layer by ramming and watering lead up to 50 Mtr and lift up to 1.50 Mtr.	1417.77	Cum	150.00	Rupees One Hundred Fifty Only
8.00	Cleaning of filter media mixed with silt including disposal outside the premises all leads and lifts complete job.	8928.00	Cft	3.50	Rupees Three And Paise Fifty Only
9.00	Cleaning and washing of filter media after removing from plant complete job.	2995.10	Cft	3.50	Rupees Three And Paise Fifty Only
10.00	Providing and laying of filter media from Ganderbal including all carriages lead lifts and placing in layers into plant complete job.	3660.90	Cft	200.00	Rupees Two Hundred Only
11.00	Re-laying of filter media into filtration plant in layers after washing and cleaning complete job.	2995.10	Cft	3.50	Rupees Three And Paise Fifty Only
12.00	Providing and laying in position specified grade of reinforced cement concrete excl. the cost of centering, shuttering, finishing, & Reinforcement. All work up to plinth level (1:1.5:3)Raft (1 cement:1 1/2 course sand:3 grade stone agg. 20 mm nominal size)	26.02	Cum	7000.00	Rupees Seven Thousand Only

Retrofitting of Water Supply Scheme Abhama by way of providing, laying & fitting of GI pipes, including revamping of filtration plant, construction of intake channel/ intake chamber at head site, improvements to existing Impounding Reservoir by way of raising of height and face lifting of structures including installation of 85 No. FHTCs for Abhama (JJM).

13.00	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth & string courses, fillets, columns, pillars, piers abutments, post & struts etc up to floor five level excluding cost of centering, shuttering, finishing & reinforcement 1:1.5:3 (1 cement:1½ coarse sand:3 graded crushed stone 20 mm nominal size)	64.56	Cum	8100.00	Rupees Eight Thousand One Hundred Only
14.00	12 mm thick cement plaster in 1:4 mix floating coat of neat cement (1 cement, 4 fine sand)	664.37	Sqm	210.00	Rupees Two Hundred Ten Only
15.00	Reinforce cement concrete work in beams, suspended floors, roofs having slope upto 15 degree landings, balconies, shelves, chajjas, lintels, bands, plain window sills, stair cases, and spiral cases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:2:4 (1 cement, 2 coarse sand, 4 graded stone agg 20mm nominal size)	8.91	Cum	7200.00	Rupees Seven Thousand Two Hundred Only
16.00	Extra for providing and mixing of water proofing material in cement conc work in doses by weight of cement as per manufacturer specification	372.00	Kg	59.00	Rupees Fifty Nine Only
17.00	Reinforcement for RCC works including Straightening cutting, bending, placing in position & binding all complete (Thermo Mechanically treated bars)	6848.00	Kg	85.00	Rupees Eighty Five Only
18.00	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing & staircase railing and similar work including applying a priming coat of approved steel primer (40mm dia GI pipes nominal bore class (b))	673.00	Kg	115.00	Rupees One Hundred Fifteen Only
19.00	Structural steel work welded in built up sections/ framed work including cutting hoisting fixing in position and applying priming coat of approved steel primer using structural steel etc as required in gratings, frames, guard bar ladders, railing, brackets gates and similar work	515.00	Kg	95.00	Rupees Ninety Five Only
20.00	Centering and shuttering including strutting, propping etc and removal of form for:-				
20.10	Foundation, footings, bases of columns etc. for mass concrete.	12.00	Sqm	250.00	Rupees Two Hundred Fifty Only
20.20	Wall (any thickness) including attached plasters, buttresses, plinth and string courses etc	759.16	Sqm	400.00	Rupees Four Hundred Only
20.30	Suspended floors, roofs, landings, balconies and access platform	92.10	Sqm	450.00	Rupees Four Hundred Fifty Only
20.40	Edges of slab and breaks in floors and walls under 20cms wide	24.00	Sqm	200.00	Rupees Two Hundred Only
21.00	P/F of different dias of sluice valve/ gate valve/ bend/ collars with fittings of standard make (Kirtoskar or VAGE) including all carriages upto site of work complete including tail pieces				
21.10	150mm dia sluice valve	5.00	No	16000.00	Rupees Sixteen Thousand Only
22.00	Providing and laying of stone soling hand packed horizontally excluding cost of stones	29.20	Cum	441.00	Rupees Four Hundred Forty One Only
23.00	Providing and laying in position cement concrete of specified grade excl. cost of centering & shuttering, all work up to plinth level 1:4:8 (1 cement:4 fine sand:8 grade stone agg.)	6.57	Cum	4000.00	Rupees Four Thousand Only
24.00	Structural steel work welded in built up section, trusses and framed work including cutting, hoisting, fixing in position and applying a primer coat of approved steel primer all complete	60.00	Kg	109.00	Rupees One Hundred Nine Only
25.00	Providing and laying in position cement concrete of specified grade excl. cost of centering & shuttering, all work up to plinth level 1:2:4 (1 cement:2 coarse sand:4 grade stone agg. 20 mm nominal size crushed)	85.28	Cum	6000.00	Rupees Six Thousand Only
26.00	18mm thick chemical plaster under layer 12mm thick cement plaster 1:5 finished with 6mm top layer with cement plaster 1:3 mix with admixture of water proofing mixture.	242.46	Sqm	290.00	Rupees Two Hundred Ninety Only
27.00	Applying priming coat with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	142.74	Sqm	37.53	Rupees Thirty Seven And Paise Fifty Three Only
28.00	Painting with ready mixed synthetic enamel paint of approved brand and manufacture in all shades to give an even shade old steel work (one or more coats)	142.74	Sqm	61.56	Rupees Sixty One And Paise Fifty Six Only
29.00	finishing walls with water proofing cement paint of required shade on new works (two or more coats) applied @ 3.84 Kg/10Sqm	439.97	Sqm	72.00	Rupees Seventy Two Only
30.00	P/F of Sign board of 8'x4' of size to be fitted with angle iron frame with cement concrete complete job.	1.00	No	10000.00	Rupees Ten Thousand Only
31.00	Providing and laying in position specified grade of reinforces cement concrete excluding the cost of centering shuttering finishing and reinforcement. All work upto plinth level in 1:2:4 mx (1 cement : 2 coarse sand:3 graded stone) 20mm nominal size.	9.60	Cum	6000.00	Rupees Six Thousand Only
32.00	Carriage of different materials from source upto site of work by mechanical transport including cost of loading, unloading and stacking complete.				
32.10	Stone soling (avg 5 Kms)	17.56	Cum	201.00	Rupees Two Hundred One Only
32.20	Sand + Bajri (avg lead 45 Kms)	129.01	Cum	620.00	Rupees Five Hundred Twenty Only
32.30	Cement + steel (avg lead 40 Kms)	167.35	M.T.	425.00	Rupees Four Hundred Twenty Five Only
33.00	Carriage of different materials from source upto site of work by mechanical transport including cost of loading, unloading and stacking complete.				
33.10	Cement + Steel (avg lead 45 Kms)	23.47	M.T.	450.00	Rupees Four Hundred Fifty Only
33.20	Sand (avg lead 40 Kms)	27.01	Cum	450.00	Rupees Four Hundred Fifty Only
33.30	Bajri (avg lead 30 Kms)	45.52	Cum	420.00	Rupees Four Hundred Twenty Only
34.00	Extra carriage of material by head load (avg lead 2000 mtrs)				
34.10	Cement	19.95	M.T.	470.00	Rupees Four Hundred Seventy Only
34.20	Steel	3.52	M.T.	1020.00	Rupees One Thousand Twenty Only
34.30	Sand + Bajri	72.53	Cum	1150.00	Rupees One Thousand One Hundred Fifty Only

Sub :- *Retrofitting of Water Supply Scheme Abhama by way of providing, laying n fitting of GI pipes, including revamping of filtration plant, construction of intake channel/ intake chamber at head site, improvements to existing Impounding Reservoir by way of raising of height and face lifting of the structures including installation of 85 No. FHTCs for Abhama (JJM).*

34.40	Stone Solling	17.56	Cum	1350.00	Rupees One Thousand Three Hundred Fifty Only
35.00	Maintenance cost for a period of two years	1.00	complete job	80000.00	Rupees Eighty Thousand Only

Terms and Conditions:-

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However, non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (60) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- Earnest Money of ₹ 136500/- deposited by your vide CDR No. 593501 dated. 13-10-2020 has been retained in the divisional office as security deposit.
- 5- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked

Head Draftsman

[Signature]
Tech. Officer

[Signature]
Executive Engineer
USD (PHE) Div. Pulwama

Copy to the:-

- 1- *Superintending Engineer, Hydraulic Circle, Shopian, for information*
- 2- *District Development Commissioner Pulwama for information.*
- 3- *Assistant Executive Engineer, PHE Sub-Div., Pulwama for information and necessary action.*
- 4- *File Concerned.*