

Jammu & Kashmir

OFFICE OF THE EXECUTIVE ENGINEER PHE DIVISION SOPORE

M/s Rather Construction Co.,

Prop.: Mohd Amin Rather,

S/o: Ali Mohammad Rather,

R/o: Arampora Ganderbal

Reg. No.: SE/HYD/BUD/2003-04/253/AAY/Civil & Sanitary

E-mail ID: maminrather@gmail.com

Phone No: 7889818961

Position of AAA : Accorded

Position of T.S : Accorded

No:- 2738-44

Dated:- 10-06-2023

Advt. Cost: Rs.56.38 lacs

Allott. Cost: Rs.58.07 lacs

Time of Complt.: 60 days

Subject: - Construction of Sump Cum Pump House stage 1st and Clear Water Sump Cum Pump House stage 2nd for W.S.Scheme Tarzoo under JJM (Tender Id: 2023_PHE_209667_4).

Ref: 1. Your on-line tender received in response to this office Fresh E-NIT No: 06/JJM/JSDS of 04/2023 dated: 12-04-2023 S.No: 04
2. Superintending Engineer Hyd. Circle Sopore's Authorization issued vide No: SE/Hyd./DB/2074-76 dated: 30-05-2023

For and on behalf of Lt. Governor of Jammu and Kashmir Union Territory, contract for the work mentioned above is here by fixed with you on the following negotiated rates, terms and conditions.

A Rates:

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
1	Earth work in excavation by mechanical means (hydraulic excavator) in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed, within a lead of 50 metres: All kinds of soil :	Cum	374.04	252.05	94276.78
2	Supply, Fabrication, Fixing in position Mild Steel Edge Cutter with mild steel anchorage including welding and making position for fixing of reinforcement of wall as per approved drawings and technical specifications and as per instructions of Site Engineer Incharge incl. all carriages & cots complete.	Kg	637.20	175.00	111510.00
3	Sinking of well through all types of sink complete as per drawings and all technical specification having inner dia of 5.50m by way of making of platform overhead wall, with loading, unloading of sand filled EC bags for required number of castings and engagement of skilled labour with sinking depth as per site conditions and removal of platform as per directions of site Engineer Incharge	Rm	7.00	21000.00	147000.00

Head Draftsman

Technical Officer

Exen

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
4	Pumping out water caused by springs, tidal or river seepage, broken water mains or drains and the like	KL	1514.49	155.50	235503.20
5	Providing and filling of E.C Bags with sand/earth including cost of E.C Bags, Eath, sand all carriages costs etc and including laying in position to acts as copper dam/ spur/ Diversion, as per site requirments and directions of site Engineer	Bag	6047.00	25.00	151175.00
6	Providing and laying of dry Stone soling in horizontal on level.	Cum	16.77	816.40	13691.03
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.1:4:8 (1 cement : 4 coarse sand : 8 graded stone agg. 40 mm nominal size Crushed	Cum	9.51	4861.84	46236.10
8	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level in 1:1.5:3 Mix.(1 cement: 1.5 coarse sand : 3 graded stone agg.) 20mm nominal size	Cum	29.44	7800.76	229654.37
9	Reinforced cement concrete work in chimneys, shafts upto floor five level including curing complete but excluding the cost of centering, shuttering, finishing and reinforcement with: 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	40.70	9600.64	390746.05
10	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	16.20	9408.14	152411.87
11	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°,landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto five level including curing but excluding the cost of centring, shuttering,finishing and reinforcement with:1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	35.39	9849.30	348566.73
12	Centering and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns etc. for mass concrete.	Sqm	25.15	262.30	6596.85
13	Centering and shuttering including strutting, propping etc. and removal of form for: Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	Sqm	473.53	573.85	271735.19
14	Centering and shuttering including strutting, propping etc. and removal of form for: Lintel, beams, plinth beams, girders, bressummers and cantilevers.	Sqm	92.66	502.85	46594.08
15	Centering and shuttering including strutting, propping etc. and removal of form for: Columns, pillars, piers, abutments, posts and struts.	Sqm	27.60	680.15	18772.14

Head Draftsman

Technical Officer

Exen

Sump Cum Pump House stage 1st and Clear Water Sump Cum Pump House stage 2nd for W.S.Scheme Tarzoo under JJM

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
16	Centering and shuttering including strutting, propping etc. and removal of form for: Suspended floors, roofs, landings, balconies and access platforms.	Sqm	153.13	635.60	97329.43
17	Centering and shuttering including strutting, propping etc. and removal of form for: Edges of slab	Sqm	119.16	242.30	28872.47
18	Extra for shuttering in circular work (20% of respective centering and Shuttering items). Foundations, footings, bases of columns etc. for mass concrete.	Sqm	13.41	52.46	703.49
19	Extra for shuttering in circular work (20% of respective centering and Shuttering items). Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	Sqm	389.62	114.80	44728.38
20	Extra for shuttering in circular work (20% of respective centering and Shuttering items). Lintel, beams, plinth beams, girders, bressummers and cantilevers	Sqm	43.26	100.60	4351.96
21	Extra for shuttering in circular work (20% of respective centering and Shuttering items). Columns, pillars, piers, abutments, posts and struts.	Sqm	7.80	136.00	1060.80
22	Extra for shuttering in circular work (20% of respective centering and Shuttering items). Suspended floors, roofs, landings, balconies and access platforms	Sqm	79.63	127.10	10120.97
23	Extra for shuttering in circular work (20% of respective centering and Shuttering items). Edges of slab	Sqm	41.76	48.46	2023.69
24	Extra for shuttering in circular work (20% of respective centering and Shuttering items). Edges of slab	Sqm	505.00	178.50	90142.50
25	Brick work in FPS brick of class designation 75 in foundation and plinth in cement mortar 1:4 mix	Cum	29.87	6183.75	184708.61
26	Extra for brick work with common burnt clay bricks/cement concrete bricks in super structure above plinth level upto floor five level	Cum	34.14	1323.65	45189.41
27	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Hot rolled deformed bars	Kg	14600.53	87.17	1272728.20
28	15mm Cement plaster on the rough side of single or half brick wall of mix: 1 : 4 (1 cement : 4 fine sand)	Sqm	320.83	300.45	96393.37
29	12mm Cement plaster finished with a floating coat of neat cement of mix: 1 : 3 (1 cement : 3 fine sand)	Sqm	284.52	343.75	97803.75
30	12mm Cement plaster finished with a floating coat of neat cement of mix: 1 : 4 (1 cement : 4 fine sand)	Sqm	258.96	260.05	67342.55
31	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia and length (hold fast lugs or with dash fasteners shall be paid for separately): second class kail wood	Cum	0.47	92065.35	43270.71

Head Draftsman

Technical Officer


Exen



S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
32	Providing and fixing glazed shutters for doors, windows and clerestory windows using 10kg/sqm (4mm thick) float glass panes including ISI marked M.S pressed butt hinges bright finished of required size with necessary screws. Second class kail wood 30mm	Sqm	9.20	3081.90	28353.48
33	Supplying and fixing rolling shutters of approved make, made of required size M.S laths interlocked together through their entire length and jointed together at the end by end locks mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete including the cost of providing and fixing necessary 27.50cm long wire springs manufacture from high tensile steel wire of adequate strength confirming to IS 4454 part 1 and M.S top cover of required thickness for rolling shutters. 80x1.25mm M.S laths with 1.25mm thick top cover	Sqm	7.62	3238.20	24675.08
34	Providing and fixing ball bearing for rolling shutters	Each	4.00	483.10	1932.40
35	Applying priming coat: With ready mixed pink or grey primer of approved brand and manufacture on wood work (hard and soft wood)	Sqm	44.30	59.50	2635.85
36	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work	Sqm	44.21	121.95	5391.41
37	Providing and applying white cement based putty of specified thickness, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. 2 mm thick	Sqm	234.09	172.40	40357.12
38	Distemping with 1st quality acrylic distemper (ready mixed)having VOC content less than 50 gms/litre, two or more coats on new work of approved manufacturer, of required shade and colour complete as per manufacturer's specifications	Sqm	234.09	82.60	19335.83
39	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface.	Sqm	185.79	59.40	11035.93
40	Finishing walls with water proofing cement paint of required shade on New work (two or more coats applied @ 3.84 kg/10sqm)	Sqm	185.79	91.80	17055.52


Head Draftsman


Technical Officer


Exen

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs
41	Providing and fixing aluminum tower bolts ISI marked anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete : 100x10 mm	Each	64.00	57.40	3673.60
42	Providing and fixing aluminum handles ISI marked anodized (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour and shade with necessary screws etc. complete.	Each	32.00	52.30	1673.60
43	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Hard drawn steel wire fabric	Kg	4496.00	102.14	459221.44
44	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel primer. M.S. tube	Kg	74.80	172.90	12932.92
45	Providing corrugated G. S. sheet roofing including vertical/curved surface fixed with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch inhorizontal/vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.50 mm thick with zinc coating not less than 275 gram/m ²	Sqm	117.80	830.25	97803.45
46	Providing ridges or hips of width 60cm overall width plain G.S. sheets fixed with polymer coated J. or L hooks, bolts and nuts 8mm dia G.I. limpet and bitumen washers complete. 0.50 mm thick with zinc coating not less than 275 gram/m ²	Mtr	69.00	626.70	43242.30
47	Providing and fixing at site Eaves boarding of 200mm wide coloured ncluding cost of holders, angle supports complete job	Mtr	54.31	500.00	27155.00
48	Providing and fixing of 0.5mm Color GS Sheet Soffit boarding incl supports etc complete job	Sqm	52.89	900.00	47601.00
49	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	Cum	373.88	198.70	74289.96

Head Draftsman


Technical Officer


Exen

S. No	Particulars of Items	Unit	Quantity	Allotted Rate	Amount in Rs.
50	Providing 40x5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embeddings in cement concrete block 30x10x15 cm 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	Each	38.00	163.00	6194.00
51	Close timbering in trenches including strutting, shoring and packing cavities (wherever required) complete. (Measurements to be taken of the face area timbered). Depth exceeding 3 m but not exceeding 4.50 m	Sqm	165.07	271.45	44808.25
52	Providing and mixing water proofing material in cement plaster work in proportion recommended by the manufacturers:	Kg	277.00	61.50	17035.50
53	Providing and fixing wire gauze shutters of 30mm thickness butt hinges bright finished off required size with necessary screws	Sqm	9.23	2966.40	27379.87
54	Extra for every additional lift of 1.5 mtr. or part thereof in all kinds of soil	Cum	97.67	81.65	7974.76
55	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	15.46	7346.48	113576.58
56	Carriage of material by mechanical transport from source to actual site of work for: Cement & Steel Avg lead 5 Km	M.T	94.40	183.35	17308.24
57	Carriage of material by mechanical transport from source to actual site of work for: Sand Avg lead 25 Km	Cum	94.15	451.97	42552.98
58	Carriage of material by mechanical transport from source to actual site of work for: Stone agg. 40mm Avg lead 25 Km	Cum	9.33	491.29	4583.74
59	Carriage of material by mechanical transport from source to actual site of work for: Stone agg. 20mm Avg lead 25 Km	Cum	141.87	451.97	64120.98
60	Carriage of material by mechanical transport from source to actual site of work for: Stone soling Avg lead 12 Km	Cum	23.81	358.98	8547.31
61	Carriage of material by mechanical transport from source to actual site of work for: Bricks Avg lead 75Km	No	6235.00	2.35	14652.25
	Total				5638340.00
	Above 3% on all itmes				169150.00
	Allotted Cost				5807490.00

Rates and quantities checked:



 Head Draughtsman



 Technical Officer



 Executive Engineer
 Jal Shakti PHE Division
 Sopore

B Terms and conditions:

1. Total amount of the work should in no case exceed beyond **Rs.5807490.00** (**Rs.Fifty eight Lacs Seven Thousand Four Hundred and Ninety only**) which includes all taxes, levies etc.
2. The work shall have to be completed by you within a period of **60 days** failing which the panality under rules shall be imposed upon you.
3. Performance security @ **3%** of allotted cost i.e **Rs.174224.00** in shape of CDR/BG/FDR shall have be deposited by you in this office within seven days from the date of issue of this allotment from this office failing which action shall be initiated as per SBD of the NIT.
4. An agreement shall have to be drawn by you with the department within a period of 07 days from the date of issuance of allotment, failure to executed such a formal deed shall not however prevent the contract from being enforced upon you. However payment on account of this work shall not be considered in absence of agreement.
5. The earnest money amounting to **Rs.113000/=** deposited by you in this office as a bid security against the contract vide CDR/FDR No: **3405641** dated : **12-05-2023** shall be considered for release once the performance security @ **3%** of allotted amount is deposited by you.
6. The allotted work shall have to be monitored by Third Party Monitoring Agency (WAPCOAS) appointed by the department.
7. All other terms and conditions shall remain same as laid down in E-NIT/ Standard bidding document/PWD from No 25 and GFR-2017.


Assistant Accounts
Officer


Technical officer


Executive Engineer
Jal Shakti PHE Division
Sopore

Copy to the:

- i) Chief Engineer Kashmir Jal Shakti PHE Department Srinagar for favour of information.
- ii) District Development Commissioner Baramulla (Chairperson DJJM) for favour of information.
- iii) Superintending Engineer Hydraulic Circle Baramulla/Bandipora (Member Secretary JJM) for favour of information.
- iv) Assistant Executive Engineer PHE Sub Division Sopore for information and necessary action.
- v) M/S WAPCOAS Ltd Corporate office 76-C intuitional area sector 18 Gurgon for information
- vi) Head Draftsman for information.
- vii) File Concerned.