

Mr. Bashir Ahmad Nalk,
Contractor,
S/o. Ghulam Ahmad Nalk,
R/o Zaglgam, Pulwama
Regd. No. 24/AAV/SE/HYDL/SHOPIAN/2004-05

Sub :- Retrofitting of Water Supply Scheme Kachipora by way of including renovation of old existing Impounding Reservoir, face lifting of structures, construction of head works by way of construction of intake channel/RCC Intake chamber including installation of 54 No. FHTCs for Kachipora (JJM).
Ref:- E-NIT S.No. 41/PHEP of 2020-21, job No. (3), Circulated vide this office No. PHEP/3169-83 Dated: 29-09-2020.

Advertised Amount of work: ₹ 66,40,000.00
Allotted Amount of work: ₹ 71,58,000.00
Rupees Seventy One Lakh(s) Fifty Eight Thousand Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following negotiated rates as accepted by you on the terms and conditions given as

Sl. No.	Description of work	No. or Qty.	Unit	RATE	
				Figures	Words
1.00	Providing and laying in position specified grade of reinforced cement concrete excl. the cost of centering, shuttering, finishing, & Reinforcement. All work up to plinth level (1:1.5:3) Raft (1 cement: 1 1/2 course sand: 3 grade stone agg. 20 mm nominal size)	38.84	Cum	7100.00	Rupees Seven Thousand One Hundred Only
2.00	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth & string courses, fillets, columns, pillars, piers abutments, post & struts etc up to floor five level excluding cost of centering, shuttering, finishing & reinforcement 1:1.5:3 (1 cement: 1 1/2 course sand: 3 graded crushed stone 20 mm nominal size)	25.80	Cum	8450.00	Rupees Eight Thousand Four Hundred Fifty Only
3.00	12 mm thick cement plaster in 1:4 mix floating coat of neat cement (1 cement, 4 fine sand)	430.70	Sqm	250.00	Rupees Two Hundred Fifty Only
4.00	Centering and shuttering including strutting, propping etc and removal of form for:-				
4.10	Foundation, footings, bases of columns etc. for mass concrete.	193.00	Sqm	230.00	Rupees Two Hundred Thirty Only
4.20	Wall (any thickness) including attached plasters, buttresses, plinth and string courses etc	155.58	Sqm	400.00	Rupees Four Hundred Only
4.30	Suspended floors, roofs, landings, balconies and access platform	85.52	Sqm	502.00	Rupees Five Hundred Two Only
5.00	Reinforcement for RCC works including Straightening cutting, bending, placing in position & binding all complete (Thermo Mechanically treated bars)	7937.00	Kg	95.00	Rupees Ninety Five Only
6.00	Structural steel work welded in built up section, trusses and framed work including cutting, hoisting, fixing in position and applying a primer coat of approved steel primer all complete	488.00	Kg	100.00	Rupees One Hundred Only
7.00	Earth work excavation by manual means in trenches for foundation drains, pipes cables etc (not exceeding 1.5 mtr in width and for shaft wells and the cesspits and the like not exceeding 10sqm on plan) depth up to 1.5 mtr including disposal of excavated soil up to 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil.	1763.07	Cum	320.00	Rupees Three Hundred Twenty Only
8.00	Providing and jaying of stone soling hand packed horizontally excluding cost of stones	18.90	Cum	441.00	Rupees Four Hundred Forty One Only
9.00	Reinforce cement concrete work in beams, suspended floors, roofs having slope upto 15 degree landings, balconies, shelves, chajjas, lintels, bands, plain window sills, stair cases, and spiral cases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:2:4 (1 cement, 2 coarse sand, 4 graded stone agg 20mm nominal size)	.91	Cum	6500.00	Rupees Six Thousand Five Hundred Only
10.00	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade on new works (two or more coats) over and including primary coat with cement primer.	57.50	Sqm	110.00	Rupees One Hundred Ten Only
11.00	Painting on G.S sheets with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade. New work (two or more coats) including a coat of approved steel primer but excluding a coat of mordant solution.	627.26	Sqm	105.00	Rupees One Hundred Five Only
12.00	Painting with synthetic enamel paint of approved brand and manufacture of give an even shade two or more coats on new work	58.81	Sqm	90.00	Rupees Ninety Only
13.00	Providing and laying in position cement concrete of specified grade excl. cost of centering & shuttering, all work up to plinth level 1:4:8 (1 cement: 4 fine sand: 8 grade stone agg.)	9.45	Cum	4200.00	Rupees Four Thousand Two Hundred Only
14.00	Providing and laying in position reinforced cement concrete of specified grade excl. cost of centering & shuttering finishing and reinforcement all work upto plinth level 1:2:4 (1 cement: 2 coarse sand: 4 graded stone agg. 40 mm nominal size)	22.58	Cum	5900.00	Rupees Five Thousand Nine Hundred Only
15.00	finishing walls with water proofing cement paint of required shade on new works (two or more coats) applied @ 3.84 Kg/10Sqm	519.21	Sqm	76.00	Rupees Seventy Six Only
16.00	Clearance of silt from Impounding Reservoir including disposal from premises all leads lifts complete job	3200.00	Cft	10.00	Rupees Ten Only
17.00	Centering and shuttering including strutting, propping etc and removal of form for:-				
17.10	Edges of slabs and breaks in floors and walls.	23.00	Mtr	220.00	Rupees Two Hundred Twenty Only
18.00	P/F of different dia of sluice valve/ gate valve/ bend/ collars with fittings of standard make (Kiroskar or VAGE) including all carriages upto site of work complete including tail pieces			18000.00	Rupees Eighteen Thousand Only
18.10	150mm dia sluice valve	2.00	No	12000.00	Rupees Twelve Thousand Only
18.20	100mm dia sluice valve	2.00	No		
19.00	Dismantling of G.I. pipes (external work) including excavation and refilling, trenches, after taking out the pipes, manually by mechanical means including stacking of pipes within 50 mtrs.			80.00	Rupees Eighty Only
19.10	Above 40mm dia bore	500.00	Mtr		
20.00	L/F of G.I. pipes excluding cost of ppe and earth work but including handling complete.			65.00	Rupees Sixty Five Only
20.10	40mm dia CI pipes	500.00	Mtr		

Sub :- *Retrofitting of Water Supply Scheme Kachipora by way of including renovation of old existing Impounding Reservoir, face lifting of structures, construction of head works by way of construction of intake channel/RCC Intake chamber including installation of 54 No. FHTCs for Kachipora (JJM).*

	P/F of flanged pipe with flanged joints 12mm thick of flanges including cost of nuts, bolts, washers, cutting of threads and making good for jointing including testing and commissioning all cartages complete.				
22.10	150mm dia flanged pipe	62.00	Mtr	1721.00	Rupees One Thousand Seven Hundred Twenty One Only
22.20	100mm dia flanged pipes	1000.00	Mtr	1220.00	Rupees One Thousand Two Hundred Twenty Only
22.30	80mm dia flanged pipes	1000.00	Mtr	880.00	Rupees Eight Hundred Fifty Only
22.40	65mm dia flanged pipe	337.00	Mtr	640.00	Rupees Six Hundred Forty Only
23.00	Applying priming coat with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	627.28	Sqm	37.53	Rupees Thirty Seven And Paise Fifty Three Only
24.00	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing & staircase railing and similar work including applying a priming coat of approved steel primer (40mm dia GI pipes nominal bore class (b))	341.00	Kg	110.00	Rupees One Hundred Ten Only
25.00	Reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete (TMT) Cold twisted bars.	597.00	Kg	100.00	Rupees One Hundred Only
26.00	Extra for providing and mixing of water proofing material in cement conc work in doses by weight of cement as per manufacturer specification	316.00	Kg	59.00	Rupees Fifty Nine Only
27.00	Providing, laying and fitting of GI pipes including all cartages head load upto site of work complete.				
27.10	50mm dia	600.00	Mtr	460.00	Rupees Four Hundred Sixty Only
27.20	40mm dia	1000.00	Mtr	370.00	Rupees Three Hundred Seventy Only
27.30	25mm dia	1500.00	Mtr	249.00	Rupees Two Hundred Forty Nine Only
27.40	20mm dia	2000.00	Mtr	180.00	Rupees One Hundred Eighty Only
27.50	15mm dia	1000.00	Mtr	140.00	Rupees One Hundred Forty Only
28.00	Filling available excavated earth (excld Rock) in trenches, plinth sides of the foundation etc layers not exceeding in 20 cm in depth, consolidating each deposited layer by ramming and watering lead up to 50 Mtr and lift up to 1.50 Mtr.	1495.03	Cum	190.00	Rupees One Hundred Ninety Only
29.00	Making connections of G.I. distribution branch with G.I. mains of following sizes by providing and fixing tee including cutting and threading the pipe etc complete.				
29.10	25mm to 40mm nominal bore	70.00	No	650.00	Rupees Five Hundred Fifty Only
29.20	above 40mm nominal bore	20.00	No	1100.00	Rupees One Thousand One Hundred Only
30.00	P/F of Sign board of 8'x4' of size to be fitted with angle iron frame with cement concrete complete job.	1.00	No	15000.00	Rupees Fifteen Thousand Only
31.00	P/F of MS Bends as required including cost of welding fixing all cartage complete				
31.10	150mm dia MS bend	4.00	No	3500.00	Rupees Three Thousand Five Hundred Only
32.00	Carriage of different materials from source upto site of work by mechanical transport including cost of loading, unloading and stacking complete.				
32.10	Stone Solling (avg lead 20 Kms)	18.00	Cum	386.00	Rupees Three Hundred Eighty Six Only
32.20	Sand + Bajri (avg lead 45 Kms)	138.58	Cum	480.00	Rupees Four Hundred Eighty Only
32.30	Cement and steel (avg lead 30 Kms)	45.31	M.T.	360.00	Rupees Three Hundred Sixty Only
33.00	Maintenance cost for a period of three years which includes 12 months DLP	1.00	complete job	98000.00	Rupees Ninety Eight Thousand Only

Terms and Conditions:-

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However, non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (60) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- Earnest Money of ₹ 133000/- deposited by your vide CDR No. 381128 dated 15-10-2020 has been retained in the divisional office as security deposit.
- 5- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked

Head Draftsman

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for information
- 2- District Development Commissioner Pulwama for information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Pulwama for information and necessary action.
- 4- File Concerned.

Tech. Officer

Executive Engineer,
JSD (PHE) Div. Pulwama