GOVE.

1.01

Above 40 mm nominal board.

AMMU AND KASHMIR

OFFICE OF THE EXECUTIVE ENGINGER FEROZPORA BASIN IRRIGATION DIVISION TANGMARGE E NO.01954-254611) (EMAIL ADDRESS:FBIDIVISIONTANGMARGGEMAIL.COM)

	Allotment No. 3	4-PHE	Dated	1:- 10/2022	<u>) </u>			
M/S:- ALI	MOHAMMAD GANIE			NO/ 6	100-94			
S/0:- G H. H	IASSAN GANIE			DATED:-	2//0/2022			
R/O :- AGR	LIKALAN PATTAN	GST. NO	:- 01 A JC	P62817J1Z	Q			
REGD. NO:	-KMR/CE/I&FCD/8-AAY/2001-02							
TENDER ID:	2022_PHE_171028_1				4/			
ADV. COS	T RS:-141.56 HEING KETCHMATIPORA BY WAY OF L	1		COST RS:-14				
SUBJECT:-	SUPPLY MAIN, SUB MAIN & DISTRIBUT CONSTRUCTION OF ANCHOR BLOCKS/S 1. Your tender received in response to 27.05.2022 issued under No.FBID/CC FDR NO:- 248571 DT:12-05-2022	this offi	ce enit N	t spots uni	DER JJM			
Reference	02. DJJM /District Development Commissioner Baramulla Authorization No:DDCB/JJM/2022-23/1725-28 Dated: 04.06.2022							
,	03. Superintending Engineer Hyd.Circle Sopore's Authorization Letter No.SE/Hyd/DB/4758-70 Dated:-28-07-2022							
	04. This office Letter of intent No/FBID/DB/3453-66 Dated:-30-07-2022							
	For & on behalf of Lt. Governor of J&K (with you on the following			bove noted wo	rk is hereby fixe			
SI.No	Description of Work / Item(s)	Qty	Units	Estimated Rate	Amount			
1	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/by mechanical means including stacking of pipes within 50 meters lead as per direction of Engineer-in-charge: 15mm - 40 mm nominal board.	3000	RM	99.65	298950			

3000

RM

(DV

110.65

331950

-					
2	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed: All kinds of soils	8193.2	cum	436	3572235.2
2.01	Ordinary rock	2057.55	cum	967.85	1991399.768
3	Laying in position centrifugally cast (spun) iron S&S or flanged pipes (excluding cost of pipe) 100 mm dia DI to 300 mm dia DI	3555	QtI	245.55	872930.25
4	Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes or Ductile Iron Pipes including testing of joints and including the cost of rubber gasket 250 mm dia DI	545	Joint	259.9	141645.5
4.01	200 mm dia DI	273	Joint	213	58149
4.02	150 mm dia DI	782	Joint	144.7	
4.03	125 mm dia DI	364	Joint	144.7	113155.4
4.04	100 mm dia DI	636	Joint		52670.8
5	Laying and fitting of G.I. pipes (all classes) complete incluidng cost of pipe specials but excluding cost of pipes/ Earth work 50 mm dia GI		RM	73.05	57049.2 221341.5
5.01	65 mm dia GI	1350	RM	73.05	
5.02	50 mm dia GI	1002	RM		98617.5
5.03	40 mm dia GI	4600		40.8	40881.6
5.04	25 mm dia GI	1/2:00(#0.#W	RM	40.8	187680
5.05	20 mm dia GI	5000	RM	30.65	153250
5.06	15 mm dia GI	5400	RM	20.25	109350
		5000	RM	20.25	101250

6

In Land

6	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete 25 mm – 40 mm	100	NO	666.25	66625
6.01	50 mm – 80 mm	50	NO.	1268.75	63437.5
7	Providing and fixing of MS Flanged joints (12mm Thick) to double flanged CI/DI pipes Incl. cutting of pipes welding charges cutting of flanged rubber gaskets bolts nuts including testing of joint and sort of carriages. Complete Job 100 mm dia GI	100	Joint	1520	152000
7.01	80 mm dia Gl	100	Joint	1100	110000
7.02	65 mm dia GI	40	joint	1000	40000
7.03	50 mm dia GI	40	Joint	800	32000
8	Welding charges of leakage spots/ sockets/ tees/ bends for Gi pipes including carriage of welding machine and DG Set upto site of work including steel strips complete job including earth work in excavation and refilling of trenches complete job.	250	job	500	125000
9	Providing and fixing of MS Bends fittings viz bends of suitable degree, tees collars etc to be fabricated from 6mm nominal size MS plate as per the requirement of site with anti corrosive red oxide primer complete job	650	Kg's	147.82	96083
10	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	9159.98	Cum	198.7	1820088.026
11	Providing fixing of approved brand ISI mark gun matel regulating values including all carriages upto working site complete 100mm Dia Gate Value		NO.	8000	32000

6

hund

ALC: U				_	
1.01	80mm Dia Gate Value	3	NO	2406.65	7219.95
11 02	65mm Dia Gate Value	3	NO.	1568.85	4706.55
11.03	50mm Dia Gate Value	4	NO.	942.75	3771
11.04	40mm Dia Gate Value	5	NO.	704.7	3523.5
11.05	25mm Dia Gate value	4	NO.	543.85	2175.4
11.06	20mm Dia Gate Value	4	NO.	463.66	1854.64
11.07	15mm Dia Gate Value	5	NO.	450	2250
12	P/F of ISI mark of approved double flanged sluice vlaue incld tail pieces incl. carriages upto site of work: 250 mm Sluice Value	4	NO.	50356	201424
12.01	200 mm Sluice Value	5	NO.	31698	158490
12 02	150mm Sluice Value	3	NO.	20243	60729
12.03	125mm Sluice Value	3	NO.	15961	47883
12.04	100mm Sluice Value	4	NO.	13164	52656
13	Construction of surface boxes for regulative values incld. Earth work concreting Angle iron frame and MS TOP Lid incd. All carilages. (as per requirement at site)	23	NO.	7000	161000
14	Providing and laying hand packed stone soiling 50 mm nominal size including filling spreading dressing ramming all leads lifts including all carriages complete job	12	Cum	1320	15840
15	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering All work upto plinth level with: 1.4.8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size)	8	cum	4861.84	38894.72

a

mush

ALC: NO.					
16	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring and shuttering. All work upto plinth level with 1:2:4 mix (1 cement : 2 coarse sand 4 graded stone aggregate 20 mm nominal size)	52	cum	6465.2	336190.4
17	Centering and shuttering including strutting, propping etc. and removal of form for Foundation/footings	324	Sqm	262.3	84985.2
18	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level	4455	Kg's	91.13	405984.15
19	12mm Cement plaster finished with a floating coat of neat cement of mix: 1:4 mix	135	Sqm	260.05	35106.75
20	P/F of nuts and bolts of differnent sizes	200	Kg's	92.85	18570
21	Road cut incl. cutting of black to surface with harrd crest (Soilng/WBM Surface and relaying of hard crest material and alaying of concrete rich mix instead of macdum/semidence incl. removal of unservicable material within lead of 100mtrs	2000	Mtr	500	1000000
22	Carriage of all materials from road site to actual site of work by mechanical transport Sand (Avg. 50 kms Lead)	29	Cum	700.373	20310.817
22.01	Stone aggregate 20 mm (Avg. lead 10 Kms)	47.8	Cum	280.853	13424.773
22.02	Stone aggregate 40 mm (Avg. lead 10 Kms)	7.2	Cum	305.279	2198.009
22.03	Cement/steel (20 kms)	19	MT	445.9585	8473.212
22.04	250 mm dia DI pipes 10 km	3000	RM	17.365	52095
22.05	200 mm dia DI pipes. 10 km	1500	RM	16.6405	24960.75
22.06	150 mm dia DI pipes. 10 km	4300	RM	10.2235	43961.05

				G.Total	14439620.00
	Alloted Rates @ 2% Above or	all items			2831298.
			Total		14156490.22
23.09	GI pipes	85.55	MT	355.695	30429.707
23.08	100 mm dia DI pipes	3500	RM	9.6025	33608.75
23.07	125 mm dia DI pipes	2000	RM	11.753	23506
23.06	150 mm dia DI pipes.	4300	RM	13.5355	58202.65
23.05	200 mm dia DI pipes	1500	RM	20.3205	30480.75
23.04	250 mm dia DI pipes	3000	RM	35.719	107157
23.03	Cement	15	MT	282.095	4231.425
23.02	Steel	4	MT	605.958	2423.832
23.01	Stone aggregate 40 mm	72	Cum	671.554	4835.189
23	Carriage of all materials from road site to actual site of work by head Load of all materials (500 M avg lead). Sand & Stone aggregate	76.8	Cum	621.207	47708.698
22.09	GI pipes 20 km	85.55	мт	249.6535	21357.857
E.	100 mm dia DI pipes 10 Km	3500	RM	6.1295	21453.25

Rates & Qty Checked

(Just

Technical Officer

Executive Engineer
akti EBI Division Tangma

Terms & Conditions

1	The cost of work should in no case exceed beyond alloted cost	

	Suance of LOI/ allotment and the date of start shall be reckoned 07 days from the date of An Agreement shall baye, to be seen as earlier
3	seven days from the date of issuance of allotment. However, failure to execute such a formal deed, shall not prevent, the contract from being enforced, upon your
	Performance security equivalent to 03% of the value of contract shall have to be deposited by you in the shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order and valid for a period of 03 months beyond the expiry S B D)/e-NIT
ς.	The allotted work shall be subjected to check by the third party monitoring agency appointed by the department.
t	Pre, during and post execution Geo-tagged photographic evidence have to be produced at the time of submission of the bill.
7	All other conditions shall be applicable as laid down in S.B.D and PWD form
8	Any rules/terms and condition if not stipulated in the S.B.D., shall be strictly dealt in accordance with the relevant rules / guidelines stipulated in G.F.R- 2017 and manual for procurement of works 2019 G.O.I.

Copy to the

212

- Chief Engineer Kmr PHE Department Srinager for favour of information please.
- District Dev Commissioner Baramulla (Chairperson DJJM) for favour of information please.
- 3 Superintending Engineer Hyd. Circle Sopore for favour of information.
- Assistant Executive Engineer PHE Sub –Division Tangmarg for information & necessary action. He will ensure the completion of work within the stipulated time period and strictly in accordance with approved proposals, besides the amount of work should not exceed beyond the provision of allotment in any case for which he shall be personally responsible.
- 5 Technical Officer Divisional Office for information.
- 6 Asstt. Accounts Officer for information .
- 7 File Concerned for records

Technical Officer

Executive Engineer
FBI Division Tangparg