

OFFICE OF THE EXECUTIVE ENGINEER, JSD (PHE) DIVISION, PULWAMA

No. PHEP/ 4284-87
Dated. 13-11-2020

Mr. Bashir Ahmad Naik,
Contractor,
S/o. Ghulam Ahmad Naik,
R/o Zagigam, Pulwama
Regd. No. 24/AAY/SE/HYDL/SHOPIAN/2004-05

Sub :- Retrofitting of Water Supply Scheme Nikas Arbal by way of providing, laying and fitting of GI pipes, including construction of spring protection work, providing structural steel mesh over spring, and face lifting of structures including installation of 91 No. FHTCs for Nikas Arbal (JJM).

Ref:- E-NIT S.No. 43/PHEP of 2020-21, job No. (2), Circulated vide this office No. PHEP/3316-29 Dated: 03-10-2020.

Advertised Amount of work: ₹ 28,48,000.00

Allotted Amount of work: ₹ 30,79,000.00

Rupees Thirty Lakh(s) Seventy Nine Thousand Only

For and on behalf of the Lt. Governor Union Territory of J&K, the contract for the above noted work is hereby fixed with you at the following negotiated rates as accepted by you on the terms and conditions given as under:-

Sl. No.	Description of work	No. or Qty.	Unit	RATE	
				Figures	Words
1.00	Earth work excavation by manual means in trenches for foundation drains, pipes cables etc (not exceeding 1.5 mtr in width and for shaft wells and the cesspits and the like not exceeding 10sqm on plan) depth up to 1.5 mtr including disposal of excavated soil up to 1 mtr from cutting edge disposed earth to be levelled and neatly dressed in all kinds of soil.	922.46	Cum	290.00	Rupees Two Hundred Ninety Only
2.00	Providing and laying of stone soling hand packed horizontally excluding cost of stones	4.99	Cum	441.00	Rupees Four Hundred Forty One Only
3.00	Desilting of silt from spring including disposal within the premises and dewatering etc complete	2367.78	Cft	11.00	Rupees Eleven Only
4.00	P/F of flanged pipe with flanged joints 12mm thck of flanges including cost of nuts, bolts, washers, cutting of threads and making good for jointing including testing and commissioning all carriages complete.				
4.10	100mm dia GI pipe with flanges	1000.00	Mtr	1050.00	Rupees One Thousand Fifty Only
4.20	80mm dia GI pipe with flanges	200.00	Mtr	800.00	Rupees Eight Hundred Only
5.00	Providing, laying and fitting of GI pipes including all carriages head load upto site of work complete.				
5.10	50mm dia	300.00	Mtr	450.00	Rupees Four Hundred Fifty Only
5.20	40mm dia	300.00	Mtr	360.00	Rupees Three Hundred Sixty Only
5.30	25mm dia	400.00	Mtr	235.00	Rupees Two Hundred Thirty Five
5.40	20mm dia	500.00	Mtr	165.00	Rupees One Hundred Sixty Five Only
5.50	15mm dia	4000.00	Mtr	125.00	Rupees One Hundred Twenty Five
6.00	Making connections of G.I. distribution branch with G.I. mains of following sizes by providing and fixing tee including cutting and threading the pipe etc complete.				
6.10	25mm to 40mm nominal bore	91.00	No	550.00	Rupees Five Hundred Fifty Only
6.20	above 40mm nominal bore	20.00	No	1200.00	Rupees One Thousand Two Hundred
7.00	Filling available excavated earth (excl'd Rock) in trenches, plinth sides of the foundation etc layers not exceeding in 20 cm in depth, consolidating each deposited layer by ramming and watering lead up to 50 Mtr and lift up to 1.50 Mtr.	816.65	Cum	150.00	Rupees One Hundred Fifty Only
8.00	Applying priming coat with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	627.26	Sqm	37.53	Rupees Thirty Seven And Paise Fifty Three Only
9.00	Finishing walls with water proofing cement paint of required shade old work (one or more coats) applied @ 2.20 kg/10 Sqm over priming coat of primer applied @ 0.80 liters/10 Sqm complete including cost of priming coat	519.21	Sqm	71.55	Rupees Seventy One And Paise Fifty Five Only
10.00	P/F of Sign board of 8'x4' of size to be fitted with angle iron frame with cement concrete complete job.	1.00	No	10000.00	Rupees Ten Thousand Only
11.00	P/F of different dia of sluice valve/ gate valve/ bend/ collars with fittings of standard make (Kirtoskar or VAGE) including all carriages upto site of work complete including tail pieces				
11.10	100mm di sluice valve	2.00	No	12000.00	Rupees Twelve Thousand Only
12.00	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade on new works (two or more coats) over and including primary coat with cement primer.	57.50	Sqm	115.00	Rupees One Hundred Fifteen Only
13.00	Painting on G.S sheets with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade. New work (two or more coats) including a coat of approved steel primer but excluding a coat of mordant solution.	627.26	Sqm	108.00	Rupees One Hundred Eight Only
14.00	Painting with synthetic enamel paint of approved brand and manufacture of give an even shade two or more coats on new work	58.61	Sqm	97.00	Rupees Ninety Seven Only
15.00	12 mm thick cement plaster of mix 1:4	73.72	Sqm	251.00	Rupees Two Hundred Fifty One Only
16.00	Centering and shuttering including shuttering, propping etc and removal of form work for:-				
16.10	Foundation, footings, bases of columns for mass concrete.	73.72	Sqm	260.00	Rupees Two Hundred Sixty Only
17.00	Structural steel work welded in built up section, trusses and framed work including cutting, hoisting, fixing in position and applying a primer coat of approved steel primer all complete	756.61	Kg	109.00	Rupees One Hundred Nine Only
18.00	Providing and laying in position cement concrete of specified grade excl. cost of centering & shuttering, all work up to plinth level 1:4:8 (1 cement 4 fine coarse 8 grade stone agg. 40 mm nominal size crushed	4.99	Cum	4250.00	Rupees Four Thousand Two Hundred Fifty Only

Sub :- **Retrofitting of Water Supply Scheme Nikas Arbal by way of providing, laying and fitting of GI pipes, including construction of spring protection work, providing structural steel mesh over spring, and face lifting of structures including installation of 91 No. FHTCs for Nikas Arbal (JJM).**

17.00	Structural steel work welded in built up section, trusses and framed work including cutting, hoisting, fixing in position and applying a primer coat of approved steel primer all complete	758.81	Kg	109.00	Rupees One Hundred Nine Only
18.00	Providing and laying in position cement concrete of specified grade excl. cost of centering & shuttering, all work up to plinth level 1:4:8 (1 cement: 4 fine coarse 8 grade stone agg. 40 mm nominal size crushed	4.99	Cum	4250.00	Rupees Four Thousand Two Hundred Fifty Only
19.00	Providing and laying in position cement concrete of specified grade excl. cost of centering & shuttering, all work up to plinth level 1:2:4 (1 cement: 2 coarse sand: 4 grade stone agg. 20 mm nominal size crushed	18.75	Cum	6300.00	Rupees Six Thousand Three Hundred Only
20.00	Providing and fixing of steel mesh 2"x2"x4mm fixed with nuts, bolts washers all carriage complete	130.00	Sqm	200.00	Rupees Two Hundred Only
21.00	Carriage of different materials from source upto actual site of work by mechanical transport including cost of loading, unloading and stacking complete.				
21.10	Stone Solling (avg lead 10 Kms)	4.99	Cum	275.00	Rupees Two Hundred Seventy Five Only
21.20	Sand + Bajri (avg lead 10 Kms)	30.51	Cum	230.00	Rupees Two Hundred Thirty Only
21.30	Cement + steel (avg lead 10 Kms)	7.55	M.T.	205.00	Rupees Two Hundred Five Only

Terms and Conditions:-

- 1- This letter of acceptance and the tender of the contractor/subsequent negotiations will constitute a legal contract document and the conditions laid down in the detailed E-NIT and agreement form No. 25 – double will hold good even before the drawl of an agreement with the department.
- 2- You have to attend the Divisional office along with your enlistment card for drawl of an agreement within a weeks time positively from the date of issuance of allotment. However, non drawl of agreement will not prevent the contract from being enforced upon you.
- 3- That the works is required to be completed within (30) days and the date of start shall be reckoned after seven days from the date of issue of this allotment letter.
- 4- Earnest Money of ₹ 57000/- deposited by your vide CDR No. 593500 dated 13-10-2020 has been retained in the divisional office as security deposit.
- 5- All other terms and conditions will remain same as per the original agreement form No. 25–double, Form FC – 33 and detailed E-NIT.

Checked

Head Draftsman

Copy to the:-

- 1- Superintending Engineer, Hydraulic Circle, Shopian, for information
- 2- District Development Commissioner Pulwama for information.
- 3- Assistant Executive Engineer, PHE Sub-Div., Pulwama for information and necessary action.
- 4- File Concerned.

Tech. Officer

Executive Engineer,
USD (PHE) Div. Pulwama